

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM	= 1	CLIENT# = 1	Land Item	SCHEDULE:	1	100				
Description =	CONSTRUCTION SURVEYING		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
001.01	CONSTRUCTION SURVEYING		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4SURV	Surveying sub	1.00	1.00 LS	700,000.000				700,000		700,000
BID ITEM	= 2	CLIENT# = 2	Land Item	SCHEDULE:	1	100				
Description =	CONTRACTOR QUALITY PROGRAM PLAN (CQPP)		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
002.01	QCPP PLAN DEVELOPMENT		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3QCPP	QCPP PLAN	1.00	1.00 LS	10,000.000			10,000			10,000
002.02	QC MANAGER		Quan:	300.00 SHIF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3QCMAN	QC MANAGER	1.00	2,368.00 HR	142.500			337,440			337,440
002.03	QC INSPECTORS		Quan:	2,160.00 SHIF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3QCINS	QC INSPECTORS	1.00	13,440.00 HR	95.000			1,276,800			1,276,800
3QCINSOT	QC INSPECTOR OVERTI	1.00	1,344.00 HR	142.500			191,520			191,520
\$1,468,320.00				[]			1,468,320			1,468,320
002.04	TESTING		Quan:	1,000.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3QCTESTING	QC TESTING	1.00	1,000.00 EA	1.000			1,000			1,000
3QCTESTLAB	QC TESTING LAB	1.00	1.00 LS	25,000.000			25,000			25,000
\$26,000.00				[]			26,000			26,000
002.05	QC REPORTS		Quan:	600.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3QCREPORTS	QC REPORTS	1.00	600.00 EA	30.000			18,000			18,000
002.06	PE REVIEW		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3QCREVIEW	QC REVIEW	1.00	1.00 LS	66,000.000			66,000			66,000
002.07	QC TRAILER		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3QCTRAILER	QC TRAILER	1.00	1.00 LS	15,000.000			15,000			15,000
====>	Item Totals:	2	- CONTRACTOR QUALITY PROGRAM PLAN (CQPP)							
\$1,940,760.00				[]			1,940,760			1,940,760
1,940,760.000		1 LS					1,940,760.00			1,940,760.00
BID ITEM	= 3	CLIENT# = 3	Land Item	SCHEDULE:	1	100				
Description =	VIBRATION MONITORING		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
003.01	VIBRATION MONITORING		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3VIBMON	VIBRATION MONITORIN	1.00	1.00 LS	15,000.000			15,000			15,000
====>	Item Totals:	3	- VIBRATION MONITORING							
\$15,000.00				[]			15,000			15,000

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 3	CLIENT# = 3									
Description =	VIBRATION MONITORING		Land Item Unit =	SCHEDULE: 1	100					
15,000.000	1 LS			LS	Takeoff Quan:	1.000		Engr Quan:		1.000
						15,000.00				15,000.00
BID ITEM = 4	CLIENT# = 4									
Description =	NOISE MITIGATION PLAN		Land Item Unit =	SCHEDULE: 1	100					
				LS	Takeoff Quan:	1.000		Engr Quan:		1.000
004.01	NOISE MITIGATION PLAN		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3NMP	NOISE MITIGATION PLA	1.00	1.00 LS	2,500.000		2,500				2,500
004.02	NOISE VARIANCE PERMITS		Quan:	80.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3NVP	NOISE VARIANCE PERM	1.00	50.00 EA	231.000		11,550				11,550
====>	Item Totals:	4	- NOISE MITIGATION PLAN							
\$14,050.00				[]		14,050				14,050
14,050.000	1 LS					14,050.00				14,050.00
BID ITEM = 5	CLIENT# = 5									
Description =	CRITICAL PATH SCHEDULE UPDATE, MIN. BID		Land Item Unit =	SCHEDULE: 1	100					
				EA	Takeoff Quan:	28.000		Engr Quan:		28.000
005.05	CRITICAL PATH SCHEDULE UPDATE, MIN. BID		Quan:	28.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3CPM	CPM SCHEDULE UPDAT	1.00	28.00 EA	2,500.000		70,000				70,000
====>	Item Totals:	5	- CRITICAL PATH SCHEDULE UPDATE, MIN. BID							
\$70,000.00				[]		70,000				70,000
2,500.000	28 EA					2,500.00				2,500.00
BID ITEM = 6	CLIENT# = 6									
Description =	MOBILIZATION-SCHEDULE 1		Land Item Unit =	SCHEDULE: 1	100					
				LS	Takeoff Quan:	1.000		Engr Quan:		1.000
006.01	SITE SET UP		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
EAS	Earthwork 4 Man Crew		80.00 CH	Prod:	80.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	80.00 HR	51.051			4,084		4,084	
8EX100	100 Excavator	1.00	80.00 HR	52.300			4,184		4,184	
FOCI	Civil Forman	1.00	80.00 MH	77.060	8,052				8,052	
LAG	General Laborer	2.00	160.00 MH	52.910	11,162				11,162	
OPE	Operator - Excavator	1.00	80.00 MH	74.560	7,796				7,796	
\$35,277.52	320.0000 MH/LS		320.00 MH	[22654.72]	27,009		8,268		35,278	
006.02	MOBILIZE EQUIPMENT		Quan:	40.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3EQMOB	MOBILIZE EQUIPMENT	1.00	52.00 EA	2,500.000		130,000				130,000
006.03	SUB MOBILIZATION		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS	1,797,000.000				1,797,000	1,797,000	
4LAND	Landscape sub	1.00	1.00 LS	20,000.000				20,000	20,000	
\$1,817,000.00				[]				1,817,000	1,817,000	

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM	= 6	CLIENT# = 6		Land Item	SCHEDULE: 1	100				
Description =	MOBILIZATION-SCHEDULE 1		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
006.04	PUNCH LIST		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		160.00 CH	Prod:	160.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	160.00 HR	51.051				8,168		8,168
8EX100	100 Excavator	1.00	160.00 HR	52.300				8,368		8,368
FOCI	Civil Forman	1.00	160.00 MH	77.060	16,104					16,104
LAG	General Laborer	2.00	320.00 MH	52.910	22,323					22,323
OPE	Operator - Excavator	1.00	160.00 MH	74.560	15,592					15,592
\$70,555.05	640.0000 MH/LS		640.00 MH	[45309.44]	54,019			16,536		70,555
006.05	CIVIL SUPERINTENDENTS		Quan:	1,120.00	SHIF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
ZSUP	==> Superintendent	1.00	8,960.00 MH	72.000	827,406					827,406
\$827,405.82	8.0000 MH/SHIF		8,960.00 MH	[576]	827,406					827,406
006.06	CONCRETE SUPERINTENDENTS		Quan:	1,120.00	SHIF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
ZSUP	==> Superintendent	1.00	8,960.00 MH	72.000	827,406					827,406
\$827,405.82	8.0000 MH/SHIF		8,960.00 MH	[576]	827,406					827,406
006.08	ELECTRICAL SUB BOND		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS	223,822.000				223,822		223,822
006.09	VACTOR TRUCKS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3VAC	VACTOR TRUCKS	1.00	1.00 LS	200,000.000			200,000			200,000
006.10	MINI EX		Quan:	560.00 DAY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
8EX035	==> 35 Excavator	1.00	4,480.00 HR	28.830				129,158		129,158
006.11	WATERTRUCK		Quan:	280.00 SHIF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
8TRW	==> Water Truck	1.00	1,400.00 HR	70.000				98,000		98,000
006.12	MISSILANIOUS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3ECOPAN	ECO PANS	1.00	1.00 LS	48,000.000			48,000			48,000
3LIGHTPLANT	LIGHT PLANTS	1.00	1.00 LS	24,000.000			24,000			24,000
3PEDACSESS	PED ACSESS RAMPS	1.00	1.00 LS	90,000.000			90,000			90,000
3WATERMETER	WATER METER FEES	1.00	1.00 LS	30,000.000			30,000			30,000
\$192,000.00				[]			192,000			192,000
006.13	OFFICE AND LAYDOWN		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3FENCE	TEMP FENCE	1.00	1.00 LS	15,000.000			15,000			15,000
3LAYDOWN	LAYDOWN YARD	1.00	1.00 LS	168,000.000			168,000			168,000
3PROFFIC	PROJECT OFFICE	1.00	1.00 LS	200,000.000			200,000			200,000
\$383,000.00				[]			383,000			383,000
006.14	ATTORNEY FEES		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3ATTORNEY	ATTORNEY COST	1.00	1.00 LS	100,000.000			100,000			100,000
006.15	CLEAN UP CREW		Quan:	112.00 SHIF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZZZZ</u>	CLEAN UP CREW		896.00 CH	Prod:	896.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	1.00	

Activity	Desc	Quantity	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
BID ITEM	= 6	CLIENT# = 6	Land Item	SCHEDULE: 1	100					
Description =	MOBILIZATION-SCHEDULE 1		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
8LO950	950 Loader	1.00	896.00 HR	81.500				73,024		73,024
LAG	General Laborer	1.00	896.00 MH	52.910	62,505					62,505
OPL	Operator - Loader	1.00	896.00 MH	74.560	87,315					87,315
\$222,844.45	16.0000 MH/SHIF		1,792.00 MH	[1121.736]	149,820			73,024		222,844
====>	Item Totals:	6	- MOBILIZATION-SCHEDULE 1							
\$5,256,469.06	20,672.0000 MH/LS		20,672.00 MH	[1483838.6]	1,885,660		1,005,000	324,987	2,040,822	5,256,469
5,256,469.060	1 LS				1,885,660.42		1,005,000.00	324,986.64	2,040,822.00	5,256,469.06

[illegible][illegible]

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 9 CLIENT# = 9 Land Item SCHEDULE: 1 100
Description = PORTABLE CHANGEABLE MESSAGE SIGN Unit = WK Takeoff Quan: 52.000 Engr Quan: 52.000

009.01 PORTABLE CHANGEABLE MESSAGE SIGN Quan: 52.00 WK Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

3VMS	MESSAGE SIGN	1.00	52.00 WK	450.000			23,400			23,400
------	--------------	------	----------	---------	--	--	--------	--	--	--------

====> **Item Totals: 9 - PORTABLE CHANGEABLE MESSAGE SIGN**
\$23,400.00 [] 23,400 **23,400**
450.000 52 WK 450.00 450.00

BID ITEM = 10 CLIENT# = 10 Land Item SCHEDULE: 1 100
Description = TEMPORARY BUSINESS, PUBLIC ACCESS AND PR Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

010.01 TEMPORARY BUSINESS, PUBLIC ACCESS AND P Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

3TBPA PR	TEMP BUISNES ACCESS	1.00	1.00 LS	5,000.000			5,000			5,000
----------	---------------------	------	---------	-----------	--	--	-------	--	--	-------

====> **Item Totals: 10 - TEMPORARY BUSINESS, PUBLIC ACCESS AND PR**
\$5,000.00 [] 5,000 **5,000**
5,000.000 1 LS 5,000.00 5,000.00

BID ITEM = 11 CLIENT# = 11 Land Item SCHEDULE: 1 100
Description = ENGINEER DIRECTED TEMPORARY BUSINESS AND Unit = FA Takeoff Quan: 100,000.000 Engr Quan: 100,000.000

011.01 ENGINEER DIRECTED TEMPORARY BUSINESS Quan: 100,000.00 FA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

9FORCE	FORCE ACCOUNT	1.00	100,000.00 FA	0.890			89,000			89,000
--------	---------------	------	---------------	-------	--	--	--------	--	--	--------

====> **Item Totals: 11 - ENGINEER DIRECTED TEMPORARY BUSINESS AND**
\$89,000.00 [] 89,000 **89,000**
0.890 100000 FA 0.89 0.89

BID ITEM = 12 CLIENT# = 12 Land Item SCHEDULE: 1 100
Description = CLEARING & GRUBBING Unit = SF Takeoff Quan: 29,939.000 Engr Quan: 29,939.000

012.01 CLEARING & GRUBBING Quan: 29,939.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

EAS	Earthwork 4 Man Crew	54.00	CH	Prod: 54.0000 CH	Lab Pcs: 4.00	Eqp Pcs: 2.00			
3DEDU02S	SOD DISPOSAL	1.00	667.00 TCY	28.000	18,676				18,676
8BA310A	418 Backhoe W/Attachme	1.00	54.00 HR	51.051		2,757			2,757
8EX100	100 Excavator	1.00	54.00 HR	52.300		2,824			2,824
FOCI	Civil Forman	1.00	54.00 MH	77.060	5,435				5,435
LAG	General Laborer	2.00	108.00 MH	52.910	7,534				7,534
OPE	Operator - Excavator	1.00	54.00 MH	74.560	5,262				5,262
\$42,488.32	0.0072 MH/SF		216.00 MH	[0.511]	18,231	18,676	5,581		42,488

====> **Item Totals: 12 - CLEARING & GRUBBING**
\$42,488.32 0.0072 MH/SF 216.00 MH [0.511] 18,231 18,676 5,581 **42,488**
1.419 29939 SF 0.61 0.62 0.19 1.42

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----	------------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 13 CLIENT# = 13 Land Item SCHEDULE: 1 100
Description = REMOVE CEMENT CONCRETE SIDEWALK Unit = SY Takeoff Quan: 19,570.000 Engr Quan: 19,570.000

013.01 REMOVE CEMENT CONCRETE SIDEWALK Quan: 19,570.00 SY Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>EA3</u>	EARTHWORK 3 MAN CREW		900.00	CH	Prod: 900.0000	CH	Lab Pcs: 3.00	Eqp Pcs: 2.00		
3DEDU02C	Concrete Trucking and Du	1.00	4,133.40	TCY	29.000		119,869			119,869
8EX100	100 Excavator	1.00	900.00	HR	52.300			47,070		47,070
8LO950	950 Loader	1.00	900.00	HR	81.500			73,350		73,350
FOCI	Civil Forman	1.00	900.00	MH	77.060	95,961				95,961
LAG	General Laborer	1.00	900.00	MH	52.910	66,477				66,477
OPE	Operator - Excavator	1.00	900.00	MH	74.560	92,909				92,909
\$495,636.12	0.1379 MH/SY		2,700.00	MH	[10.974]	255,348	119,869	120,420		495,636

013.02 GRADING SIDEWALK Quan: 19,570.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EA3</u>	EARTHWORK 3 MAN CREW		348.75	CH	Prod: 348.7525	CH	Lab Pcs: 3.00	Eqp Pcs: 2.00		
8EX100	100 Excavator	1.00	348.75	HR	52.300		18,240			18,240
8LO950	950 Loader	1.00	348.75	HR	81.500		28,423			28,423
FOCI	Civil Forman	1.00	348.75	MH	77.060	35,101				35,101
LAG	General Laborer	1.00	348.75	MH	52.910	24,329				24,329
OPE	Operator - Excavator	1.00	348.75	MH	74.560	33,986				33,986
\$140,078.12	0.0534 MH/SY		1,046.25	MH	[4.009]	93,415	46,663			140,078

=====> **Item Totals: 13 - REMOVE CEMENT CONCRETE SIDEWALK**
\$635,714.24 0.1914 MH/SY 3,746.25 MH [14.983] 348,763 119,869 167,083 **635,714**
32.484 19570 SY 17.82 6.13 8.54 32.48

BID ITEM = 14 CLIENT# = 14 Land Item SCHEDULE: 1 100
Description = REMOVE PAVEMENT Unit = SY Takeoff Quan: 49,157.000 Engr Quan: 49,157.000

014.01 REMOVE PAVEMENT Quan: 49,157.00 SY Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>DEM</u>	Demo 5 Man Crew		1,520.40	CH	Prod: 1,520.4039	CH	Lab Pcs: 5.00	Eqp Pcs: 3.00		
3DEDU02C	Concrete Trucking and Du	1.00	38,197.00	TCY	29.000		1,107,713			1,107,713
3DEDU02B	TRUCKING BRICK MIX	1.00	4,931.00	TCY	29.000		142,999			142,999
8EX135A	135 Excavator W/Attach	1.00	1,520.40	HR	68.251			103,769		103,769
8EX200	200 Excavator	1.00	1,520.40	HR	78.000			118,591		118,591
8LO950	950 Loader	1.00	1,520.40	HR	81.500			123,913		123,913
FOCI	Civil Forman	1.00	1,520.40	MH	77.060	162,111				162,111
LAG	General Laborer	2.00	3,040.81	MH	52.910	224,605				224,605
OPE	Operator - Excavator	2.00	3,040.81	MH	74.560	313,910				313,910
\$2,297,610.01	0.1546 MH/SY		7,602.02	MH	[11.98]	700,625	1,250,712	346,273		2,297,610

=====> **Item Totals: 14 - REMOVE PAVEMENT**
\$2,297,610.01 0.1546 MH/SY 7,602.02 MH [11.98] 700,625 1,250,712 346,273 **2,297,610**
46.740 49157 SY 14.25 25.44 7.04 46.74

BID ITEM = 15 CLIENT# = 15 Land Item SCHEDULE: 1 100
Description = REMOVE PAVEMENT, OVER 14 INCH DEPTH, INC Unit = SY Takeoff Quan: 7,582.000 Engr Quan: 7,582.000

015.01 REMOVE PAVEMENT, OVER 14 INCH DEPTH, IN Quan: 7,582.00 SY Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>DEM</u>	Demo 5 Man Crew		454.37	CH	Prod: 454.3799	CH	Lab Pcs: 5.00	Eqp Pcs: 3.00		
3DEDU02C	Concrete Trucking and Du	1.00	5,984.00	TCY	29.000		173,536			173,536

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract
BID ITEM	= 15	CLIENT# = 15		Land Item	SCHEDULE: 1	100			
Description =	REMOVE PAVEMENT, OVER 14 INCH DEPTH, INC		Unit =	SY	Takeoff	Quan:	7,582.000	Engr Quan:	7,582.000
3DEDU02B	TRUCKING BRICK MIX	1.00	912.00 TCY	29.000			26,448		26,448
3RAILDIS	DISPOSAL OF RAIL	1.00	13,503.12 LF	2.000			27,006		27,006
3TIEDIS	DISPOSAL RAIL TIE	1.00	3,375.78 LF	2.000			6,752		6,752
8EX135A	135 Excavator W/Attach	1.00	454.38 HR	68.251				31,012	31,012
8EX200	200 Excavator	1.00	454.38 HR	78.000				35,442	35,442
8LO950	950 Loader	1.00	454.38 HR	81.500				37,032	37,032
FOCI	Civil Forman	1.00	454.38 MH	77.060	48,448				48,448
LAG	General Laborer	2.00	908.76 MH	52.910	67,124				67,124
OPE	Operator - Excavator	2.00	908.76 MH	74.560	93,813				93,813
\$546,612.53	0.2996 MH/SY	2,271.90	MH	[23.213]	209,385		233,742	103,485	546,613
015.02	STELL YOKE REMOVAL			Quan:	20.00 EA	Hrs/Shft:	10.00 Cal: 510	WC: WAAVG	
8LO950	==> 950 Loader	1.00	80.00 HR	81.500				6,520	6,520
LAG	==> General Laborer	1.00	80.00 MH	52.910	5,581				5,581
\$12,100.82	4.0000 MH/EA	80.00	MH	[232.804]	5,581			6,520	12,101
====>	Item Totals:	15	- REMOVE PAVEMENT, OVER 14 INCH DEPTH, INC						
\$558,713.35	0.3101 MH/SY	2,351.90	MH	[23.827]	214,966		233,742	110,005	558,713
73.689	7582 SY				28.35		30.83	14.51	73.69

BID ITEM	= 16	CLIENT# = 16		Land Item	SCHEDULE: 1	100			
Description =	REMOVE PAVEMENT, OVER 14 INCH DEPTH, INC		Unit =	SY	Takeoff	Quan:	5,742.000	Engr Quan:	5,742.000
016.01	REMOVE PAVEMENT, OVER 14 INCH DEPTH, IN			Quan:	5,742.00 SY	Hrs/Shft:	10.00 Cal: 610	WC: WAAVG	
<u>DEM</u>	Demo 5 Man Crew		229.19 CH	Prod:	229.1911 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
3DEDU02C	Concrete Trucking and Du	1.00	5,001.00 TCY	29.000		145,029			145,029
3DEDU02B	TRUCKING BRICK MIX	1.00	741.00 TCY	29.000		21,489			21,489
3TIEDIS	DISPOSAL RAIL TIE	1.00	2,583.24 LF	2.000		5,166			5,166
8EX135A	135 Excavator W/Attach	1.00	229.19 HR	68.251			15,642		15,642
8EX200	200 Excavator	1.00	229.19 HR	78.000			17,877		17,877
8LO950	950 Loader	1.00	229.19 HR	81.500			18,679		18,679
FOCI	Civil Forman	1.00	229.19 MH	77.060	24,437				24,437
LAG	General Laborer	2.00	458.38 MH	52.910	33,858				33,858
OPE	Operator - Excavator	2.00	458.38 MH	74.560	47,320				47,320
\$329,496.94	0.1995 MH/SY	1,145.95	MH	[15.461]	105,614		171,684	52,198	329,497
====>	Item Totals:	16	- REMOVE PAVEMENT, OVER 14 INCH DEPTH, INC						
\$329,496.94	0.1995 MH/SY	1,145.95	MH	[15.461]	105,614		171,684	52,198	329,497
57.384	5742 SY				18.39		29.90	9.09	57.38

BID ITEM	= 17	CLIENT# = 17		Land Item	SCHEDULE: 1	100			
Description =	REMOVE CURB		Unit =	LF	Takeoff	Quan:	1,489.000	Engr Quan:	1,489.000
017.01	REMOVE CURB			Quan:	1,489.00 LF	Hrs/Shft:	10.00 Cal: 510	WC: WAAVG	
<u>EAS</u>	Earthwork 4 Man Crew		25.00 CH	Prod:	25.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
3DEDU02C	Concrete Trucking and Du	1.00	26.00 TCY	29.000		754			754
8BA310A	418 Backhoe W/Attachme	1.00	25.00 HR	51.051			1,276		1,276
8EX100	100 Excavator	1.00	25.00 HR	52.300			1,307		1,307
FOCI	Civil Forman	1.00	25.00 MH	77.060	2,516				2,516
LAG	General Laborer	2.00	50.00 MH	52.910	3,488				3,488
OPE	Operator - Excavator	1.00	25.00 MH	74.560	2,436				2,436

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 17		CLIENT# = 17	Land Item	SCHEDULE: 1	100					
Description =	REMOVE CURB		Unit =	LF	Takeoff Quan:	1,489.000		Engr Quan:	1,489.000	
\$11,778.22	0.0671 MH/LF	100.00 MH		[4.755]	8,440	754	2,584			11,778
=====> Item Totals: 17 - REMOVE CURB										
\$11,778.22	0.0671 MH/LF	100.00 MH		[4.755]	8,440	754	2,584			11,778
7.910	1489 LF				5.67	0.51	1.74			7.91

BID ITEM = 18		CLIENT# = 18	Land Item	SCHEDULE: 1	100					
Description =	REMOVE PIPE		Unit =	LF	Takeoff Quan:	2,284.000		Engr Quan:	2,284.000	
018.01	REMOVE PIPE		Quan:	2,284.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
UNS	Underground Utilities 4 Man	153.69	CH	Prod:	153.6927 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
3PIPEDIS	PIPE DISPOSAL	1.00	2,284.00 LF	2.000		4,568			4,568	
8BA310A	418 Backhoe W/Attachme	1.00	153.69 HR	51.051			7,846		7,846	
8EX100	100 Excavator	1.00	153.69 HR	52.300			8,038		8,038	
FOCI	Civil Forman	1.00	153.69 MH	77.060	15,469				15,469	
LAP	Labor Underground Water	1.00	153.69 MH	53.880	10,912				10,912	
OPB	Operator - Backhoe	1.00	153.69 MH	74.560	14,977				14,977	
OPE	Operator - Excavator	1.00	153.69 MH	74.560	14,977				14,977	
\$76,786.80	0.2691 MH/LF	614.76 MH		[20.73]	56,335	4,568	15,884			76,787
=====> Item Totals: 18 - REMOVE PIPE										
\$76,786.80	0.2691 MH/LF	614.76 MH		[20.73]	56,335	4,568	15,884			76,787
33.619	2284 LF				24.66	2.00	6.95			33.62

BID ITEM = 19		CLIENT# = 19	Land Item	SCHEDULE: 1	100					
Description =	REMOVE BRACKET ARM, ROADWAY LUMINAIRE		Unit =	EA	Takeoff Quan:	57.000		Engr Quan:	57.000	
019.01	REMOVE BRACKET ARM, ROADWAY LUMINAI		Quan:	57.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	57.00 EA	210.000				11,970		11,970

BID ITEM = 20		CLIENT# = 20	Land Item	SCHEDULE: 1	100					
Description =	REMOVE BRACKET ARM, PEDESTRIAN SCALE LUM		Unit =	EA	Takeoff Quan:	10.000		Engr Quan:	10.000	
020.01	REMOVE BRACKET ARM, PEDESTRIAN SCALE		Quan:	10.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	10.00 EA	210.000				2,100		2,100

BID ITEM = 21		CLIENT# = 21	Land Item	SCHEDULE: 1	100					
Description =	REMOVE ALADDIN ARM ASSEMBLY		Unit =	EA	Takeoff Quan:	2.000		Engr Quan:	2.000	
021.01	REMOVE ALADDIN ARM ASSEMBLY		Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	2.00 EA	200.000				400		400

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
-------------------	------	-----	---------------	-----------	-------	---------------	-----------------	------------	--------------	-------

BID ITEM = **22** CLIENT# = 22 Land Item SCHEDULE: 1 100
Description = REMOVE CATCH BASIN OR SAND BOX Unit = EA Takeoff Quan: 3.000 Engr Quan: 3.000

022.01 REMOVE CATCH BASIN OR SAND BOX Quan: 3.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man		3.00 CH	Prod:	3.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	3.00 HR	51.051				153	153
8EX100	100 Excavator	1.00	3.00 HR	52.300				157	157
FOCI	Civil Forman	1.00	3.00 MH	77.060	302				302
LAP	Labor Underground Water	1.00	3.00 MH	53.880	213				213
OPB	Operator - Backhoe	1.00	3.00 MH	74.560	292				292
OPE	Operator - Excavator	1.00	3.00 MH	74.560	292				292
\$1,409.67	4.0000 MH/EA		12.00 MH	[308.067]	1,100			310	1,410

=====> **Item Totals: 22 - REMOVE CATCH BASIN OR SAND BOX**
\$1,409.67 4.0000 MH/EA 12.00 MH [308.067] 1,100 310 **1,410**
469.890 3 EA 366.55 103.34 469.89

BID ITEM = **23** CLIENT# = 23 Land Item SCHEDULE: 1 100
Description = REMOVE CONDUIT RISER Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

023.01 REMOVE CONDUIT RISER Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4ELEC	Electrical sub	1.00	1.00 EA	400.000				400	400
-------	----------------	------	---------	---------	--	--	--	-----	-----

BID ITEM = **24** CLIENT# = 24 Land Item SCHEDULE: 1 100
Description = REMOVE DOWN GUY ASSEMBLY Unit = EA Takeoff Quan: 8.000 Engr Quan: 8.000

024.01 REMOVE DOWN GUY ASSEMBLY Quan: 8.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4ELEC	Electrical sub	1.00	8.00 EA	250.000				2,000	2,000
-------	----------------	------	---------	---------	--	--	--	-------	-------

BID ITEM = **25** CLIENT# = 25 Land Item SCHEDULE: 1 100
Description = REMOVE ELECTRICAL VAULT Unit = EA Takeoff Quan: 2.000 Engr Quan: 2.000

025.01 REMOVE ELECTRICAL VAULT Quan: 2.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>DBC</u>	DUCTBANK CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
8EX100	100 Excavator	1.00	8.00 HR	52.300				418	418
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546	546
8LO950	950 Loader	1.00	8.00 HR	81.500				652	652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780
\$5,096.95	20.0000 MH/EA		40.00 MH	[1460.805]	3,481			1,616	5,097

=====> **Item Totals: 25 - REMOVE ELECTRICAL VAULT**
\$5,096.95 20.0000 MH/EA 40.00 MH [1460.805] 3,481 1,616 **5,097**
2,548.475 2 EA 1,740.28 808.20 2,548.48

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract

BID ITEM = **26** CLIENT# = 26 Land Item SCHEDULE: 1 100
Description = REMOVE FOUNDATION, PEDESTAL Unit = EA Takeoff Quan: 20.000 Engr Quan: 20.000

026.01 REMOVE FOUNDATION, PEDESTAL Quan: 20.00 EA Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		20.00	CH	Prod:	20.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2AGS17	SEATTLE TYPE 1@110.2	1.00	52.63	TON	25.750		1,494				1,494
3DEDU02C	Concrete Trucking and Du	1.00	52.63	TCY	29.000			1,526			1,526
8BA310A	418 Backhoe W/Attachme	1.00	20.00	HR	51.051				1,021		1,021
8EX100	100 Excavator	1.00	20.00	HR	52.300				1,046		1,046
FOCI	Civil Forman	1.00	20.00	MH	77.060	2,730					2,730
LAG	General Laborer	2.00	40.00	MH	52.910	3,775					3,775
OPE	Operator - Excavator	1.00	20.00	MH	74.560	2,643					2,643
\$14,234.39	4.0000 MH/EA		80.00	MH	[386.16]	9,147	1,494	1,526	2,067		14,234

====> **Item Totals: 26 - REMOVE FOUNDATION, PEDESTAL**
 \$14,234.39 4.0000 MH/EA 80.00 MH [386.16] 9,147 1,494 1,526 2,067 **14,234**
 711.720 20 EA 457.35 74.71 76.31 103.35 711.72

BID ITEM = **27** CLIENT# = 27 Land Item SCHEDULE: 1 100
Description = REMOVE FOUNDATION, PED PUSH BUTTON POST Unit = EA Takeoff Quan: 13.000 Engr Quan: 13.000

027.01 REMOVE FOUNDATION, PED PUSH BUTTON PO Quan: 13.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		3.25	CH	Prod:	3.2500	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
3DEDU02C	Concrete Trucking and Du	1.00	4.33	TCY	29.000		126				126
8BA310A	418 Backhoe W/Attachme	1.00	3.25	HR	51.051				166		166
8EX100	100 Excavator	1.00	3.25	HR	52.300				170		170
FOCI	Civil Forman	1.00	3.25	MH	77.060	327					327
LAG	General Laborer	2.00	6.50	MH	52.910	453					453
OPE	Operator - Excavator	1.00	3.25	MH	74.560	317					317
\$1,558.69	1.0000 MH/EA		13.00	MH	[70.796]	1,097		126	336		1,559

====> **Item Totals: 27 - REMOVE FOUNDATION, PED PUSH BUTTON POST**
 \$1,558.69 1.0000 MH/EA 13.00 MH [70.796] 1,097 126 336 **1,559**
 119.899 13 EA 84.40 9.66 25.84 119.90

BID ITEM = **28** CLIENT# = 28 Land Item SCHEDULE: 1 100
Description = REMOVE FOUNDATION, METAL STRAIN POLE Unit = EA Takeoff Quan: 27.000 Engr Quan: 27.000

028.01 REMOVE FOUNDATION, METAL STRAIN POLE Quan: 27.00 EA Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		54.00	CH	Prod:	54.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2AGS17	SEATTLE TYPE 1@110.2	1.00	86.40	TON	25.750		2,453				2,453
3DEDU02C	Concrete Trucking and Du	1.00	86.40	TCY	29.000			2,506			2,506
8BA310A	418 Backhoe W/Attachme	1.00	54.00	HR	51.051				2,757		2,757
8EX100	100 Excavator	1.00	54.00	HR	52.300				2,824		2,824
FOCI	Civil Forman	1.00	54.00	MH	77.060	5,758					5,758
LAG	General Laborer	2.00	108.00	MH	52.910	7,977					7,977
OPE	Operator - Excavator	1.00	54.00	MH	74.560	5,575					5,575
\$29,848.88	8.0000 MH/EA		216.00	MH	[600.71]	19,309	2,453	2,506	5,581		29,849

====> **Item Totals: 28 - REMOVE FOUNDATION, METAL STRAIN POLE**
 \$29,848.88 8.0000 MH/EA 216.00 MH [600.71] 19,309 2,453 2,506 5,581 **29,849**
 1,105.514 27 EA 715.17 90.85 92.80 206.70 1,105.51

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = **29** CLIENT# = 29 Land Item SCHEDULE: 1 100
Description = REMOVE FOUNDATION, FULL-DEPTH, METAL POL Unit = EA Takeoff Quan: 4.000 Engr Quan: 4.000

029.01 REMOVE FOUNDATION, FULL-DEPTH, METAL Quan: 4.00 EA Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>DEM</u>	Demo 5 Man Crew		32.00	CH	Prod:	32.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2AGS17	SEATTLE TYPE 1@110.2	1.00	176.00	TON	25.750		4,997				4,997
3DEDU02C	Concrete Trucking and Du	1.00	176.00	TCY	29.000			5,104			5,104
8EX135A	135 Excavator W/Attach	1.00	32.00	HR	68.251				2,184		2,184
8EX200	200 Excavator	1.00	32.00	HR	78.000				2,496		2,496
8LO950	950 Loader	1.00	32.00	HR	81.500				2,608		2,608
FOCI	Civil Forman	1.00	32.00	MH	77.060	3,412					3,412
LAG	General Laborer	2.00	64.00	MH	52.910	4,727					4,727
OPE	Operator - Excavator	2.00	64.00	MH	74.560	6,607					6,607
\$32,134.65	40.0000 MH/EA		160.00	MH	[3098.758]	14,746	4,997	5,104	7,288		32,135

=====> **Item Totals: 29 - REMOVE FOUNDATION, FULL-DEPTH, METAL POL**
\$32,134.65 40.0000 MH/EA 160.00 MH [3098.758] 14,746 4,997 5,104 7,288 **32,135**
8,033.663 4 EA 3,686.53 1,249.13 1,276.00 1,822.01 8,033.66

BID ITEM = **30** CLIENT# = 30 Land Item SCHEDULE: 1 100
Description = REMOVE FOUNDATION, STREET LIGHT POLE Unit = EA Takeoff Quan: 36.000 Engr Quan: 36.000

030.01 REMOVE FOUNDATION, STREET LIGHT POLE Quan: 36.00 EA Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		36.00	CH	Prod:	36.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2AGS17	SEATTLE TYPE 1@110.2	1.00	115.20	TON	25.750		3,270				3,270
3DEDU02C	Concrete Trucking and Du	1.00	115.20	TCY	29.000			3,341			3,341
8BA310A	418 Backhoe W/Attachme	1.00	36.00	HR	51.051				1,838		1,838
8EX100	100 Excavator	1.00	36.00	HR	52.300				1,883		1,883
FOCI	Civil Forman	1.00	36.00	MH	77.060	3,838					3,838
LAG	General Laborer	2.00	72.00	MH	52.910	5,318					5,318
OPE	Operator - Excavator	1.00	36.00	MH	74.560	3,716					3,716
\$23,204.87	4.0000 MH/EA		144.00	MH	[300.355]	12,873	3,270	3,341	3,721		23,205

=====> **Item Totals: 30 - REMOVE FOUNDATION, STREET LIGHT POLE**
\$23,204.87 4.0000 MH/EA 144.00 MH [300.355] 12,873 3,270 3,341 3,721 **23,205**
644.580 36 EA 357.58 90.85 92.80 103.35 644.58

BID ITEM = **31** CLIENT# = 31 Land Item SCHEDULE: 1 100
Description = REMOVE FOUNDATION, STEEL MAST ARM POLE Unit = EA Takeoff Quan: 19.000 Engr Quan: 19.000

031.01 REMOVE FOUNDATION, STEEL MAST ARM POL Quan: 19.00 EA Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		38.00	CH	Prod:	38.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2AGS17	SEATTLE TYPE 1@110.2	1.00	112.00	TON	25.750		3,180				3,180
3DEDU02C	Concrete Trucking and Du	1.00	112.00	TCY	29.000			3,248			3,248
8BA310A	418 Backhoe W/Attachme	1.00	38.00	HR	51.051				1,940		1,940
8EX100	100 Excavator	1.00	38.00	HR	52.300				1,987		1,987
FOCI	Civil Forman	1.00	38.00	MH	77.060	5,186					5,186
LAG	General Laborer	2.00	76.00	MH	52.910	7,172					7,172
OPE	Operator - Excavator	1.00	38.00	MH	74.560	5,021					5,021
\$27,734.17	8.0000 MH/EA		152.00	MH	[772.32]	17,379	3,180	3,248	3,927		27,734

=====> **Item Totals: 31 - REMOVE FOUNDATION, STEEL MAST ARM POLE**

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 31	CLIENT# = 31		Land Item	SCHEDULE: 1	100					
Description =	REMOVE FOUNDATION, STEEL MAST ARM POLE		Unit =	EA	Takeoff Quan:		19.000	Engr Quan:		19.000
\$27,734.17	8.0000 MH/EA	152.00	MH	[772.32]	17,379	3,180	3,248	3,927		27,734
1,459.693	19 EA				914.70	167.35	170.95	206.70		1,459.69

BID ITEM = 32	CLIENT# = 32		Land Item	SCHEDULE: 1	100					
Description =	REMOVE FOUNDATION, PEDESTRIAN LIGHT POLE		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000

032.01 REMOVE FOUNDATION, PEDESTRIAN LIGHT P Quan: 1.00 EA Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

EAS	Earthwork 4 Man Crew		1.00	CH	Prod: 1.0000	CH	Lab Pcs: 4.00	Eqp Pcs: 2.00		
8BA310A	418 Backhoe W/Attachme	1.00	1.00	HR	51.051			51		51
8EX100	100 Excavator	1.00	1.00	HR	52.300			52		52
FOCI	Civil Forman	1.00	1.00	MH	77.060	136				136
LAG	General Laborer	2.00	2.00	MH	52.910	189				189
OPE	Operator - Excavator	1.00	1.00	MH	74.560	132				132
\$560.69	4.0000 MH/EA	4.00	MH	[386.16]	457			103		561

====> Item Totals:	32	- REMOVE FOUNDATION, PEDESTRIAN LIGHT POLE								
\$560.69	4.0000 MH/EA	4.00	MH	[386.16]	457			103		561
560.690	1 EA				457.36			103.33		560.69

BID ITEM = 33	CLIENT# = 33		Land Item	SCHEDULE: 1	100					
Description =	REMOVE FOUNDATION, SERVICE CABINET		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000

033.01 REMOVE FOUNDATION, SERVICE CABINET Quan: 1.00 EA Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

EAS	Earthwork 4 Man Crew		1.00	CH	Prod: 1.0000	CH	Lab Pcs: 4.00	Eqp Pcs: 2.00		
3DEDU02C	Concrete Trucking and Du	1.00	5.00	TCY	29.000			145		145
8BA310A	418 Backhoe W/Attachme	1.00	1.00	HR	51.051			51		51
8EX100	100 Excavator	1.00	1.00	HR	52.300			52		52
FOCI	Civil Forman	1.00	1.00	MH	77.060	136				136
LAG	General Laborer	2.00	2.00	MH	52.910	189				189
OPE	Operator - Excavator	1.00	1.00	MH	74.560	132				132
\$705.69	4.0000 MH/EA	4.00	MH	[386.16]	457			145	103	706

====> Item Totals:	33	- REMOVE FOUNDATION, SERVICE CABINET								
\$705.69	4.0000 MH/EA	4.00	MH	[386.16]	457			145	103	706
705.690	1 EA				457.36			145.00	103.33	705.69

BID ITEM = 34	CLIENT# = 34		Land Item	SCHEDULE: 1	100					
Description =	REMOVE FOUNDATION, TRAFFIC SIGNAL CONTRO		Unit =	EA	Takeoff Quan:		24.000	Engr Quan:		24.000

034.01 REMOVE FOUNDATION, TRAFFIC SIGNAL CON Quan: 24.00 EA Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

EAS	Earthwork 4 Man Crew		24.00	CH	Prod: 24.0000	CH	Lab Pcs: 4.00	Eqp Pcs: 2.00		
3DEDU02C	Concrete Trucking and Du	1.00	27.13	TCY	29.000			787		787
8BA310A	418 Backhoe W/Attachme	1.00	24.00	HR	51.051			1,225		1,225
8EX100	100 Excavator	1.00	24.00	HR	52.300			1,255		1,255
FOCI	Civil Forman	1.00	24.00	MH	77.060	3,276				3,276
LAG	General Laborer	2.00	48.00	MH	52.910	4,530				4,530
OPE	Operator - Excavator	1.00	24.00	MH	74.560	3,171				3,171
\$14,243.55	4.0000 MH/EA	96.00	MH	[386.16]	10,976			787	2,480	14,244

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 34	CLIENT# = 34		Land Item	SCHEDULE: 1	100				
Description =	REMOVE FOUNDATION, TRAFFIC SIGNAL CONTRO	Unit =	EA	Takeoff Quan:		24.000	Engr Quan:		24.000
====>	Item Totals: 34 - REMOVE FOUNDATION, TRAFFIC SIGNAL CONTRO								
\$14,243.55	4.0000 MH/EA	96.00 MH	[386.16]	10,976		787	2,480		14,244
593.481	24 EA			457.35		32.78	103.35		593.48

BID ITEM = 35	CLIENT# = 35		Land Item	SCHEDULE: 1	100				
Description =	REMOVE GATE VALVE	Unit =	EA	Takeoff Quan:		21.000	Engr Quan:		21.000
035.01 REMOVE GATE VALVE		Quan:	21.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>UNM</u>	Underground Utilities 6 Man	12.00 CH	Prod:	12.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
8EX135A	135 Excavator W/Attach	1.00 12.00 HR	68.251			819		819	
8EX200	200 Excavator	1.00 12.00 HR	78.000			936		936	
8LO950	950 Loader	1.00 12.00 HR	81.500			978		978	
FOCI	Civil Forman	1.00 12.00 MH	77.060	1,208				1,208	
LAP	Labor Underground Water	2.00 24.00 MH	53.880	1,704				1,704	
OPE	Operator - Excavator	1.00 12.00 MH	74.560	1,169				1,169	
OPL	Operator - Loader	1.00 12.00 MH	74.560	1,169				1,169	
\$7,983.59	2.8571 MH/EA	60.00 MH	[209.905]	5,251		2,733		7,984	
====>	Item Totals: 35 - REMOVE GATE VALVE								
\$7,983.59	2.8571 MH/EA	60.00 MH	[209.905]	5,251		2,733		7,984	
380.171	21 EA			250.03		130.14		380.17	

BID ITEM = 36	CLIENT# = 36		Land Item	SCHEDULE: 1	100				
Description =	REMOVE HANDHOLE	Unit =	EA	Takeoff Quan:		111.000	Engr Quan:		111.000
036.01 REMOVE HANDHOLE		Quan:	111.00 EA	Hrs/Shft:	10.00	Cal: 610	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew	20.00 CH	Prod:	20.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
3DEDU02C	Concrete Trucking and Du	1.00 25.23 TCY	29.000		732			732	
8BA310A	418 Backhoe W/Attachme	1.00 20.00 HR	51.051			1,021		1,021	
8EX100	100 Excavator	1.00 20.00 HR	52.300			1,046		1,046	
FOCI	Civil Forman	1.00 20.00 MH	77.060	2,132				2,132	
LAG	General Laborer	2.00 40.00 MH	52.910	2,955				2,955	
OPE	Operator - Excavator	1.00 20.00 MH	74.560	2,065				2,065	
\$9,950.34	0.7207 MH/EA	80.00 MH	[54.118]	7,152	732	2,067		9,950	
====>	Item Totals: 36 - REMOVE HANDHOLE								
\$9,950.34	0.7207 MH/EA	80.00 MH	[54.118]	7,152	732	2,067		9,950	
89.643	111 EA			64.43	6.59	18.62		89.64	

BID ITEM = 37	CLIENT# = 37		Land Item	SCHEDULE: 1	100				
Description =	REMOVE HYDRANT	Unit =	EA	Takeoff Quan:		13.000	Engr Quan:		13.000
037.01 REMOVE HYDRANT		Quan:	13.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>UNM</u>	Underground Utilities 6 Man	26.00 CH	Prod:	26.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
8EX135A	135 Excavator W/Attach	1.00 26.00 HR	68.251		1,775			1,775	
8EX200	200 Excavator	1.00 26.00 HR	78.000		2,028			2,028	
8LO950	950 Loader	1.00 26.00 HR	81.500		2,119			2,119	
FOCI	Civil Forman	1.00 26.00 MH	77.060	2,617				2,617	

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 37	CLIENT# = 37									
Description =	REMOVE HYDRANT			Land Item Unit =	SCHEDULE: 1 100					
				EA	Takeoff Quan:		13.000	Engr Quan:		13.000
LAP	Labor Underground Water	2.00	52.00 MH	53.880	3,692					3,692
OPE	Operator - Excavator	1.00	26.00 MH	74.560	2,534					2,534
OPL	Operator - Loader	1.00	26.00 MH	74.560	2,534					2,534
\$17,297.80	10.0000 MH/EA		130.00 MH	[734.669]	11,376			5,922		17,298
====> Item Totals:	37 - REMOVE HYDRANT									
\$17,297.80	10.0000 MH/EA		130.00 MH	[734.669]	11,376			5,922		17,298
1,330.600	13 EA				875.10			455.50		1,330.60

BID ITEM = 38	CLIENT# = 38									
Description =	REMOVE INLET			Land Item Unit =	SCHEDULE: 1 100					
				EA	Takeoff Quan:		4.000	Engr Quan:		4.000
038.01	REMOVE INLET			Quan:	4.00 EA	Hrs/Shft:	10.00	Cal:	S10	WC: WAAVG
UNS	Underground Utilities 4 Man		3.90 CH	Prod:	3.9024 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	3.90 HR	51.051			199		199	
8EX100	100 Excavator	1.00	3.90 HR	52.300			204		204	
FOCI	Civil Forman	1.00	3.90 MH	77.060	532				532	
LAP	Labor Underground Water	1.00	3.90 MH	53.880	375				375	
OPB	Operator - Backhoe	1.00	3.90 MH	74.560	515				515	
OPE	Operator - Excavator	1.00	3.90 MH	74.560	515				515	
\$2,340.58	3.9000 MH/EA		15.60 MH	[409.59]	1,938			403		2,341
====> Item Totals:	38 - REMOVE INLET									
\$2,340.58	3.9000 MH/EA		15.60 MH	[409.59]	1,938			403		2,341
585.145	4 EA				484.38			100.76		585.15

BID ITEM = 39	CLIENT# = 39									
Description =	REMOVE LUMINAIRE, ROADWAY			Land Item Unit =	SCHEDULE: 1 100					
				EA	Takeoff Quan:		77.000	Engr Quan:		77.000
039.01	REMOVE LUMINAIRE, ROADWAY			Quan:	77.00 EA	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
4ELEC	Electrical sub	1.00	77.00 EA	210.000				16,170		16,170

BID ITEM = 40	CLIENT# = 40									
Description =	REMOVE PAVEMENT INCLUDING RAIL AND CABLE			Land Item Unit =	SCHEDULE: 1 100					
				SY	Takeoff Quan:		3,648.000	Engr Quan:		3,648.000
040.01	REMOVE PAVEMENT INCLUDING RAIL AND CA			Quan:	3,648.00 SY	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
DEM	Demo 5 Man Crew		344.00 CH	Prod:	344.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
3DEDU02C	Concrete Trucking and Du	1.00	2,963.00 TCY	29.000		85,927			85,927	
3DEDU02B	TRUCKING BRICK MIX	1.00	685.00 TCY	29.000		19,865			19,865	
3RAILDIS	DISPOSAL OF RAIL	1.00	7,000.00 LF	2.000		14,000			14,000	
3TIEDIS	DISPOSAL RAIL TIE	1.00	1,635.00 LF	2.000		3,270			3,270	
8EX135A	135 Excavator W/Attach	1.00	344.00 HR	68.251			23,478		23,478	
8EX200	200 Excavator	1.00	344.00 HR	78.000			26,832		26,832	
8LO950	950 Loader	1.00	344.00 HR	81.500			28,036		28,036	
FOCI	Civil Forman	1.00	344.00 MH	77.060	34,623				34,623	
LAG	General Laborer	2.00	688.00 MH	52.910	47,995				47,995	
OPE	Operator - Excavator	2.00	688.00 MH	74.560	67,046				67,046	
\$351,071.74	0.4714 MH/SY		1,720.00 MH	[34.438]	149,663		123,062	78,346		351,072

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 40	CLIENT# = 40		Land Item	SCHEDULE: 1	100					
Description =	REMOVE PAVEMENT INCLUDING RAIL AND CABLE	Unit =	SY	Takeoff Quan:	3,648.000	Engr Quan:	3,648.000			
=====>	Item Totals: 40 - REMOVE PAVEMENT INCLUDING RAIL AND CABLE									
\$351,071.74	0.4714 MH/SY	1,720.00 MH	[34.438]	149,663		123,062	78,346			351,072
96.237	3648 SY			41.03		33.73	21.48			96.24

BID ITEM = 41	CLIENT# = 41		Land Item	SCHEDULE: 1	100					
Description =	REMOVE MAINTENANCE HOLE	Unit =	EA	Takeoff Quan:	3.000	Engr Quan:	3.000			
041.01	REMOVE MAINTENANCE HOLE	Quan:	3.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>UNM</u>	Underground Utilities 6 Man	12.00 CH	Prod:	12.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00		
3DEDU02C	Concrete Trucking and Du	1.00 21.00 TCY	29.000		609			609		
8EX135A	135 Excavator W/Attach	1.00 12.00 HR	68.251			819		819		
8EX200	200 Excavator	1.00 12.00 HR	78.000			936		936		
8LO950	950 Loader	1.00 12.00 HR	81.500			978		978		
FOCI	Civil Forman	1.00 12.00 MH	77.060	1,208				1,208		
LAP	Labor Underground Water	2.00 24.00 MH	53.880	1,704				1,704		
OPE	Operator - Excavator	1.00 12.00 MH	74.560	1,169				1,169		
OPL	Operator - Loader	1.00 12.00 MH	74.560	1,169				1,169		
\$8,592.59	20.0000 MH/EA	60.00 MH	[1469.333]	5,251	609	2,733		8,593		
=====>	Item Totals: 41 - REMOVE MAINTENANCE HOLE									
\$8,592.59	20.0000 MH/EA	60.00 MH	[1469.333]	5,251	609	2,733		8,593		
2,864.197	3 EA			1,750.20	203.00	911.00		2,864.20		

BID ITEM = 42	CLIENT# = 42		Land Item	SCHEDULE: 1	100					
Description =	REMOVE PEDESTAL	Unit =	EA	Takeoff Quan:	22.000	Engr Quan:	22.000			
042.01	REMOVE PEDESTAL	Quan:	22.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00 22.00 EA	400.000			8,800		8,800		

BID ITEM = 43	CLIENT# = 43		Land Item	SCHEDULE: 1	100					
Description =	REMOVE POLE, METAL STRAIN	Unit =	EA	Takeoff Quan:	24.000	Engr Quan:	24.000			
043.01	REMOVE POLE, METAL STRAIN	Quan:	24.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00 24.00 EA	1,600.000			38,400		38,400		

BID ITEM = 44	CLIENT# = 44		Land Item	SCHEDULE: 1	100					
Description =	REMOVE MAST ARM	Unit =	EA	Takeoff Quan:	2.000	Engr Quan:	2.000			
044.01	REMOVE MAST ARM	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00 2.00 EA	1,600.000			3,200		3,200		

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 45	CLIENT# = 45		Land Item	SCHEDULE: 1	100					
Description =	REMOVE POLE, STREET LIGHT		Unit =	EA	Takeoff Quan:		31.000	Engr Quan:		31.000
045.01	REMOVE POLE, STREET LIGHT		Quan:	31.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	31.00 EA	400.000				12,400		12,400
BID ITEM = 46	CLIENT# = 46		Land Item	SCHEDULE: 1	100					
Description =	REMOVE POLE, STEEL MAST ARM		Unit =	EA	Takeoff Quan:		19.000	Engr Quan:		19.000
046.01	REMOVE POLE, STEEL MAST ARM		Quan:	19.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	19.00 EA	1,600.000				30,400		30,400
BID ITEM = 47	CLIENT# = 47		Land Item	SCHEDULE: 1	100					
Description =	REMOVE POLE, PEDESTRIAN LIGHT		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
047.01	REMOVE POLE, PEDESTRIAN LIGHT		Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	2.00 EA	400.000				800		800
BID ITEM = 48	CLIENT# = 48		Land Item	SCHEDULE: 1	100					
Description =	REMOVE POLE, WOOD		Unit =	EA	Takeoff Quan:		19.000	Engr Quan:		19.000
048.01	REMOVE POLE, WOOD		Quan:	19.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	19.00 EA	390.000				7,410		7,410
BID ITEM = 49	CLIENT# = 49		Land Item	SCHEDULE: 1	100					
Description =	REMOVE POST, BUS ZONE		Unit =	EA	Takeoff Quan:		24.000	Engr Quan:		24.000
049.01	REMOVE POST, BUS ZONE		Quan:	24.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZ</u>	SIGN CREW		12.00 CH	Prod:	12.0000 CH	Lab Pcs:	1.00	Eqp Pcs:		0.00
LAG	General Laborer	1.00	12.00 MH	52.910	837					837
\$837.12	0.5000 MH/EA		12.00 MH	[29.1]	837					837
Item Totals:	49 - REMOVE POST, BUS ZONE									
\$837.12	0.5000 MH/EA		12.00 MH	[29.1]	837					837
34.880	24 EA				34.88					34.88
BID ITEM = 50	CLIENT# = 50		Land Item	SCHEDULE: 1	100					
Description =	REMOVE POST, PEDESTRIAN PUSHBUTTON		Unit =	EA	Takeoff Quan:		13.000	Engr Quan:		13.000
050.01	REMOVE POST, PEDESTRIAN PUSHBUTTON		Quan:	13.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	13.00 EA	310.000				4,030		4,030

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM	= 51	CLIENT# = 51	Land Item	SCHEDULE: 1	100					
Description =	REMOVE POST, TRAFFIC SIGN		Unit =	EA	Takeoff Quan:	233.000		Engr Quan:	233.000	
051.01	REMOVE POST, TRAFFIC SIGN		Quan:	233.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZ</u>	SIGN CREW		116.50 CH	Prod:	116.5000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
LAG	General Laborer	1.00	116.50 MH	52.910	8,127				8,127	
\$8,127.08	0.5000 MH/EA		116.50 MH	[29.101]	8,127				8,127	
====>	Item Totals:	51	- REMOVE POST, TRAFFIC SIGN							
\$8,127.08	0.5000 MH/EA		116.50 MH	[29.101]	8,127				8,127	
34.880	233 EA				34.88				34.88	
BID ITEM	= 52	CLIENT# = 52	Land Item	SCHEDULE: 1	100					
Description =	REMOVE SIGN, STREET DESIGNATION		Unit =	EA	Takeoff Quan:	22.000		Engr Quan:	22.000	
052.01	REMOVE SIGN, STREET DESIGNATION		Quan:	22.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZ</u>	SIGN CREW		11.00 CH	Prod:	11.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
LAG	General Laborer	1.00	11.00 MH	52.910	767				767	
\$767.36	0.5000 MH/EA		11.00 MH	[29.1]	767				767	
====>	Item Totals:	52	- REMOVE SIGN, STREET DESIGNATION							
\$767.36	0.5000 MH/EA		11.00 MH	[29.1]	767				767	
34.880	22 EA				34.88				34.88	
BID ITEM	= 53	CLIENT# = 53	Land Item	SCHEDULE: 1	100					
Description =	REMOVE SIGN, ILLUMINATED SIGN		Unit =	EA	Takeoff Quan:	5.000		Engr Quan:	5.000	
053.01	REMOVE SIGN, ILLUMINATED SIGN		Quan:	5.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	5.00 EA	570.000				2,850	2,850	
BID ITEM	= 54	CLIENT# = 54	Land Item	SCHEDULE: 1	100					
Description =	REMOVE SIGN, BUS ZONE		Unit =	EA	Takeoff Quan:	3.000		Engr Quan:	3.000	
054.01	REMOVE SIGN, BUS ZONE		Quan:	3.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZ</u>	SIGN CREW		1.50 CH	Prod:	1.5000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
LAG	General Laborer	1.00	1.50 MH	52.910	105				105	
\$104.64	0.5000 MH/EA		1.50 MH	[29.1]	105				105	
====>	Item Totals:	54	- REMOVE SIGN, BUS ZONE							
\$104.64	0.5000 MH/EA		1.50 MH	[29.1]	105				105	
34.880	3 EA				34.88				34.88	
BID ITEM	= 55	CLIENT# = 55	Land Item	SCHEDULE: 1	100					
Description =	REMOVE SIGN, STREET NAME, POLE MOUNTED		Unit =	EA	Takeoff Quan:	33.000		Engr Quan:	33.000	
055.01	REMOVE SIGN, STREET NAME		Quan:	33.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		

Activity	Desc	Quantity	Unit	Unit Cost	Labor	Perm	Constr	Equip	Sub-	Total
Resource		Pcs				Material	Matl/Exp	Ment	Contract	
BID ITEM = 55	CLIENT# = 55		Land Item	SCHEDULE: 1	100					
Description =	REMOVE SIGN, STREET NAME, POLE MOUNTED		Unit =	EA	Takeoff	Quan:	33.000	Engr	Quan:	33.000
ZZZ	SIGN CREW		16.00 CH	Prod:	16.0000	CH	Lab Pcs:	1.00	Eqp Pcs:	0.00
LAG	General Laborer	1.00	16.00 MH	52.910	1,116					1,116
\$1,116.17	0.4848 MH/EA		16.00 MH	[28.219]	1,116					1,116
=====>	Item Totals:	55	- REMOVE SIGN, STREET NAME, POLE MOUNTED							
\$1,116.17	0.4848 MH/EA		16.00 MH	[28.219]	1,116					1,116
33.823	33 EA				33.82					33.82
BID ITEM = 56	CLIENT# = 56		Land Item	SCHEDULE: 1	100					
Description =	REMOVE SIGN, OVERHEAD		Unit =	EA	Takeoff	Quan:	12.000	Engr	Quan:	12.000
056.01	REMOVE SIGN, OVERHEAD		Quan:	12.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	12.00 EA	50.000					600	600
BID ITEM = 57	CLIENT# = 57		Land Item	SCHEDULE: 1	100					
Description =	REMOVE SIGN, TRAFFIC		Unit =	EA	Takeoff	Quan:	341.000	Engr	Quan:	341.000
057.01	REMOVE SIGN, TRAFFIC		Quan:	341.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
ZZZ	SIGN CREW		170.50 CH	Prod:	170.5000	CH	Lab Pcs:	1.00	Eqp Pcs:	0.00
LAG	General Laborer	1.00	170.50 MH	52.910	11,894					11,894
\$11,894.14	0.5000 MH/EA		170.50 MH	[29.1]	11,894					11,894
=====>	Item Totals:	57	- REMOVE SIGN, TRAFFIC							
\$11,894.14	0.5000 MH/EA		170.50 MH	[29.1]	11,894					11,894
34.880	341 EA				34.88					34.88
BID ITEM = 58	CLIENT# = 58		Land Item	SCHEDULE: 1	100					
Description =	REMOVE SIGN, STREET NAME		Unit =	EA	Takeoff	Quan:	13.000	Engr	Quan:	13.000
058.01	REMOVE SIGN, STREET NAME		Quan:	13.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
ZZZ	SIGN CREW		6.50 CH	Prod:	6.5000	CH	Lab Pcs:	1.00	Eqp Pcs:	0.00
LAG	General Laborer	1.00	6.50 MH	52.910	453					453
\$453.45	0.5000 MH/EA		6.50 MH	[29.101]	453					453
=====>	Item Totals:	58	- REMOVE SIGN, STREET NAME							
\$453.45	0.5000 MH/EA		6.50 MH	[29.101]	453					453
34.881	13 EA				34.88					34.88
BID ITEM = 59	CLIENT# = 59		Land Item	SCHEDULE: 1	100					
Description =	REMOVE SERVICE CABINET		Unit =	EA	Takeoff	Quan:	1.000	Engr	Quan:	1.000
059.01	REMOVE SERVICE CABINET		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 EA	990.000					990	990

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 60	CLIENT# = 60	Land Item	SCHEDULE: 1	100					
Description =	REMOVE TRAFFIC SIGNAL CONTROLLER CABINET	Unit =	EA	Takeoff Quan:	26.000	Engr Quan:	26.000		
060.01	REMOVE TRAFFIC SIGNAL CONTROLLER CABI	Quan:	26.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
4ELEC	Electrical sub	1.00	26.00 EA	990.000				25,740	25,740
BID ITEM = 61	CLIENT# = 61	Land Item	SCHEDULE: 1	100					
Description =	REMOVE TREE	Unit =	EA	Takeoff Quan:	53.000	Engr Quan:	53.000		
061.01	REMOVE TREE	Quan:	53.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
3TREEREM	TREE REMOVAL	1.00	53.00 EA	2,350.000			124,550		124,550
====>	Item Totals: 61 - REMOVE TREE								
\$124,550.00				[]			124,550		124,550
2,350.000		53 EA					2,350.00		2,350.00
BID ITEM = 62	CLIENT# = 62	Land Item	SCHEDULE: 1	100					
Description =	REMOVE VALVE CHAMBER	Unit =	EA	Takeoff Quan:	4.000	Engr Quan:	4.000		
062.01	REMOVE VALVE CHAMBER	Quan:	4.00 EA	Hrs/Shft:	10.00	Cal:	610	WC:	WAAVG
UNM	Underground Utilities 6 Man	8.00	CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546		546
8EX200	200 Excavator	1.00	8.00 HR	78.000			624		624
8LO950	950 Loader	1.00	8.00 HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	853				853
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,203				1,203
OPE	Operator - Excavator	1.00	8.00 MH	74.560	826				826
OPL	Operator - Loader	1.00	8.00 MH	74.560	826				826
\$5,529.58	10.0000 MH/EA	40.00	MH	[779.215]	3,708		1,822		5,530
====>	Item Totals: 62 - REMOVE VALVE CHAMBER								
\$5,529.58	10.0000 MH/EA	40.00	MH	[779.215]	3,708		1,822		5,530
1,382.395	4 EA				926.90		455.50		1,382.40
BID ITEM = 63	CLIENT# = 63	Land Item	SCHEDULE: 1	100					
Description =	REMOVE VEHICLE SIGNAL HEAD	Unit =	EA	Takeoff Quan:	200.000	Engr Quan:	200.000		
063.01	REMOVE VEHICLE SIGNAL HEAD	Quan:	200.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
4ELEC	Electrical sub	1.00	200.00 EA	290.000				58,000	58,000
BID ITEM = 64	CLIENT# = 64	Land Item	SCHEDULE: 1	100					
Description =	REMOVE PEDESTRIAN SIGNAL HEAD	Unit =	EA	Takeoff Quan:	146.000	Engr Quan:	146.000		
064.01	REMOVE PEDESTRIAN SIGNAL HEAD	Quan:	146.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
4ELEC	Electrical sub	1.00	146.00 EA	150.000				21,900	21,900

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 65	CLIENT# = 65	Land Item	SCHEDULE: 1	100						
Description =	REMOVE PEDESTRIAN PUSH BUTTON ASSEMBLY	Unit =	EA	Takeoff Quan:			72.000	Engr Quan:		72.000
065.01	REMOVE PEDESTRIAN PUSH BUTTON ASSEMB	Quan:	72.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	72.00 EA	90.000				6,480		6,480
BID ITEM = 66	CLIENT# = 66	Land Item	SCHEDULE: 1	100						
Description =	REMOVE VIDEO DETECTION CAMERA	Unit =	EA	Takeoff Quan:			5.000	Engr Quan:		5.000
066.01	REMOVE VIDEO DETECTION CAMERA	Quan:	5.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	5.00 EA	290.000				1,450		1,450
BID ITEM = 67	CLIENT# = 67	Land Item	SCHEDULE: 1	100						
Description =	REMOVE BICYCLE PUSHBUTTON ASSEMBLY	Unit =	EA	Takeoff Quan:			1.000	Engr Quan:		1.000
067.01	REMOVE BICYCLE PUSHBUTTON ASSEMBLY	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	90.000				90		90
BID ITEM = 68	CLIENT# = 68	Land Item	SCHEDULE: 1	100						
Description =	REMOVE EMERGENCY PRE-EMPT DETECTOR	Unit =	EA	Takeoff Quan:			3.000	Engr Quan:		3.000
068.01	REMOVE EMERGENCY PRE-EMPT DETECTOR	Quan:	3.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	3.00 EA	110.000				330		330
BID ITEM = 69	CLIENT# = 69	Land Item	SCHEDULE: 1	100						
Description =	REMOVE RRFB SYSTEM, (19TH & UNION)	Unit =	LS	Takeoff Quan:			1.000	Engr Quan:		1.000
069.01	REMOVE RRFB SYSTEM, (19TH & UNION)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	3,090.000				3,090		3,090
BID ITEM = 70	CLIENT# = 70	Land Item	SCHEDULE: 1	100						
Description =	SAWCUT CEMENT CONCRETE SIDEWALK, FULL DE	Unit =	LF	Takeoff Quan:			6,831.000	Engr Quan:		6,831.000
070.01	SAWCUT CEMENT CONCRETE SIDEWALK, FUL	Quan:	27,324.00 INFT	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4SAWC	Sawcutting	1.00	27,324.00 INFT	0.580				15,848		15,848
BID ITEM = 71	CLIENT# = 71	Land Item	SCHEDULE: 1	100						
Description =	SAWCUT RIGID PAVEMENT, FULL DEPTH	Unit =	LF	Takeoff Quan:			19,472.000	Engr Quan:		19,472.000

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract

BID ITEM = 71 CLIENT# = 71 Land Item SCHEDULE: 1 100
Description = SAWCUT RIGID PAVEMENT, FULL DEPTH Unit = LF Takeoff Quan: 19,472.000 Engr Quan: 19,472.000

071.01 SAWCUT RIGID PAVEMENT, FULL DEPTH **Quan: 282,459.25 INFT Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

4SAWC	Sawcutting	1.00	282,459.24	INFT	0.680			192,072	192,072
-------	------------	------	------------	------	-------	--	--	---------	---------

BID ITEM = 72 CLIENT# = 72 Land Item SCHEDULE: 1 100
Description = ABANDON CATCH BASIN Unit = EA Takeoff Quan: 2.000 Engr Quan: 2.000

072.01 ABANDON CATCH BASIN **Quan: 2.00 EA Hrs/Shft: 10.00 Cal: 610 WC: WAAVG**

<u>UNS</u>	Underground Utilities 4 Man	4.00	CH	Prod:	4.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2AGS17	SEATTLE TYPE 1@110.2	1.00	20.00	TON	25.750		568			568
8BA310A	418 Backhoe W/Attachme	1.00	4.00	HR	51.051			204		204
8EX100	100 Excavator	1.00	4.00	HR	52.300			209		209
FOCI	Civil Forman	1.00	4.00	MH	77.060	426				426
LAP	Labor Underground Water	1.00	4.00	MH	53.880	301				301
OPB	Operator - Backhoe	1.00	4.00	MH	74.560	413				413
OPE	Operator - Excavator	1.00	4.00	MH	74.560	413				413
\$2,534.26	8.0000 MH/EA	16.00	MH	[653.495]	1,553	568		413		2,534

=====> **Item Totals: 72 - ABANDON CATCH BASIN**
 \$2,534.26 8.0000 MH/EA 16.00 MH [653.495] 1,553 568 413 **2,534**
 1,267.130 2 EA 776.54 283.90 206.70 1,267.13

BID ITEM = 73 CLIENT# = 73 Land Item SCHEDULE: 1 100
Description = ABANDON VALVE CHAMBER Unit = EA Takeoff Quan: 19.000 Engr Quan: 19.000

073.01 ABANDON VALVE CHAMBER **Quan: 19.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>UNM</u>	Underground Utilities 6 Man	19.00	CH	Prod:	19.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2AGS17	SEATTLE TYPE 1@110.2	1.00	50.00	TON	25.750		1,419			1,419
8EX135A	135 Excavator W/Attach	1.00	19.00	HR	68.251			1,297		1,297
8EX200	200 Excavator	1.00	19.00	HR	78.000			1,482		1,482
8LO950	950 Loader	1.00	19.00	HR	81.500			1,548		1,548
FOCI	Civil Forman	1.00	19.00	MH	77.060	1,912				1,912
LAP	Labor Underground Water	2.00	38.00	MH	53.880	2,698				2,698
OPE	Operator - Excavator	1.00	19.00	MH	74.560	1,852				1,852
OPL	Operator - Loader	1.00	19.00	MH	74.560	1,852				1,852
\$14,060.15	5.0000 MH/EA	95.00	MH	[367.333]	8,313	1,419		4,327		14,060

=====> **Item Totals: 73 - ABANDON VALVE CHAMBER**
 \$14,060.15 5.0000 MH/EA 95.00 MH [367.333] 8,313 1,419 4,327 **14,060**
 740.008 19 EA 437.55 74.71 227.75 740.01

BID ITEM = 74 CLIENT# = 74 Land Item SCHEDULE: 1 100
Description = ABANDON AND FILL PIPE Unit = LF Takeoff Quan: 1,282.000 Engr Quan: 1,282.000

074.01 ABANDON AND FILL PIPE **Quan: 1,282.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>UNS</u>	Underground Utilities 4 Man	66.29	CH	Prod:	66.2961	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2CRCDF	CDF@110.25%	1.00	37.29	CY	106.150	4,364				4,364

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 74	CLIENT# = 74									
Description =	ABANDON AND FILL PIPE		Land Item Unit =	SCHEDULE: 1 100						
				LF	Takeoff Quan:		1,282.000	Engr Quan:		1,282.000
3PUMPLINE	LINE PUMP	1.00	41.44 HR	175.000			7,252			7,252
8BA310A	418 Backhoe W/Attachme	1.00	66.30 HR	51.051				3,385		3,385
8EX100	100 Excavator	1.00	66.30 HR	52.300				3,467		3,467
FOCI	Civil Forman	1.00	66.30 MH	77.060	6,673					6,673
LAP	Labor Underground Water	1.00	66.30 MH	53.880	4,707					4,707
OPB	Operator - Backhoe	1.00	66.30 MH	74.560	6,461					6,461
OPE	Operator - Excavator	1.00	66.30 MH	74.560	6,461					6,461
\$42,770.40	0.2068 MH/LF		265.20 MH	[15.932]	24,302	4,364	7,252	6,852		42,770
=====> Item Totals: 74 - ABANDON AND FILL PIPE										
\$42,770.40	0.2068 MH/LF		265.20 MH	[15.932]	24,302	4,364	7,252	6,852		42,770
33.362	1282 LF				18.96	3.40	5.66	5.34		33.36

BID ITEM = 75	CLIENT# = 75									
Description =	REMOVE, STORE AND REINSTALL KCM SIGN		Land Item Unit =	SCHEDULE: 1 100						
				EA	Takeoff Quan:		1.000	Engr Quan:		1.000
075.01	REMOVE, STORE AND REINSTALL KCM SIGN	Quan:	1.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
<u>ZZZ</u>	SIGN CREW		1.00 CH	Prod:	1.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
LAG	General Laborer	1.00	1.00 MH	52.910	70					70
\$69.76	1.0000 MH/EA		1.00 MH	[58.2]	70					70
=====> Item Totals: 75 - REMOVE, STORE AND REINSTALL KCM SIGN										
\$69.76	1.0000 MH/EA		1.00 MH	[58.2]	70					70
69.760	1 EA				69.76					69.76

BID ITEM = 76	CLIENT# = 76									
Description =	REMOVE, STORE AND REINSTALL MOSAIC TILE		Land Item Unit =	SCHEDULE: 1 100						
				EA	Takeoff Quan:		6.000	Engr Quan:		6.000
076.01	REMOVE STOR MOSAIC TILE	Quan:	6.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
<u>EAS</u>	Earthwork 4 Man Crew		3.00 CH	Prod:	3.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
4SAWC	Sawcutting	1.00	216.00 INFT	0.580				125	125	
8BA310A	418 Backhoe W/Attachme	1.00	3.00 HR	51.051				153	153	
8EX100	100 Excavator	1.00	3.00 HR	52.300				157	157	
FOCI	Civil Forman	1.00	3.00 MH	77.060	302				302	
LAG	General Laborer	2.00	6.00 MH	52.910	419				419	
OPE	Operator - Excavator	1.00	3.00 MH	74.560	292				292	
\$1,448.17	2.0000 MH/EA		12.00 MH	[141.593]	1,013			310	125	1,448
076.02	INSTALL MOSIAC TILE	Quan:	6.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
<u>COM</u>	Concrete 6 Man Crew		5.00 CH	Prod:	5.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
CEJ	Cement Mason	5.00	25.00 MH	64.980	2,130				2,130	
FOCO	Concrete Forman	1.00	5.00 MH	68.980	452				452	
\$2,581.51	5.0000 MH/EA		30.00 MH	[361.057]	2,582					2,582
=====> Item Totals: 76 - REMOVE, STORE AND REINSTALL MOSAIC TILE										
\$4,029.68	7.0000 MH/EA		42.00 MH	[502.65]	3,594			310	125	4,030
671.613	6 EA				599.06			51.67	20.88	671.61

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 77 CLIENT# = 77 Land Item SCHEDULE: 1 100
Description = REMOVE SPAN WIRE Unit = LF Takeoff Quan: 2,230.000 Engr Quan: 2,230.000

077.01 REMOVE SPAN WIRE Quan: 2,230.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4ELEC	Electrical sub	1.00	2,230.00 LF	3.300				7,359		7,359
-------	----------------	------	-------------	-------	--	--	--	-------	--	-------

BID ITEM = 78 CLIENT# = 78 Land Item SCHEDULE: 1 100
Description = REMOVE, STORE AND REINSTALL BIKE RACK Unit = EA Takeoff Quan: 36.000 Engr Quan: 36.000

078.01 REMOVE, STORE AND REINSTALL BIKE RACK Quan: 36.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>ZZZZ</u>	SITE FURNISHINGS CREW	72.00	CH	Prod: 72.0000 CH	Lab Pcs: 2.00	Eqp Pcs: 0.00
LAG	General Laborer	2.00	144.00 MH	52.910	10,045	10,045
\$10,045.48	4.0000 MH/ EA	144.00 MH	[232.804]	10,045		10,045

=====> **Item Totals: 78 - REMOVE, STORE AND REINSTALL BIKE RACK**
\$10,045.48 4.0000 MH/ EA 144.00 MH [232.804] 10,045 **10,045**
279.041 36 EA 279.04

BID ITEM = 79 CLIENT# = 79 Land Item SCHEDULE: 1 100
Description = REMOVE, STORE AND REINSTALL BOLLARD Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

079.01 REMOVE, STORE AND REINSTALL BOLLARD Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>ZZZZ</u>	SITE FURNISHINGS CREW	4.00	CH	Prod: 4.0000 CH	Lab Pcs: 2.00	Eqp Pcs: 0.00
LAG	General Laborer	2.00	8.00 MH	52.910	558	558
\$558.08	8.0000 MH/EA	8.00 MH	[465.61]	558		558

=====> **Item Totals: 79 - REMOVE, STORE AND REINSTALL BOLLARD**
\$558.08 8.0000 MH/EA 8.00 MH [465.61] 558 **558**
558.080 1 EA 558.08

BID ITEM = 80 CLIENT# = 80 Land Item SCHEDULE: 1 100
Description = REMOVE, STORE AND REINSTALL BENCH Unit = EA Takeoff Quan: 6.000 Engr Quan: 6.000

080.01 REMOVE, STORE AND REINSTALL BENCH Quan: 6.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>ZZZZ</u>	SITE FURNISHINGS CREW	12.00	CH	Prod: 12.0000 CH	Lab Pcs: 2.00	Eqp Pcs: 0.00
LAG	General Laborer	2.00	24.00 MH	52.910	1,674	1,674
\$1,674.24	4.0000 MH/EA	24.00 MH	[232.803]	1,674		1,674

=====> **Item Totals: 80 - REMOVE, STORE AND REINSTALL BENCH**
\$1,674.24 4.0000 MH/EA 24.00 MH [232.803] 1,674 **1,674**
279.040 6 EA 279.04

BID ITEM = 81 CLIENT# = 81 Land Item SCHEDULE: 1 100
Description = REMOVE, STORE AND REINSTALL LITTER RECEP Unit = EA Takeoff Quan: 14.000 Engr Quan: 14.000

081.01 REMOVE, STORE AND REINSTALL LITTER REC Quan: 14.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 81	CLIENT# = 81		Land Item	SCHEDULE: 1 100						
Description =	REMOVE, STORE AND REINSTALL LITTER RECEP		Unit =	EA	Takeoff Quan:		14.000	Engr Quan:		14.000
<u>ZZZZ</u>	SITE FURNISHINGS CREW		14.00 CH	Prod:	14.0000 CH	Lab Pcs:		2.00	Eqp Pcs:	0.00
LAG	General Laborer	2.00	28.00 MH	52.910	1,953					1,953
\$1,953.29	2.0000 MH/EA		28.00 MH	[116.402]	1,953					1,953
====>	Item Totals:	81	- REMOVE, STORE AND REINSTALL LITTER RECEP							
\$1,953.29	2.0000 MH/EA		28.00 MH	[116.402]	1,953					1,953
139.521	14 EA				139.52					139.52

BID ITEM = 82	CLIENT# = 82		Land Item	SCHEDULE: 1 100						
Description =	SALVAGE, STORE AND REINSTALL BRICK PAVER		Unit =	SY	Takeoff Quan:		43.000	Engr Quan:		43.000

082.01 REMOVE BRICK PAVERS **Quan: 43.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>EAS</u>	Earthwork 4 Man Crew		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	4.00 HR	51.051			204		204
8EX100	100 Excavator	1.00	4.00 HR	52.300			209		209
FOCI	Civil Forman	1.00	4.00 MH	77.060	403				403
LAG	General Laborer	2.00	8.00 MH	52.910	558				558
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390				390
\$1,763.87	0.3720 MH/SY		16.00 MH	[26.343]	1,350		413		1,764

082.02 INSTALL BRICK PAVERS **Quan: 43.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408				3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723				723
\$4,130.40	1.1162 MH/SY		48.00 MH	[80.608]	4,130				4,130

====>	Item Totals:	82	- SALVAGE, STORE AND REINSTALL BRICK PAVER							
\$5,894.27	1.4883 MH/SY		64.00 MH	[106.95]	5,481		413			5,894
137.076	43 SY				127.46		9.61			137.08

BID ITEM = 83	CLIENT# = 83		Land Item	SCHEDULE: 1 100						
Description =	REMOVE CURB, GRANITE W/ SALVAGE		Unit =	LF	Takeoff Quan:		690.000	Engr Quan:		690.000

083.01 REMOVE CURB, GRANITE W/ SALVAGE **Quan: 690.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>EAS</u>	Earthwork 4 Man Crew		34.50 CH	Prod:	34.5000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	34.50 HR	51.051			1,761		1,761
8EX100	100 Excavator	1.00	34.50 HR	52.300			1,804		1,804
FOCI	Civil Forman	1.00	34.50 MH	77.060	3,472				3,472
LAG	General Laborer	2.00	69.00 MH	52.910	4,813				4,813
OPE	Operator - Excavator	1.00	34.50 MH	74.560	3,362				3,362
\$15,213.42	0.2000 MH/LF		138.00 MH	[14.159]	11,648		3,566		15,213

====>	Item Totals:	83	- REMOVE CURB, GRANITE W/ SALVAGE							
\$15,213.42	0.2000 MH/LF		138.00 MH	[14.159]	11,648		3,566			15,213
22.048	690 LF				16.88		5.17			22.05

BID ITEM = 84	CLIENT# = 84		Land Item	SCHEDULE: 1 100						
Description =	REMOVE FOUNDATION, BUS SHELTER		Unit =	EA	Takeoff Quan:		5.000	Engr Quan:		5.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 84	CLIENT# = 84		Land Item	SCHEDULE: 1	100					
Description =	REMOVE FOUNDATION, BUS SHELTER		Unit =	EA	Takeoff Quan:		5.000	Engr Quan:		5.000
084.01	REMOVE FOUNDATION, BUS SHELTER	Quan:	5.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>EAS</u>	Earthwork 4 Man Crew	5.00	CH	Prod:	5.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
3DEDU02C	Concrete Trucking and Du	1.00	26.00 TCY	29.000		754			754	
8BA310A	418 Backhoe W/Attachme	1.00	5.00 HR	51.051				255	255	
8EX100	100 Excavator	1.00	5.00 HR	52.300				261	261	
FOCI	Civil Forman	1.00	5.00 MH	77.060	503				503	
LAG	General Laborer	2.00	10.00 MH	52.910	698				698	
OPE	Operator - Excavator	1.00	5.00 MH	74.560	487				487	
\$2,958.83	4.0000 MH/EA	20.00	MH	[283.184]	1,688		754	517		2,959
=====>	Item Totals: 84 - REMOVE FOUNDATION, BUS SHELTER									
\$2,958.83	4.0000 MH/EA	20.00	MH	[283.184]	1,688		754	517		2,959
591.766	5 EA				337.62		150.80	103.35		591.77

BID ITEM = 85	CLIENT# = 85		Land Item	SCHEDULE: 1	100					
Description =	REMOVE FOUNDATION, LITTER RECEPTACLE		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
085.01	REMOVE FOUNDATION, LITTER RECEPTACLE	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>EAS</u>	Earthwork 4 Man Crew	0.50	CH	Prod:	0.5000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	0.50 HR	51.051				26	26	
8EX100	100 Excavator	1.00	0.50 HR	52.300				26	26	
FOCI	Civil Forman	1.00	0.50 MH	77.060	50				50	
LAG	General Laborer	2.00	1.00 MH	52.910	70				70	
OPE	Operator - Excavator	1.00	0.50 MH	74.560	49				49	
\$220.47	2.0000 MH/EA	2.00	MH	[141.59]	169			52		220
=====>	Item Totals: 85 - REMOVE FOUNDATION, LITTER RECEPTACLE									
\$220.47	2.0000 MH/EA	2.00	MH	[141.59]	169			52		220
220.470	1 EA				168.82			51.65		220.47

BID ITEM = 86	CLIENT# = 86		Land Item	SCHEDULE: 1	100					
Description =	REMOVE INTERCONNECT CABLE		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
086.01	REMOVE INTERCONNECT CABLE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	7,580.000				7,580		7,580

BID ITEM = 87	CLIENT# = 87		Land Item	SCHEDULE: 1	100					
Description =	REMOVE STEEL RAILING		Unit =	LF	Takeoff Quan:		28.000	Engr Quan:		28.000
087.01	REMOVE STEEL RAILING	Quan:	28.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>EAS</u>	Earthwork 4 Man Crew	2.00	CH	Prod:	2.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	2.00 HR	51.051				102	102	
8EX100	100 Excavator	1.00	2.00 HR	52.300				105	105	
FOCI	Civil Forman	1.00	2.00 MH	77.060	201				201	
LAG	General Laborer	2.00	4.00 MH	52.910	279				279	
OPE	Operator - Excavator	1.00	2.00 MH	74.560	195				195	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 87	CLIENT# = 87		Land Item	SCHEDULE: 1	100					
Description =	REMOVE STEEL RAILING		Unit =	LF	Takeoff Quan:		28.000	Engr Quan:		28.000
\$881.92	0.2857 MH/LF	8.00 MH	[20.227]	675				207		882
=====> Item Totals: 87 - REMOVE STEEL RAILING										
\$881.92	0.2857 MH/LF	8.00 MH	[20.227]	675				207		882
31.497	28 LF			24.12				7.38		31.50

BID ITEM = 88	CLIENT# = 88		Land Item	SCHEDULE: 1	100					
Description =	REMOVE, STORE AND REINSTALL STEEL RAILIN		Unit =	LF	Takeoff Quan:		73.000	Engr Quan:		73.000
088.01	REMOVE AND STOR STEEL RAILING		Quan:	73.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		2.00 CH	Prod:	2.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	2.00 HR	51.051				102		102
8EX100	100 Excavator	1.00	2.00 HR	52.300				105		105
FOCI	Civil Forman	1.00	2.00 MH	77.060	201					201
LAG	General Laborer	2.00	4.00 MH	52.910	279					279
OPE	Operator - Excavator	1.00	2.00 MH	74.560	195					195
\$881.92	0.1095 MH/LF	8.00 MH	[7.758]	675				207		882
088.02	INSTALL STEEL RAILING		Quan:	73.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZZ</u>	SITE FURNISHINGS CREW		6.00 CH	Prod:	6.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
LAG	General Laborer	2.00	12.00 MH	52.910	837					837
\$837.12	0.1643 MH/LF	12.00 MH	[9.567]	837						837
=====> Item Totals: 88 - REMOVE, STORE AND REINSTALL STEEL RAILIN										
\$1,719.04	0.2739 MH/LF	20.00 MH	[17.326]	1,512				207		1,719
23.548	73 LF			20.72				2.83		23.55

BID ITEM = 89	CLIENT# = 89		Land Item	SCHEDULE: 1	100					
Description =	REMOVE, STORE AND REINSTALL 18"-HIGH DEC		Unit =	LF	Takeoff Quan:		65.000	Engr Quan:		65.000
089.01	REMOVE AND STOR DECRATIVE FENCE		Quan:	65.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		2.00 CH	Prod:	2.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	2.00 HR	51.051				102		102
8EX100	100 Excavator	1.00	2.00 HR	52.300				105		105
FOCI	Civil Forman	1.00	2.00 MH	77.060	201					201
LAG	General Laborer	2.00	4.00 MH	52.910	279					279
OPE	Operator - Excavator	1.00	2.00 MH	74.560	195					195
\$881.92	0.1230 MH/LF	8.00 MH	[8.713]	675				207		882
089.02	INSTALL DECROTIVE FENCE		Quan:	65.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZZ</u>	SITE FURNISHINGS CREW		6.00 CH	Prod:	6.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
LAG	General Laborer	2.00	12.00 MH	52.910	837					837
\$837.12	0.1846 MH/LF	12.00 MH	[10.745]	837						837
=====> Item Totals: 89 - REMOVE, STORE AND REINSTALL 18"-HIGH DEC										
\$1,719.04	0.3076 MH/LF	20.00 MH	[19.458]	1,512				207		1,719
26.447	65 LF			23.27				3.18		26.45

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract
									Total

BID ITEM = **90** CLIENT# = 90 Land Item SCHEDULE: 1 100
Description = REMOVE PONY BAR FENCE Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

090.01 REMOVE PONY BAR FENCE Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		8.00	CH	Prod:	8.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
3PFENCEDIS	DISOSE PONY BAR FEN	1.00	1.00	LS	1,000.000			1,000			1,000
8BA310A	418 Backhoe W/Attachme	1.00	8.00	HR	51.051				408		408
8EX100	100 Excavator	1.00	8.00	HR	52.300				418		418
FOCI	Civil Forman	1.00	8.00	MH	77.060	805					805
LAG	General Laborer	2.00	16.00	MH	52.910	1,116					1,116
OPE	Operator - Excavator	1.00	8.00	MH	74.560	780					780
\$4,527.75	32.0000 MH/LS		32.00	MH	[2265.48]	2,701		1,000	827		4,528

=====> **Item Totals: 90 - REMOVE PONY BAR FENCE**
 \$4,527.75 32.0000 MH/LS 32.00 MH [2265.48] 2,701 1,000 827 **4,528**
 4,527.750 1 LS 2,700.95 1,000.00 826.80 4,527.75

BID ITEM = **91** CLIENT# = 91 Land Item SCHEDULE: 1 100
Description = REMOVE SCL VAULT LID AND RISERS Unit = EA Takeoff Quan: 3.000 Engr Quan: 3.000

091.01 REMOVE SCL VAULT LID AND RISERS Quan: 3.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		8.00	CH	Prod:	8.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	8.00	HR	51.051				408		408
8EX100	100 Excavator	1.00	8.00	HR	52.300				418		418
FOCI	Civil Forman	1.00	8.00	MH	77.060	805					805
LAG	General Laborer	2.00	16.00	MH	52.910	1,116					1,116
OPE	Operator - Excavator	1.00	8.00	MH	74.560	780					780
\$3,527.75	10.6666 MH/EA		32.00	MH	[755.16]	2,701			827		3,528

=====> **Item Totals: 91 - REMOVE SCL VAULT LID AND RISERS**
 \$3,527.75 10.6666 MH/EA 32.00 MH [755.16] 2,701 827 **3,528**
 1,175.917 3 EA 900.32 275.60 1,175.92

BID ITEM = **92** CLIENT# = 92 Land Item SCHEDULE: 1 100
Description = ABANDON MONITORING WELL Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

092.01 ABANDON MONITORING WELL Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		4.00	CH	Prod:	4.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2AGS07	SEATTLE TYPE 7@110.2	1.00	5.00	TON	29.750		164				164
8BA310A	418 Backhoe W/Attachme	1.00	4.00	HR	51.051				204		204
8EX100	100 Excavator	1.00	4.00	HR	52.300				209		209
FOCI	Civil Forman	1.00	4.00	MH	77.060	403					403
LAG	General Laborer	2.00	8.00	MH	52.910	558					558
OPE	Operator - Excavator	1.00	4.00	MH	74.560	390					390
\$1,927.87	16.0000 MH/EA		16.00	MH	[1132.73]	1,350	164		413		1,928

=====> **Item Totals: 92 - ABANDON MONITORING WELL**
 \$1,927.87 16.0000 MH/EA 16.00 MH [1132.73] 1,350 164 **1,928**
 1,927.870 1 EA 1,350.47 164.00 413.40 1,927.87

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract

BID ITEM = **93** CLIENT# = 93 Land Item SCHEDULE: 1 100
Description = REMOVE TREE GRATE Unit = EA Takeoff Quan: 21.000 Engr Quan: 21.000

093.01 REMOVE TREE GRATE Quan: 21.00 EA Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		5.00	CH	Prod:	5.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	5.00	HR	51.051				255		255
8EX100	100 Excavator	1.00	5.00	HR	52.300				261		261
FOCI	Civil Forman	1.00	5.00	MH	77.060	503					503
LAG	General Laborer	2.00	10.00	MH	52.910	698					698
OPE	Operator - Excavator	1.00	5.00	MH	74.560	487					487
\$2,204.83	0.9523 MH/EA		20.00	MH	[67.425]	1,688			517		2,205

=====> **Item Totals: 93 - REMOVE TREE GRATE**
 \$2,204.83 0.9523 MH/EA 20.00 MH [67.425] 1,688 517 **2,205**
 104.992 21 EA 80.39 24.61 104.99

BID ITEM = **94** CLIENT# = 94 Land Item SCHEDULE: 1 100
Description = REMOVE AND SALVAGE WATER FOUNTAIN Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

094.01 REMOVE AND SALVAGE WATER FOUNTAIN Quan: 1.00 EA Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		4.00	CH	Prod:	4.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	4.00	HR	51.051				204		204
8EX100	100 Excavator	1.00	4.00	HR	52.300				209		209
FOCI	Civil Forman	1.00	4.00	MH	77.060	403					403
LAG	General Laborer	2.00	8.00	MH	52.910	558					558
OPE	Operator - Excavator	1.00	4.00	MH	74.560	390					390
\$1,763.87	16.0000 MH/EA		16.00	MH	[1132.73]	1,350			413		1,764

=====> **Item Totals: 94 - REMOVE AND SALVAGE WATER FOUNTAIN**
 \$1,763.87 16.0000 MH/EA 16.00 MH [1132.73] 1,350 413 **1,764**
 1,763.870 1 EA 1,350.47 413.40 1,763.87

BID ITEM = **95** CLIENT# = 95 Land Item SCHEDULE: 1 100
Description = REMOVE WATER METER BOX Unit = EA Takeoff Quan: 4.000 Engr Quan: 4.000

095.01 REMOVE WATER METER BOX Quan: 4.00 EA Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		1.00	CH	Prod:	1.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	1.00	HR	51.051				51		51
8EX100	100 Excavator	1.00	1.00	HR	52.300				52		52
FOCI	Civil Forman	1.00	1.00	MH	77.060	101					101
LAG	General Laborer	2.00	2.00	MH	52.910	140					140
OPE	Operator - Excavator	1.00	1.00	MH	74.560	97					97
\$440.95	1.0000 MH/EA		4.00	MH	[70.798]	338			103		441

=====> **Item Totals: 95 - REMOVE WATER METER BOX**
 \$440.95 1.0000 MH/EA 4.00 MH [70.798] 338 103 **441**
 110.238 4 EA 84.41 25.83 110.24

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
-------------------	------	-----	---------------	-----------	-------	---------------	-----------------	------------	--------------	-------

BID ITEM = **96** CLIENT# = 96 Land Item SCHEDULE: 1 100
Description = REMOVE BUTTERFLY VALVE Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

096.01 REMOVE BUTTERFLY VALVE Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		1.00 CH	Prod:	1.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
8EX135A	135 Excavator W/Attach	1.00	1.00 HR	68.251				68	68
8EX200	200 Excavator	1.00	1.00 HR	78.000				78	78
8LO950	950 Loader	1.00	1.00 HR	81.500				81	81
FOCI	Civil Forman	1.00	1.00 MH	77.060	101				101
LAP	Labor Underground Water	2.00	2.00 MH	53.880	142				142
OPE	Operator - Excavator	1.00	1.00 MH	74.560	97				97
OPL	Operator - Loader	1.00	1.00 MH	74.560	97				97
\$665.29	5.0000 MH/EA		5.00 MH	[367.35]	438			228	665

====> **Item Totals: 96 - REMOVE BUTTERFLY VALVE**
\$665.29 5.0000 MH/EA 5.00 MH [367.35] 438 228 **665**
665.290 1 EA 437.56 227.73 665.29

BID ITEM = **97** CLIENT# = 97 Land Item SCHEDULE: 1 100
Description = ABANDON VALVE VAULT Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

097.01 ABANDON VALVE VAULT Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		1.00 CH	Prod:	1.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2AGS17	SEATTLE TYPE 1@110.2	1.00	5.00 TON	25.750	142				142
8EX135A	135 Excavator W/Attach	1.00	1.00 HR	68.251				68	68
8EX200	200 Excavator	1.00	1.00 HR	78.000				78	78
8LO950	950 Loader	1.00	1.00 HR	81.500				81	81
FOCI	Civil Forman	1.00	1.00 MH	77.060	101				101
LAP	Labor Underground Water	2.00	2.00 MH	53.880	142				142
OPE	Operator - Excavator	1.00	1.00 MH	74.560	97				97
OPL	Operator - Loader	1.00	1.00 MH	74.560	97				97
\$807.24	5.0000 MH/EA		5.00 MH	[367.35]	438	142		228	807

====> **Item Totals: 97 - ABANDON VALVE VAULT**
\$807.24 5.0000 MH/EA 5.00 MH [367.35] 438 142 228 **807**
807.240 1 EA 437.56 141.95 227.73 807.24

BID ITEM = **98** CLIENT# = 98 Land Item SCHEDULE: 1 100
Description = REMOVE AND DISPOSE POLE, METAL STRAIN Unit = EA Takeoff Quan: 12.000 Engr Quan: 12.000

098.01 REMOVE AND DISPOSE POLE, METAL STRAIN Quan: 12.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4ELEC	Electrical sub	1.00	12.00 EA	2,650.000				31,800	31,800
-------	----------------	------	----------	-----------	--	--	--	--------	--------

BID ITEM = **99** CLIENT# = 99 Land Item SCHEDULE: 1 100
Description = COMMON EXCAVATION Unit = CY Takeoff Quan: 11,277.000 Engr Quan: 11,277.000

099.01 COMMON EXCAVATION Quan: 11,277.00 CY Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>GRM</u>	Grading 5 Man Crew		422.22 CH	Prod:	422.2262 CH	Lab Pcs:	5.00	Eqp Pcs:	4.00
3DEDU02D	Dirt Trucking and Dump	1.00	14,762.56 TCY	24.500		361,683			361,683

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 99	CLIENT# = 99									
Description =	COMMON EXCAVATION		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	11,277.000	Engr Quan:	11,277.000		
8DO0450	JD 450 Dozer	1.00	422.23 HR	49.500				20,900		20,900
8EX135A	135 Excavator W/Attach	1.00	422.23 HR	68.251				28,818		28,818
8EX200	200 Excavator	1.00	422.23 HR	78.000				32,934		32,934
8RO84	84 Inch Roller	1.00	422.23 HR	55.700				23,518		23,518
FOCI	Civil Forman	1.00	422.23 MH	77.060	45,020					45,020
LAG	General Laborer	2.00	844.45 MH	52.910	62,374					62,374
OPE	Operator - Excavator	2.00	844.45 MH	74.560	87,175					87,175
\$662,421.12	0.1872 MH/CY		2,111.13 MH	[14.503]	194,568		361,683	106,170		662,421
====> Item Totals: 99 - COMMON EXCAVATION										
\$662,421.12	0.1872 MH/CY		2,111.13 MH	[14.503]	194,568		361,683	106,170		662,421
58.741	11277 CY				17.25		32.07	9.41		58.74

BID ITEM = 100	CLIENT# = 100									
Description =	UTILITY VERIFICATION EXCAVATION. 10 FT D		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	153.000	Engr Quan:	153.000		

100.01 UTILITY VERIFICATION EXCAVATION. 10 FT D Quan: 153.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4ELEC	Electrical sub	1.00	153.00 EA	3,000.000				459,000		459,000
-------	----------------	------	-----------	-----------	--	--	--	---------	--	---------

BID ITEM = 101	CLIENT# = 101									
Description =	UTILITY VERIFICATION EXCAVATION. 5 FT DE		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	11.000	Engr Quan:	11.000		

101.01 UTILITY VERIFICATION EXCAVATION. 5 FT DE Quan: 11.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4ELEC	Electrical sub	1.00	11.00 EA	2,250.000				24,750		24,750
-------	----------------	------	----------	-----------	--	--	--	--------	--	--------

BID ITEM = 102	CLIENT# = 102									
Description =	SAFETY SYSTEMS IN TRENCH EXCAVATION, MIN		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	37,667.000	Engr Quan:	37,667.000		

102.01 SAFETY SYSTEMS IN TRENCH EXCAVATION, M Quan: 37,717.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

3SHORETREN	TRENCH SHORING	1.00	1.00 LS	100,000.000			100,000			100,000
------------	----------------	------	---------	-------------	--	--	---------	--	--	---------

====> Item Totals: 102 - SAFETY SYSTEMS IN TRENCH EXCAVATION, MIN										
\$100,000.00				[]			100,000			100,000
2.655	37667 SF						2.65			2.65

BID ITEM = 103	CLIENT# = 103									
Description =	SUPPORT AND SAFETY SYSTEM		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	1,515.000	Engr Quan:	1,515.000		

103.01 SLIDE RAIL RENT Quan: 1,515.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

3SHORESOLDI	SOILDER PILE SHORING	1.00	1,515.00 SF	24.000			36,360			36,360
-------------	----------------------	------	-------------	--------	--	--	--------	--	--	--------

103.02 INSTALL SLIDE RAIL Quan: 1,515.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

UNM	Underground Utilities 6 Man		40.00 CH	Prod: 40.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00		
8EX135A	135 Excavator W/Attach	1.00	40.00 HR	68.251		2,730		2,730		

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 103	CLIENT# = 103									
Description =	SUPPORT AND SAFETY SYSTEM			Land Item Unit =	SCHEDULE: 1 100					
					SF Takeoff Quan:	1,515.000		Engr Quan:		1,515.000
8EX200	200 Excavator	1.00	40.00 HR	78.000				3,120		3,120
8LO950	950 Loader	1.00	40.00 HR	81.500				3,260		3,260
FOCI	Civil Forman	1.00	40.00 MH	77.060	4,026					4,026
LAP	Labor Underground Water	2.00	80.00 MH	53.880	5,680					5,680
OPE	Operator - Excavator	1.00	40.00 MH	74.560	3,898					3,898
OPL	Operator - Loader	1.00	40.00 MH	74.560	3,898					3,898
\$26,612.01	0.1320 MH/SF		200.00 MH	[9.699]	17,502			9,110		26,612
103.03	REMOVE SLIDE RAIL			Quan:	1,515.00 SF	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>UNM</u>	Underground Utilities 6 Man		20.00 CH	Prod:	20.0000 CH	Lab Pcs:	5.00	Eqp Pcs:		3.00
8EX135A	135 Excavator W/Attach	1.00	20.00 HR	68.251				1,365		1,365
8EX200	200 Excavator	1.00	20.00 HR	78.000				1,560		1,560
8LO950	950 Loader	1.00	20.00 HR	81.500				1,630		1,630
FOCI	Civil Forman	1.00	20.00 MH	77.060	2,013					2,013
LAP	Labor Underground Water	2.00	40.00 MH	53.880	2,840					2,840
OPE	Operator - Excavator	1.00	20.00 MH	74.560	1,949					1,949
OPL	Operator - Loader	1.00	20.00 MH	74.560	1,949					1,949
\$13,306.01	0.0660 MH/SF		100.00 MH	[4.849]	8,751			4,555		13,306
=====>	Item Totals:	103	- SUPPORT AND SAFETY SYSTEM							
\$76,278.02	0.1980 MH/SF		300.00 MH	[14.548]	26,253		36,360	13,665		76,278
50.349	1515 SF				17.33		24.00	9.02		50.35
BID ITEM = 104	CLIENT# = 104									
Description =	UTILITY CROSSING SUPPORT IN TRENCH			Land Item Unit =	SCHEDULE: 1 100					
					LS Takeoff Quan:	1.000		Engr Quan:		1.000
104.01	UTILITY CROSSING SUPPORT IN TRENCH			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
3SHORUTSU	UTILITY SUPPORT	1.00	1.00 LS	1,500.000			1,500			1,500
=====>	Item Totals:	104	- UTILITY CROSSING SUPPORT IN TRENCH							
\$1,500.00				[]			1,500			1,500
1,500.000	1 LS						1,500.00			1,500.00
BID ITEM = 105	CLIENT# = 105									
Description =	DEWATERING			Land Item Unit =	SCHEDULE: 1 100					
					FA Takeoff Quan:	100,000.000		Engr Quan:		100,000.000
105.01	DEWATERING			Quan:	100,000.00 FA	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
9FORCE	FORCE ACCOUNT	1.00	100,000.00 FA	0.890			89,000			89,000
=====>	Item Totals:	105	- DEWATERING							
\$89,000.00				[]			89,000			89,000
0.890	100000 FA						0.89			0.89
BID ITEM = 106	CLIENT# = 106									
Description =	CONTROLLED DENSITY FILL			Land Item Unit =	SCHEDULE: 1 100					
					CY Takeoff Quan:	50.000		Engr Quan:		50.000
106.01	CONTROLLED DENSITY FILL			Quan:	50.00 CY	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 106	CLIENT# = 106									
Description =	CONTROLLED DENSITY FILL		Land Item Unit =	SCHEDULE: 1 100						
				CY	Takeoff Quan:		50.000	Engr Quan:		50.000
<u>UNM</u>	Underground Utilities 6 Man		5.00 CH	Prod:	5.0000 CH	Lab Pcs:		5.00	Eqp Pcs:	3.00
2CRCDF	CDF@110.25%	1.00	50.00 CY	106.150		5,852				5,852
3DEDU02D	Dirt Trucking and Dump	1.00	60.00 TCY	24.500			1,470			1,470
8EX135A	135 Excavator W/Attach	1.00	5.00 HR	68.251				341		341
8EX200	200 Excavator	1.00	5.00 HR	78.000				390		390
8LO950	950 Loader	1.00	5.00 HR	81.500				407		407
FOCI	Civil Forman	1.00	5.00 MH	77.060	503					503
LAP	Labor Underground Water	2.00	10.00 MH	53.880	710					710
OPE	Operator - Excavator	1.00	5.00 MH	74.560	487					487
OPL	Operator - Loader	1.00	5.00 MH	74.560	487					487
\$10,648.01	0.5000 MH/CY		25.00 MH	[36.733]	2,188	5,852	1,470	1,139		10,648
=====> Item Totals: 106 - CONTROLLED DENSITY FILL										
\$10,648.01	0.5000 MH/CY		25.00 MH	[36.733]	2,188	5,852	1,470	1,139		10,648
212.960	50 CY				43.76	117.03	29.40	22.77		212.96

BID ITEM = 107	CLIENT# = 107									
Description =	MINERAL AGGREGATE, TYPE 2		Land Item Unit =	SCHEDULE: 1 100						
				TN	Takeoff Quan:		19,931.000	Engr Quan:		19,931.000
107.01	MINERAL AGGREGATE, TYPE 2			Quan: 19,931.00 TN	Hrs/Shft: 10.00	Cal: 610	WC: WAAVG			
<u>GRM</u>	Grading 5 Man Crew		711.34 CH	Prod:	711.3462 CH	Lab Pcs:		5.00	Eqp Pcs:	4.00
2AGS02	SEATTLE TYPE 2@110.2	1.00	19,931.00 TON	29.750		653,724				653,724
8DO0450	JD 450 Dozer	1.00	711.35 HR	49.500				35,212		35,212
8EX135A	135 Excavator W/Attach	1.00	711.35 HR	68.251				48,550		48,550
8EX200	200 Excavator	1.00	711.35 HR	78.000				55,485		55,485
8RO84	84 Inch Roller	1.00	711.35 HR	55.700				39,622		39,622
FOCI	Civil Forman	1.00	711.35 MH	77.060	75,847					75,847
LAG	General Laborer	2.00	1,422.69 MH	52.910	105,085					105,085
OPE	Operator - Excavator	2.00	1,422.69 MH	74.560	146,868					146,868
\$1,160,393.18	0.1784 MH/TN		3,556.73 MH	[13.824]	327,799	653,724		178,870		1,160,393
=====> Item Totals: 107 - MINERAL AGGREGATE, TYPE 2										
\$1,160,393.18	0.1784 MH/TN		3,556.73 MH	[13.824]	327,799	653,724		178,870		1,160,393
58.221	19931 TN				16.45	32.80		8.97		58.22

BID ITEM = 108	CLIENT# = 108									
Description =	MINERAL AGGREGATE, TYPE 17		Land Item Unit =	SCHEDULE: 1 100						
				TN	Takeoff Quan:		7,568.000	Engr Quan:		7,568.000
108.01	MINERAL AGGREGATE, TYPE 17			Quan: 7,568.00 TN	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
2AGS17	SEATTLE TYPE 1@110.2	1.00	7,568.00 TON	25.750		214,851				214,851
3DEDU02D	Dirt Trucking and Dump	1.00	6,054.19 TCY	24.500			148,328			148,328
\$363,178.45				[]		214,851	148,328			363,178
=====> Item Totals: 108 - MINERAL AGGREGATE, TYPE 17										
\$363,178.45				[]		214,851	148,328			363,178
47.989	7568 TN					28.39	19.60			47.99

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 109 CLIENT# = 109 Land Item SCHEDULE: 1 100
Description = MINERAL AGGREGATE, TYPE 9 Unit = CY Takeoff Quan: 32.000 Engr Quan: 32.000

109.01 MINERAL AGGREGATE, TYPE 9 Quan: 32.00 CY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		5.00	CH	Prod:	5.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2AGS09	SEATTLE TYPE 9@110.2	1.00	55.17	TON			1,810				1,810
8BA310A	418 Backhoe W/Attachme	1.00	5.00	HR					255		255
8EX100	100 Excavator	1.00	5.00	HR					261		261
FOCI	Civil Forman	1.00	5.00	MH			503				503
LAG	General Laborer	2.00	10.00	MH			698				698
OPE	Operator - Excavator	1.00	5.00	MH			487				487
\$4,014.37	0.6250 MH/CY		20.00	MH	[44.248]		1,688	1,810		517	4,014

====> **Item Totals: 109 - MINERAL AGGREGATE, TYPE 9**
 \$4,014.37 0.6250 MH/CY 20.00 MH [44.248] 1,688 1,810 517 **4,014**
 125.449 32 CY 52.75 56.55 16.15 125.45

BID ITEM = 110 CLIENT# = 110 Land Item SCHEDULE: 1 100
Description = SURFACE PREP, PRELEVEL Unit = TN Takeoff Quan: 49.000 Engr Quan: 49.000

110.01 SURFACE PREP, PRELEVEL Quan: 49.00 TN Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4ASPH	Asphalt Paving sub	1.00	49.00	TN		195.000				9,555	9,555
-------	--------------------	------	-------	----	--	---------	--	--	--	-------	-------

BID ITEM = 111 CLIENT# = 111 Land Item SCHEDULE: 1 100
Description = SURFACE PREP, PLANE BITUMINOUS PAVEMENT Unit = SY Takeoff Quan: 14,240.000 Engr Quan: 14,240.000

111.01 SURFACE PREP, PLANE BITUMINOUS PAVEME Quan: 14,240.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		22.03	CH	Prod:	22.0348	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
3DEDU02A	Asphalt trucking and Dump	1.00	1,457.97	TCY		29.000		42,281			42,281
4MILL	Milling Sub	1.00	14,240.00	SY		2.000				28,480	28,480
8BA310A	418 Backhoe W/Attachme	1.00	22.03	HR		51.051			1,125		1,125
8EX100	100 Excavator	1.00	22.03	HR		52.300			1,152		1,152
FOCI	Civil Forman	1.00	22.03	MH		77.060	2,217				2,217
LAG	General Laborer	2.00	44.07	MH		52.910	3,074				3,074
OPE	Operator - Excavator	1.00	22.03	MH		74.560	2,147				2,147
\$80,476.36	0.0061 MH/SY		88.13	MH	[0.438]	7,438		42,281	2,277	28,480	80,476

====> **Item Totals: 111 - SURFACE PREP, PLANE BITUMINOUS PAVEMENT**
 \$80,476.36 0.0061 MH/SY 88.13 MH [0.438] 7,438 42,281 2,277 28,480 **80,476**
 5.651 14240 SY 0.52 2.97 0.16 2.00 5.65

BID ITEM = 112 CLIENT# = 112 Land Item SCHEDULE: 1 100
Description = PAVEMENT, WMA (CL 1/2 IN) Unit = TN Takeoff Quan: 3,942.000 Engr Quan: 3,942.000

112.01 PAVEMENT, WMA (CL 1/2 IN) Quan: 3,942.00 TN Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		37.88	CH	Prod:	37.8856	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
4ASPH	Asphalt Paving sub	1.00	3,942.00	TN		162.000				638,604	638,604
8BA310A	418 Backhoe W/Attachme	1.00	37.89	HR		51.051			1,934		1,934
8EX100	100 Excavator	1.00	37.89	HR		52.300			1,982		1,982

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 112	CLIENT# = 112									
Description =	PAVEMENT, WMA (CL 1/2 IN)		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	3,942.000		Engr Quan:	3,942.000	
FOCI	Civil Forman	1.00	37.89 MH	77.060	3,814					3,814
LAG	General Laborer	2.00	75.77 MH	52.910	5,286					5,286
OPE	Operator - Excavator	1.00	37.89 MH	74.560	3,692					3,692
\$655,311.60	0.0384 MH/TN		151.55 MH	[2.722]	12,792			3,916	638,604	655,312
====> Item Totals:	112 - PAVEMENT, WMA (CL 1/2 IN)									
\$655,311.60	0.0384 MH/TN		151.55 MH	[2.722]	12,792			3,916	638,604	655,312
166.238	3942 TN				3.24			0.99	162.00	166.24

BID ITEM = 113	CLIENT# = 113									
Description =	PAVEMENT PATCH, TEMPORARY		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	1,066.000		Engr Quan:	1,066.000	
113.01	PAVEMENT PATCH, TEMPORARY		Quan: 1,066.00 TN	Hrs/Shft: 10.00	Cal: X10	WC: WAAVG				
EAS	Earthwork 4 Man Crew		177.11 CH	Prod: 177.1166 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00		
3COLDMIX	COLD MIX	1.00	1,066.00 TN	110.000	117,260			117,260		
3DEDU02A	Asphalt trucking and Dump	1.00	1,023.10 TCY	29.000	29,670			29,670		
8BA310A	418 Backhoe W/Attachme	1.00	177.12 HR	51.051			9,042	9,042		
8EX100	100 Excavator	1.00	177.12 HR	52.300			9,263	9,263		
FOCI	Civil Forman	1.00	177.12 MH	77.060	32,109			32,109		
LAG	General Laborer	2.00	354.23 MH	52.910	44,324			44,324		
OPE	Operator - Excavator	1.00	177.12 MH	74.560	31,080			31,080		
\$272,747.93	0.6646 MH/TN		708.47 MH	[85.548]	107,513	146,930	18,306	272,748		
====> Item Totals:	113 - PAVEMENT PATCH, TEMPORARY									
\$272,747.93	0.6646 MH/TN		708.47 MH	[85.548]	107,513	146,930	18,306	272,748		
255.861	1066 TN				100.86	137.83	17.17	255.86		

BID ITEM = 114	CLIENT# = 114									
Description =	ROADWAY CEM CONC, VARIABLE MIXES, 12 IN		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	30,990.000		Engr Quan:	30,990.000	
114.01	ROADWAY CEM CONC, VARIABLE MIXES, 12 IN		Quan: 30,990.00 SY	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
COL	Concrete 9 Man Crew		1,652.00 CH	Prod: 1,652.0000 CH	Lab Pcs:	9.00	Eqp Pcs:	0.00		
2CRP3D	3 DAY PAVING M@110.2	1.02	10,536.60 CY	125.150	1,453,818			1,453,818		
2DOWEL	DOWELS@110.25%	1.00	31,180.00 LF	15.750	541,421			541,421		
2JOINT	JOINT MATERIAL@110.2	1.00	14,058.00 LF	2.750	42,622			42,622		
2TIEBAR	TIE BARS@110.25%	1.00	4,686.00 EA	2.940	15,189			15,189		
3SAWSEAL	SAWING AND SEALING	1.00	30,990.00 LF	3.680		114,043		114,043		
CEJ	Cement Mason	8.00	13,216.00 MH	64.980	1,125,970			1,125,970		
FOCO	Concrete Forman	1.00	1,652.00 MH	68.980	149,198			149,198		
\$3,442,260.59	0.4797 MH/SY		14,868.00 MH	[34.527]	1,275,167	2,053,050	114,043	3,442,261		
====> Item Totals:	114 - ROADWAY CEM CONC, VARIABLE MIXES, 12 IN									
\$3,442,260.59	0.4797 MH/SY		14,868.00 MH	[34.527]	1,275,167	2,053,050	114,043	3,442,261		
111.076	30990 SY				41.15	66.25	3.68	111.08		

BID ITEM = 115	CLIENT# = 115									
Description =	ROADWAY CEM CONC, HES (24 HR), 12 IN		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	23,997.000		Engr Quan:	23,997.000	

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment Contract	

BID ITEM = 115 CLIENT# = 115 Land Item SCHEDULE: 1 100
Description = ROADWAY CEM CONC, HES (24 HR), 12 IN Unit = SY Takeoff Quan: 23,997.000 Engr Quan: 23,997.000

115.01 ROADWAY CEM CONC, HES (24 HR), 12 IN Quan: 23,997.00 SY Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>COL</u>	Concrete 9 Man Crew		1,279.00	CH	Prod: 1,279.0000 CH	Lab Pcs:	9.00	Eqp Pcs:	0.00
2CRP1D	1 DAY PAVING M@110.2	1.02	8,158.29	CY	187.150	1,683,323			1,683,323
2DOWEL	DOWELS@110.25%	1.00	24,144.00	LF	15.750	419,245			419,245
2TIEBAR	TIE BARS@110.25%	1.00	3,628.00	SY	2.940	11,760			11,760
3SAWSEAL	SAWING AND SEALING	1.00	24,144.00	LF	3.680		88,850		88,850
CEJ	Cement Mason	8.00	10,232.00	MH	64.980	1,180,961			1,180,961
FOCO	Concrete Forman	1.00	1,279.00	MH	68.980	156,543			156,543
\$3,540,681.84	0.4796 MH/SY		11,511.00	MH	[47.075]	1,337,503	2,114,329	88,850	3,540,682

=====> **Item Totals: 115 - ROADWAY CEM CONC, HES (24 HR), 12 IN**
 \$3,540,681.84 0.4796 MH/SY 11,511.00 MH [47.075] 1,337,503 2,114,329 88,850 **3,540,682**
 147.547 23997 SY 55.74 88.11 3.70 147.55

BID ITEM = 116 CLIENT# = 116 Land Item SCHEDULE: 1 100
Description = ROADWAY CEM CONC BASE, VARIABLE MIXES, 1 Unit = SY Takeoff Quan: 2,045.000 Engr Quan: 2,045.000

116.01 ROADWAY CEM CONC BASE, VARIABLE MIXES Quan: 2,045.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COL</u>	Concrete 9 Man Crew		109.00	CH	Prod: 109.0000 CH	Lab Pcs:	9.00	Eqp Pcs:	0.00
2CRP3D	3 DAY PAVING M@110.2	1.02	576.15	CY	125.150	79,496			79,496
2DOWEL	DOWELS@110.25%	1.00	2,057.00	LF	15.750	35,719			35,719
2JOINT	JOINT MATERIAL@110.2	1.00	2,985.00	LF	2.750	9,050			9,050
2TIEBAR	TIE BARS@110.25%	1.00	309.00	EA	2.940	1,002			1,002
CEJ	Cement Mason	8.00	872.00	MH	64.980	74,292			74,292
FOCO	Concrete Forman	1.00	109.00	MH	68.980	9,844			9,844
\$209,402.55	0.4797 MH/SY		981.00	MH	[34.523]	84,136	125,266		209,403

=====> **Item Totals: 116 - ROADWAY CEM CONC BASE, VARIABLE MIXES, 1**
 \$209,402.55 0.4797 MH/SY 981.00 MH [34.523] 84,136 125,266 **209,403**
 102.397 2045 SY 41.14 61.25 102.40

BID ITEM = 117 CLIENT# = 117 Land Item SCHEDULE: 1 100
Description = ROADWAY CEM CONC BASE, HES (24 HR), 10 I Unit = SY Takeoff Quan: 1,730.000 Engr Quan: 1,730.000

117.01 ROADWAY CEM CONC BASE, HES (24 HR), 10 I Quan: 1,730.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COL</u>	Concrete 9 Man Crew		92.00	CH	Prod: 92.0000 CH	Lab Pcs:	9.00	Eqp Pcs:	0.00
2CRP1D	1 DAY PAVING M@110.2	1.02	473.01	CY	187.150	97,598			97,598
2DOWEL	DOWELS@110.25%	1.00	1,740.00	LF	15.750	30,214			30,214
2JOINT	JOINT MATERIAL@110.2	1.00	2,525.00	LF	2.750	7,655			7,655
2TIEBAR	TIE BARS@110.25%	1.00	261.00	EA	2.940	846			846
CEJ	Cement Mason	8.00	736.00	MH	64.980	62,705			62,705
FOCO	Concrete Forman	1.00	92.00	MH	68.980	8,309			8,309
\$207,327.16	0.4786 MH/SY		828.00	MH	[34.444]	71,014	136,313		207,327

=====> **Item Totals: 117 - ROADWAY CEM CONC BASE, HES (24 HR), 10 I**
 \$207,327.16 0.4786 MH/SY 828.00 MH [34.444] 71,014 136,313 **207,327**
 119.842 1730 SY 41.05 78.79 119.84

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM	= 118	CLIENT# = 118	Land Item	SCHEDULE: 1	100					
Description =	PCCP PANEL DIAMOND GRIND		Unit =	FA	Takeoff Quan:	20,000.000		Engr Quan:	20,000.000	
118.01	PCCP PANEL DIAMOND GRIND			Quan:	20,000.00 FA	Hrs/Shift:	10.00	Cal:	510	WC: WAAVG
9FORCE	FORCE ACCOUNT	1.00	20,000.00 FA	0.890			17,800			17,800
====>	Item Totals:	118	- PCCP PANEL DIAMOND GRIND							
\$17,800.00				[]			17,800			17,800
0.890		20000 FA					0.89			0.89
BID ITEM	= 119	CLIENT# = 119	Land Item	SCHEDULE: 1	100					
Description =	PCCP PANEL REINFORCING		Unit =	EA	Takeoff Quan:	916.000		Engr Quan:	916.000	
119.01	PCCP PANEL REINFORCING			Quan:	916.00 EA	Hrs/Shift:	10.00	Cal:	510	WC: WAAVG
<u>COL</u>	Concrete 9 Man Crew	152.34	CH	Prod:	152.3473 CH	Lab Pcs:	9.00	Eqp Pcs:	0.00	
2RB05	#5 Rebar@110.25%	1.00	225,336.00 LF	1.000		248,433				248,433
CEJ	Cement Mason	8.00	1,218.78 MH	64.980	103,837					103,837
FOCO	Concrete Forman	1.00	152.35 MH	68.980	13,759					13,759
\$366,029.15	1.4968 MH/EA	1,371.13 MH		[107.725]	117,596	248,433				366,029
====>	Item Totals:	119	- PCCP PANEL REINFORCING							
\$366,029.15	1.4968 MH/EA	1,371.13 MH		[107.725]	117,596	248,433				366,029
399.595	916 EA				128.38	271.22				399.60
BID ITEM	= 120	CLIENT# = 120	Land Item	SCHEDULE: 1	100					
Description =	AREAWAY PROTECTION ZONE 1		Unit =	EA	Takeoff Quan:	1.000		Engr Quan:	1.000	
120.01	AREAWAY PROTECTION ZONE 1			Quan:	1.00 EA	Hrs/Shift:	10.00	Cal:	510	WC: WAAVG
3AREAWAY	AREA WAY PROTECTIO	1.00	1.00 LS	26,000.000			26,000			26,000
====>	Item Totals:	120	- AREAWAY PROTECTION ZONE 1							
\$26,000.00				[]			26,000			26,000
26,000.000		1 EA					26,000.00			26,000.00
BID ITEM	= 121	CLIENT# = 121	Land Item	SCHEDULE: 1	100					
Description =	AREAWAY PROTECTION ZONE 2		Unit =	EA	Takeoff Quan:	1.000		Engr Quan:	1.000	
121.01	AREAWAY PROTECTION ZONE 2			Quan:	1.00 EA	Hrs/Shift:	10.00	Cal:	510	WC: WAAVG
3AREAWAY	AREA WAY PROTECTIO	1.00	1.00 LS	26,000.000			26,000			26,000
====>	Item Totals:	121	- AREAWAY PROTECTION ZONE 2							
\$26,000.00				[]			26,000			26,000
26,000.000		1 EA					26,000.00			26,000.00
BID ITEM	= 122	CLIENT# = 122	Land Item	SCHEDULE: 1	100					
Description =	MAINTENANCE HOLE, TYPE 204A		Unit =	EA	Takeoff Quan:	6.000		Engr Quan:	6.000	

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract

BID ITEM = 122 CLIENT# = 122 Land Item SCHEDULE: 1 100
Description = MAINTENANCE HOLE, TYPE 204A Unit = EA Takeoff Quan: 6.000 Engr Quan: 6.000

122.01 MAINTENANCE HOLE, TYPE 204A **Quan: 6.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>UNM</u>	Underground Utilities 6 Man	32.00	CH	Prod:	32.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CPSMH204A	TYPE 204A MAIN@110.2	1.00	6.00 EA	1,796.000		11,881			11,881
2CPSZ230	TYPE 230 CASTI@110.25	1.00	6.00 EA	785.000		5,193			5,193
3DEDU02D	Dirt Trucking and Dump	1.00	36.00 TCY	24.500			882		882
8EX135A	135 Excavator W/Attach	1.00	32.00 HR	68.251				2,184	2,184
8EX200	200 Excavator	1.00	32.00 HR	78.000				2,496	2,496
8LO950	950 Loader	1.00	32.00 HR	81.500				2,608	2,608
FOCI	Civil Forman	1.00	32.00 MH	77.060	3,221				3,221
LAP	Labor Underground Water	2.00	64.00 MH	53.880	4,544				4,544
OPE	Operator - Excavator	1.00	32.00 MH	74.560	3,118				3,118
OPL	Operator - Loader	1.00	32.00 MH	74.560	3,118				3,118
\$39,244.92	26.6666 MH/EA	160.00	MH	[1959.113]	14,002	17,073	882	7,288	39,245

122.02 CHANNEL MH **Quan: 6.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew	16.00	CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	24.00 CY	121.150		3,206			3,206
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816				6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445				1,445
\$11,466.45	16.0000 MH/EA	96.00	MH	[1155.382]	8,261	3,206			11,466

=====> **Item Totals: 122 - MAINTENANCE HOLE, TYPE 204A**
 \$50,711.37 42.6666 MH/EA 256.00 MH [3114.495] 22,262 20,279 882 7,288 **50,711**
 8,451.895 6 EA 3,710.40 3,379.83 147.00 1,214.67 8,451.90

BID ITEM = 123 CLIENT# = 123 Land Item SCHEDULE: 1 100
Description = MAINTENANCE HOLE, TYPE 204.5A Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

123.01 MAINTENANCE HOLE, TYPE 204.5A **Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>UNM</u>	Underground Utilities 6 Man	8.00	CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CPSMH2045A	TYPE 204.5A MA@110.25	1.00	1.00 EA	2,225.400		2,454			2,454
2CPSZ230	TYPE 230 CASTI@110.25	1.00	1.00 EA	785.000		865			865
3DEDU02D	Dirt Trucking and Dump	1.00	6.00 TCY	24.500			147		147
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546	546
8EX200	200 Excavator	1.00	8.00 HR	78.000				624	624
8LO950	950 Loader	1.00	8.00 HR	81.500				652	652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136				1,136
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780
\$8,788.36	40.0000 MH/EA	40.00	MH	[2938.68]	3,500	3,319	147	1,822	8,788

123.02 CHANNEL MH 204.5 **Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew	4.00	CH	Prod:	4.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	2.00 CY	121.150		267			267
CEJ	Cement Mason	5.00	20.00 MH	64.980	1,704				1,704
FOCO	Concrete Forman	1.00	4.00 MH	68.980	361				361
\$2,332.34	24.0000 MH/EA	24.00	MH	[1733.07]	2,065	267			2,332

=====> **Item Totals: 123 - MAINTENANCE HOLE, TYPE 204.5A**
 \$11,120.70 64.0000 MH/EA 64.00 MH [4671.75] 5,566 3,586 147 1,822 **11,121**

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
BID ITEM = 123	CLIENT# = 123			Land Item	SCHEDULE: 1	100				
Description =	MAINTENANCE HOLE, TYPE 204.5A			Unit =	EA	Takeoff Quan:	1.000	Engr Quan:		1.000
11,120.700	1 EA					5,565.60	3,586.10	147.00	1,822.00	11,120.70

BID ITEM = 124	CLIENT# = 124			Land Item	SCHEDULE: 1	100				
Description =	MAINTENANCE HOLE, TYPE 204B			Unit =	EA	Takeoff Quan:	3.000	Engr Quan:		3.000

124.01 MAINTENANCE HOLE, TYPE 204B Quan: 3.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man			16.00	CH	Prod:	16.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CPSMH204B	TYPE 204B MAIN@110.2	1.00	3.00	EA		1,643.600	5,436				5,436
2CPSZ230	TYPE 230 CASTI@110.25	1.00	3.00	EA		785.000	2,596				2,596
3DEDU02D	Dirt Trucking and Dump	1.00	15.00	TCY		24.500		368			368
8EX135A	135 Excavator W/Attach	1.00	16.00	HR		68.251			1,092		1,092
8EX200	200 Excavator	1.00	16.00	HR		78.000			1,248		1,248
8LO950	950 Loader	1.00	16.00	HR		81.500			1,304		1,304
FOCI	Civil Forman	1.00	16.00	MH		77.060	1,610				1,610
LAP	Labor Underground Water	2.00	32.00	MH		53.880	2,272				2,272
OPE	Operator - Excavator	1.00	16.00	MH		74.560	1,559				1,559
OPL	Operator - Loader	1.00	16.00	MH		74.560	1,559				1,559
\$19,044.89	26.6666 MH/EA		80.00	MH		[1959.12]	7,001	8,033	368	3,644	19,045

124.02 CHANNEL MH 204B Quan: 3.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew			6.00	CH	Prod:	6.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	5.00	CY		121.150	668				668
CEJ	Cement Mason	5.00	30.00	MH		64.980	2,556				2,556
FOCO	Concrete Forman	1.00	6.00	MH		68.980	542				542
\$3,765.64	12.0000 MH/EA		36.00	MH		[866.537]	3,098	668			3,766

====> Item Totals: 124 - MAINTENANCE HOLE, TYPE 204B											
\$22,810.53	38.6666 MH/EA		116.00	MH		[2825.657]	10,099	8,700	368	3,644	22,811
7,603.510	3 EA						3,366.20	2,900.15	122.50	1,214.67	7,603.51

BID ITEM = 125	CLIENT# = 125			Land Item	SCHEDULE: 1	100				
Description =	MAINTENANCE HOLE, TYPE 205B			Unit =	EA	Takeoff Quan:	2.000	Engr Quan:		2.000

125.01 MAINTENANCE HOLE, TYPE 205B Quan: 2.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man			16.00	CH	Prod:	16.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CPSMH205B	TYPE 205B MAIN@110.2	1.00	2.00	EA		2,125.100	4,686				4,686
2CPSZ230	TYPE 230 CASTI@110.25	1.00	2.00	EA		785.000	1,731				1,731
3DEDU02D	Dirt Trucking and Dump	1.00	15.00	TCY		24.500		368			368
8EX135A	135 Excavator W/Attach	1.00	16.00	HR		68.251			1,092		1,092
8EX200	200 Excavator	1.00	16.00	HR		78.000			1,248		1,248
8LO950	950 Loader	1.00	16.00	HR		81.500			1,304		1,304
FOCI	Civil Forman	1.00	16.00	MH		77.060	1,610				1,610
LAP	Labor Underground Water	2.00	32.00	MH		53.880	2,272				2,272
OPE	Operator - Excavator	1.00	16.00	MH		74.560	1,559				1,559
OPL	Operator - Loader	1.00	16.00	MH		74.560	1,559				1,559
\$17,429.07	40.0000 MH/EA		80.00	MH		[2938.68]	7,001	6,417	368	3,644	17,429

125.02 CHANNEL MH 205B Quan: 2.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew			6.00	CH	Prod:	6.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	5.00	CY		121.150	668				668

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 125	CLIENT# = 125									
Description =	MAINTENANCE HOLE, TYPE 205B			Land Item Unit =	SCHEDULE: 1 100					
				EA	Takeoff Quan:		2.000	Engr Quan:		2.000
CEJ	Cement Mason	5.00	30.00 MH	64.980	2,556					2,556
FOCO	Concrete Forman	1.00	6.00 MH	68.980	542					542
\$3,765.64	18.0000 MH/EA		36.00 MH	[1299.805]	3,098	668				3,766

====> Item Totals:	125	- MAINTENANCE HOLE, TYPE 205B								
\$21,194.71	58.0000 MH/EA		116.00 MH	[4238.485]	10,099	7,085	368	3,644		21,195
10,597.355	2 EA				5,049.30	3,542.31	183.75	1,822.00		10,597.36

BID ITEM = 126	CLIENT# = 126									
Description =	MAINTENANCE HOLE, TYPE 206B			Land Item Unit =	SCHEDULE: 1 100					
				EA	Takeoff Quan:		1.000	Engr Quan:		1.000

126.01 MAINTENANCE HOLE, TYPE 206B **Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>UNM</u>	Underground Utilities 6 Man		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2CPSMH206B	TYPE 206B MAIN@110.2	1.00	1.00 EA	3,754.200	4,139					4,139
2CPSZ230	TYPE 230 CASTI@110.25	1.00	1.00 EA	785.000	865					865
3DEDU02D	Dirt Trucking and Dump	1.00	4.00 TCY	24.500		98				98
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546			546
8EX200	200 Excavator	1.00	8.00 HR	78.000			624			624
8LO950	950 Loader	1.00	8.00 HR	81.500			652			652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805					805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136					1,136
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780					780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780					780
\$10,424.87	40.0000 MH/EA		40.00 MH	[2938.68]	3,500	5,004	98	1,822		10,425

126.02 CHANNEL MH 206B **Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		3.00 CH	Prod:	3.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	4.00 CY	121.150	534					534
CEJ	Cement Mason	5.00	15.00 MH	64.980	1,278					1,278
FOCO	Concrete Forman	1.00	3.00 MH	68.980	271					271
\$2,083.17	18.0000 MH/EA		18.00 MH	[1299.8]	1,549	534				2,083

====> Item Totals:	126	- MAINTENANCE HOLE, TYPE 206B								
\$12,508.04	58.0000 MH/EA		58.00 MH	[4238.48]	5,049	5,539	98	1,822		12,508
12,508.040	1 EA				5,049.30	5,538.74	98.00	1,822.00		12,508.04

BID ITEM = 127	CLIENT# = 127									
Description =	MAINTENANCE HOLE, TYPE 207B			Land Item Unit =	SCHEDULE: 1 100					
				EA	Takeoff Quan:		4.000	Engr Quan:		4.000

127.01 MAINTENANCE HOLE, TYPE 207B **Quan: 4.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>UNM</u>	(Mod) Underground Utilities 6 Man		48.00 CH	Prod:	48.0000 CH	Lab Pcs:	7.00	Eqp Pcs:	4.00	
2CPSMH207B	TYPE 207B MAIN@110.2	1.00	4.00 EA	7,451.530	32,861					32,861
2CPSZ230	TYPE 230 CASTI@110.25	1.00	4.00 EA	785.000	3,462					3,462
3DEDU02D	Dirt Trucking and Dump	1.00	60.00 TCY	24.500		1,470				1,470
8EX135A	135 Excavator W/Attach	1.00	48.00 HR	68.251			3,276			3,276
8EX200	200 Excavator	1.00	48.00 HR	78.000			3,744			3,744
8EX400	400 Excavator	1.00	48.00 HR	175.700			8,434			8,434
8LO950	950 Loader	1.00	48.00 HR	81.500			3,912			3,912
FOCI	Civil Forman	1.00	48.00 MH	77.060	4,831					4,831
LAP	Labor Underground Water	2.00	96.00 MH	53.880	6,816					6,816
OPE	Operator - Excavator	3.00	144.00 MH	74.560	14,033					14,033

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 127	CLIENT# = 127		Land Item	SCHEDULE: 1	100					
Description =	MAINTENANCE HOLE, TYPE 207B		Unit =	EA	Takeoff Quan:		4.000	Engr Quan:		4.000
OPL	Operator - Loader	1.00	48.00 MH	74.560	4,678					4,678
\$87,516.31	84.0000 MH/EA	336.00 MH	[6376.393]	30,358	36,323	1,470	19,366			87,516
127.02	CHANNEL MH 207B		Quan:	4.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
COM	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	13.00 CY	121.150	1,736					1,736
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,997.20	24.0000 MH/EA	96.00 MH	[1733.073]	8,261	1,736					9,997
====>	Item Totals: 127 - MAINTENANCE HOLE, TYPE 207B									
\$97,513.51	108.0000 MH/EA	432.00 MH	[8109.465]	38,618	38,059	1,470	19,366			97,514
24,378.378	4 EA			9,654.60	9,514.87	367.50	4,841.41			24,378.38

BID ITEM = 128	CLIENT# = 128		Land Item	SCHEDULE: 1	100					
Description =	MAINTENANCE HOLE, TYPE 210B		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
128.01	MAINTENANCE HOLE, TYPE 210B		Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
UNM	(Mod) Unerground Utilities 6 Man		32.00 CH	Prod:	32.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		4.00
2CPSMH210B	TYPE 210B MAIN@110.2	1.00	2.00 EA	16,006.400	35,294					35,294
2CPSZ230	TYPE 230 CASTI@110.25	1.00	2.00 EA	785.000	1,731					1,731
3DEDU02D	Dirt Trucking and Dump	1.00	60.00 TCY	24.500		1,470				1,470
8EX135A	135 Excavator W/Attach	1.00	32.00 HR	68.251			2,184			2,184
8EX200	200 Excavator	1.00	32.00 HR	78.000			2,496			2,496
8EX400	400 Excavator	1.00	32.00 HR	175.700			5,622			5,622
8LO950	950 Loader	1.00	32.00 HR	81.500			2,608			2,608
FOCI	Civil Forman	1.00	32.00 MH	77.060	3,221					3,221
LAP	Labor Underground Water	2.00	64.00 MH	53.880	4,544					4,544
OPE	Operator - Excavator	2.00	64.00 MH	74.560	6,237					6,237
OPL	Operator - Loader	1.00	32.00 MH	74.560	3,118					3,118
\$68,525.44	96.0000 MH/EA	192.00 MH	[7189.595]	17,120	37,025	1,470	12,910			68,525
128.02	CHANNEL MH 208B		Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
COM	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	17.00 CY	121.150	2,271					2,271
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$10,531.47	48.0000 MH/EA	96.00 MH	[3466.145]	8,261	2,271					10,531
====>	Item Totals: 128 - MAINTENANCE HOLE, TYPE 210B									
\$79,056.91	144.0000 MH/EA	288.00 MH	[10655.74]	25,381	39,296	1,470	12,910			79,057
39,528.455	2 EA			12,690.40	19,647.85	735.00	6,455.21			39,528.46

BID ITEM = 129	CLIENT# = 129		Land Item	SCHEDULE: 1	100					
Description =	EXTRA DEPTH, TYPE 204A MAINTENANCE HOLE		Unit =	VF	Takeoff Quan:		16.000	Engr Quan:		16.000
129.01	EXTRA DEPTH, TYPE 204A MAINTENANCE HOL		Quan:	16.00 VF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
UNM	Unerground Utilities 6 Man		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	5.00	Eqp Pcs:		3.00
2CPSD204	EXTRA DEPTH MH@110.	1.00	16.00 LF	1.000	18					18
3DEDU02D	Dirt Trucking and Dump	1.00	8.00 TCY	24.500		196				196

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 129	CLIENT# = 129		Land Item	SCHEDULE: 1 100						
Description =	EXTRA DEPTH, TYPE 204A MAINTENANCE HOLE		Unit = VF	Takeoff Quan:			16.000	Engr Quan:		16.000
8EX135A	135 Excavator W/Attach	1.00	16.00 HR	68.251				1,092		1,092
8EX200	200 Excavator	1.00	16.00 HR	78.000				1,248		1,248
8LO950	950 Loader	1.00	16.00 HR	81.500				1,304		1,304
FOCI	Civil Forman	1.00	16.00 MH	77.060	1,610					1,610
LAP	Labor Underground Water	2.00	32.00 MH	53.880	2,272					2,272
OPE	Operator - Excavator	1.00	16.00 MH	74.560	1,559					1,559
OPL	Operator - Loader	1.00	16.00 MH	74.560	1,559					1,559
\$10,858.43	5.0000 MH/VF		80.00 MH	[367.335]	7,001	18	196	3,644		10,858
=====> Item Totals: 129 - EXTRA DEPTH, TYPE 204A MAINTENANCE HOLE										
\$10,858.43	5.0000 MH/VF		80.00 MH	[367.335]	7,001	18	196	3,644		10,858
678.652	16 VF				437.55	1.10	12.25	227.75		678.65

BID ITEM = 130	CLIENT# = 130		Land Item	SCHEDULE: 1 100						
Description =	EXTRA DEPTH, TYPE 204B MAINTENANCE HOLE		Unit = VF	Takeoff Quan:			8.000	Engr Quan:		8.000
130.01	EXTRA DEPTH, TYPE 204B MAINTENANCE HOL	Quan:	8.00 VF	Hrs/Shift: 10.00	Cal: 510	WC: WAAVG				
<u>UNM</u>	Underground Utilities 6 Man		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2CPSD204	EXTRA DEPTH MH@110.	1.00	8.00 LF	1.000		9			9	
3DEDU02D	Dirt Trucking and Dump	1.00	4.00 TCY	24.500		98			98	
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546		546
8EX200	200 Excavator	1.00	8.00 HR	78.000				624		624
8LO950	950 Loader	1.00	8.00 HR	81.500				652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805					805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136					1,136
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780					780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780					780
\$5,429.22	5.0000 MH/VF		40.00 MH	[367.335]	3,500	9	98	1,822		5,429
=====> Item Totals: 130 - EXTRA DEPTH, TYPE 204B MAINTENANCE HOLE										
\$5,429.22	5.0000 MH/VF		40.00 MH	[367.335]	3,500	9	98	1,822		5,429
678.653	8 VF				437.55	1.10	12.25	227.75		678.65

BID ITEM = 131	CLIENT# = 131		Land Item	SCHEDULE: 1 100						
Description =	EXTRA DEPTH, TYPE 206B MAINTENANCE HOLE		Unit = VF	Takeoff Quan:			1.000	Engr Quan:		1.000
131.01	EXTRA DEPTH, TYPE 206B MAINTENANCE HOL	Quan:	1.00 VF	Hrs/Shift: 10.00	Cal: 510	WC: WAAVG				
<u>UNM</u>	Underground Utilities 6 Man		2.00 CH	Prod:	2.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2CPSD206	EXTRA DEPTH MH@110.	1.00	1.00 VF	1.000		1			1	
3DEDU02D	Dirt Trucking and Dump	1.00	1.00 TCY	24.500		25			25	
8EX135A	135 Excavator W/Attach	1.00	2.00 HR	68.251				136		136
8EX200	200 Excavator	1.00	2.00 HR	78.000				156		156
8LO950	950 Loader	1.00	2.00 HR	81.500				163		163
FOCI	Civil Forman	1.00	2.00 MH	77.060	201					201
LAP	Labor Underground Water	2.00	4.00 MH	53.880	284					284
OPE	Operator - Excavator	1.00	2.00 MH	74.560	195					195
OPL	Operator - Loader	1.00	2.00 MH	74.560	195					195
\$1,356.18	10.0000 MH/VF		10.00 MH	[734.66]	875	1	25	455		1,356
=====> Item Totals: 131 - EXTRA DEPTH, TYPE 206B MAINTENANCE HOLE										
\$1,356.18	10.0000 MH/VF		10.00 MH	[734.66]	875	1	25	455		1,356

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 131	CLIENT# = 131	Land Item	SCHEDULE: 1	100						
Description =	EXTRA DEPTH, TYPE 206B MAINTENANCE HOLE	Unit =	VF	Takeoff Quan:		1.000		Engr Quan:		1.000
1,356.180	1 VF			875.09	1.10	24.50	455.49			1,356.18

BID ITEM = 132	CLIENT# = 132	Land Item	SCHEDULE: 1	100						
Description =	EXTRA DEPTH, TYPE 207B MAINTENANCE HOLE	Unit =	VF	Takeoff Quan:		22.000		Engr Quan:		22.000

132.01 EXTRA DEPTH, TYPE 207B MAINTENANCE HOL Quan: 22.00 VF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man	33.00	CH	Prod:	33.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CPSED207	EXTRA DEPTH MH@110.	1.00	22.00 VF	1.000		24				24
3DEDU02D	Dirt Trucking and Dump	1.00	31.00 TCY	24.500		760				760
8EX135A	135 Excavator W/Attach	1.00	33.00 HR	68.251				2,252		2,252
8EX200	200 Excavator	1.00	33.00 HR	78.000				2,574		2,574
8LO950	950 Loader	1.00	33.00 HR	81.500				2,689		2,689
FOCI	Civil Forman	1.00	33.00 MH	77.060	3,321					3,321
LAP	Labor Underground Water	2.00	66.00 MH	53.880	4,686					4,686
OPE	Operator - Excavator	1.00	33.00 MH	74.560	3,216					3,216
OPL	Operator - Loader	1.00	33.00 MH	74.560	3,216					3,216
\$22,738.65	7.5000 MH/VF	165.00	MH	[551.001]	14,439	24	760	7,516		22,739

====> Item Totals:	132	- EXTRA DEPTH, TYPE 207B MAINTENANCE HOLE								
\$22,738.65	7.5000 MH/VF	165.00	MH	[551.001]	14,439	24	760	7,516		22,739
1,033.575	22 VF			656.32	1.10	34.52	341.63			1,033.58

BID ITEM = 133	CLIENT# = 133	Land Item	SCHEDULE: 1	100						
Description =	EXTRA DEPTH TYPE 210B MAINTENANCE HOLE	Unit =	VF	Takeoff Quan:		4.000		Engr Quan:		4.000

133.01 EXTRA DEPTH TYPE 210B MAINTENANCE HOL Quan: 4.00 VF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	(Mod) Underground Utilities 6 Man	8.00	CH	Prod:	8.0000	CH	Lab Pcs:	6.00	Eqp Pcs:	4.00
2CPSED210	EXTRA DEPTH MH@110.	1.00	4.00 VF	1.000		4				4
3DEDU02D	Dirt Trucking and Dump	1.00	12.00 TCY	24.500		294				294
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546		546
8EX200	200 Excavator	1.00	8.00 HR	78.000				624		624
8EX400	400 Excavator	1.00	8.00 HR	175.700				1,406		1,406
8LO950	950 Loader	1.00	8.00 HR	81.500				652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805					805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136					1,136
OPE	Operator - Excavator	2.00	16.00 MH	74.560	1,559					1,559
OPL	Operator - Loader	1.00	8.00 MH	74.560	780					780
\$7,806.01	12.0000 MH/VF	48.00	MH	[898.703]	4,280	4	294	3,228		7,806

====> Item Totals:	133	- EXTRA DEPTH TYPE 210B MAINTENANCE HOLE								
\$7,806.01	12.0000 MH/VF	48.00	MH	[898.703]	4,280	4	294	3,228		7,806
1,951.503	4 VF			1,070.00	1.10	73.50	806.90			1,951.50

BID ITEM = 134	CLIENT# = 134	Land Item	SCHEDULE: 1	100						
Description =	RECHANNEL MAINTENANCE HOLE	Unit =	EA	Takeoff Quan:		2.000		Engr Quan:		2.000

134.01 RECHANNEL MAINTENANCE HOLE Quan: 2.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew	6.00	CH	Prod:	6.0000	CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
------------	---------------------	------	----	--------------	---------------	-----------	----------	------	----------	------

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 134	CLIENT# = 134									
Description =	RECHANNEL MAINTENANCE HOLE			Land Item Unit = EA	SCHEDULE: 1 100	Takeoff Quan:	2.000	Engr Quan:		2.000
2CR040	4000LB READY M@110.2	1.00	8.00 CY	121.150		1,069				1,069
CEJ	Cement Mason	5.00	30.00 MH	64.980	2,556					2,556
FOCO	Concrete Forman	1.00	6.00 MH	68.980	542					542
\$4,166.34	18.0000 MH/EA		36.00 MH	[1299.805]	3,098	1,069				4,166
====> Item Totals:	134 - RECHANNEL MAINTENANCE HOLE									
\$4,166.34	18.0000 MH/EA		36.00 MH	[1299.805]	3,098	1,069				4,166
2,083.170	2 EA				1,548.90	534.27				2,083.17

BID ITEM = 135	CLIENT# = 135									
Description =	REBUILD MAINTENANCE HOLE			Land Item Unit = EA	SCHEDULE: 1 100	Takeoff Quan:	1.000	Engr Quan:		1.000
135.01	REBUILD MAINTENANCE HOLE			Quan: 1.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
EAS	Earthwork 4 Man Crew		1.00 CH	Prod: 1.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00		
2CPSZ230	TYPE 230 CASTI@110.25	1.00	1.00 EA	785.000	865					865
8BA310A	418 Backhoe W/Attachme	1.00	1.00 HR	51.051			51			51
8EX100	100 Excavator	1.00	1.00 HR	52.300			52			52
FOCI	Civil Forman	1.00	1.00 MH	77.060	101					101
LAG	General Laborer	2.00	2.00 MH	52.910	140					140
OPE	Operator - Excavator	1.00	1.00 MH	74.560	97					97
\$1,306.41	4.0000 MH/EA		4.00 MH	[283.19]	338	865		103		1,306
====> Item Totals:	135 - REBUILD MAINTENANCE HOLE									
\$1,306.41	4.0000 MH/EA		4.00 MH	[283.19]	338	865		103		1,306
1,306.410	1 EA				337.62	865.46		103.33		1,306.41

BID ITEM = 136	CLIENT# = 136									
Description =	CATCH BASIN, TYPE 240A			Land Item Unit = EA	SCHEDULE: 1 100	Takeoff Quan:	2.000	Engr Quan:		2.000
136.01	CATCH BASIN, TYPE 240A			Quan: 2.00 EA	Hrs/Shft: 10.00	Cal: Z10	WC: WAAVG			
UNS	Underground Utilities 4 Man		16.00 CH	Prod: 16.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00		
2CPSCB240	TYPE 240 CATCH@110.2	1.00	2.00 EA	1,068.400	2,356					2,356
2CPSZ262	TYPE 262 INLET@110.25	1.00	2.00 EA	375.000	827					827
3DEDU02D	Dirt Trucking and Dump	1.00	10.00 TCY	24.500		245				245
8BA310A	418 Backhoe W/Attachme	1.00	16.00 HR	51.051			817			817
8EX100	100 Excavator	1.00	16.00 HR	52.300			837			837
FOCI	Civil Forman	1.00	16.00 MH	77.060	2,542					2,542
LAP	Labor Underground Water	1.00	16.00 MH	53.880	1,788					1,788
OPB	Operator - Backhoe	1.00	16.00 MH	74.560	2,461					2,461
OPE	Operator - Excavator	1.00	16.00 MH	74.560	2,461					2,461
\$14,332.59	32.0000 MH/EA		64.00 MH	[3920.84]	9,251	3,183	245	1,654		14,333
====> Item Totals:	136 - CATCH BASIN, TYPE 240A									
\$14,332.59	32.0000 MH/EA		64.00 MH	[3920.84]	9,251	3,183	245	1,654		14,333
7,166.295	2 EA				4,625.65	1,591.35	122.50	826.80		7,166.30

BID ITEM = 137	CLIENT# = 137									
Description =	CATCH BASIN, TYPE 242A			Land Item Unit = EA	SCHEDULE: 1 100	Takeoff Quan:	3.000	Engr Quan:		3.000

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment Contract	

BID ITEM = 137 CLIENT# = 137 Land Item SCHEDULE: 1 100
Description = CATCH BASIN, TYPE 242A Unit = EA Takeoff Quan: 3.000 Engr Quan: 3.000

137.01 CATCH BASIN, TYPE 242A Quan: 3.00 EA Hrs/Shft: 10.00 Cal: Z10 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	24.00	CH	Prod:	24.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2CPSCB242	TYPE 242 CATCH@110.2	1.00	3.00 EA	1,445.330	4,780				4,780
2CPSZ262	TYPE 262 INLET@110.25	1.00	3.00 EA	375.000	1,240				1,240
3DEDU02D	Dirt Trucking and Dump	1.00	15.00 TCY	24.500		368			368
8BA310A	418 Backhoe W/Attachme	1.00	24.00 HR	51.051			1,225		1,225
8EX100	100 Excavator	1.00	24.00 HR	52.300			1,255		1,255
FOCI	Civil Forman	1.00	24.00 MH	77.060	3,813				3,813
LAP	Labor Underground Water	1.00	24.00 MH	53.880	2,681				2,681
OPB	Operator - Backhoe	1.00	24.00 MH	74.560	3,691				3,691
OPE	Operator - Excavator	1.00	24.00 MH	74.560	3,691				3,691
\$22,745.58	32.0000 MH/EA	96.00	MH	[3920.84]	13,877	6,021	368	2,480	22,746

=====> **Item Totals: 137 - CATCH BASIN, TYPE 242A**
 \$22,745.58 32.0000 MH/EA 96.00 MH [3920.84] 13,877 6,021 368 2,480 **22,746**
 7,581.860 3 EA 4,625.64 2,006.91 122.50 826.81 7,581.86

BID ITEM = 138 CLIENT# = 138 Land Item SCHEDULE: 1 100
Description = CATCH BASIN, TYPE 242B Unit = EA Takeoff Quan: 9.000 Engr Quan: 9.000

138.01 CATCH BASIN, TYPE 242B Quan: 9.00 EA Hrs/Shft: 10.00 Cal: Z10 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	72.00	CH	Prod:	72.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2CPSCB242	TYPE 242 CATCH@110.2	1.00	9.00 EA	1,445.330	14,341				14,341
2CPSZ263	TYPE 263 INLET@110.25	1.00	9.00 EA	700.000	6,946				6,946
3DEDU02D	Dirt Trucking and Dump	1.00	45.00 TCY	24.500		1,103			1,103
8BA310A	418 Backhoe W/Attachme	1.00	72.00 HR	51.051			3,676		3,676
8EX100	100 Excavator	1.00	72.00 HR	52.300			3,766		3,766
FOCI	Civil Forman	1.00	72.00 MH	77.060	11,440				11,440
LAP	Labor Underground Water	1.00	72.00 MH	53.880	8,044				8,044
OPB	Operator - Backhoe	1.00	72.00 MH	74.560	11,074				11,074
OPE	Operator - Excavator	1.00	72.00 MH	74.560	11,074				11,074
\$71,461.56	32.0000 MH/EA	288.00	MH	[3920.84]	41,631	21,287	1,103	7,441	71,462

=====> **Item Totals: 138 - CATCH BASIN, TYPE 242B**
 \$71,461.56 32.0000 MH/EA 288.00 MH [3920.84] 41,631 21,287 1,103 7,441 **71,462**
 7,940.173 9 EA 4,625.64 2,365.23 122.50 826.81 7,940.17

BID ITEM = 139 CLIENT# = 139 Land Item SCHEDULE: 1 100
Description = INLET, TYPE 250A Unit = EA Takeoff Quan: 14.000 Engr Quan: 14.000

139.01 INLET, TYPE 250A Quan: 14.00 EA Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	56.00	CH	Prod:	56.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2CPSIN250	TYPE 250 INLET@110.25	1.00	14.00 EA	363.000	5,603				5,603
2CPSZ262	TYPE 262 INLET@110.25	1.00	14.00 EA	375.000	5,788				5,788
8BA310A	418 Backhoe W/Attachme	1.00	56.00 HR	51.051			2,859		2,859
8EX100	100 Excavator	1.00	56.00 HR	52.300			2,929		2,929
FOCI	Civil Forman	1.00	56.00 MH	77.060	7,643				7,643
LAP	Labor Underground Water	1.00	56.00 MH	53.880	5,379				5,379
OPB	Operator - Backhoe	1.00	56.00 MH	74.560	7,399				7,399
OPE	Operator - Excavator	1.00	56.00 MH	74.560	7,399				7,399

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 139	CLIENT# = 139		Land Item	SCHEDULE: 1	100					
Description =	INLET, TYPE 250A		Unit =	EA	Takeoff Quan:		14.000	Engr Quan:		14.000
\$44,999.41	16.0000 MH/EA	224.00 MH	[1680.36]	27,821	11,391			5,788		44,999
=====> Item Totals: 139 - INLET, TYPE 250A										
\$44,999.41	16.0000 MH/EA	224.00 MH	[1680.36]	27,821	11,391			5,788		44,999
3,214.244	14 EA			1,987.20	813.65			413.40		3,214.24

BID ITEM = 140	CLIENT# = 140		Land Item	SCHEDULE: 1	100					
Description =	INLET, TYPE 250B		Unit =	EA	Takeoff Quan:		39.000	Engr Quan:		39.000
140.01	INLET, TYPE 250B		Quan:	39.00 EA	Hrs/Shft:	10.00	Cal: S10	WC: WAAVG		
UNS	Underground Utilities 4 Man	156.00 CH	Prod:	156.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00		
2CPSIN250	TYPE 250 INLET@110.25	1.00 39.00 EA	355.000		15,264			15,264		
2CPSZ263	TYPE 263 INLET@110.25	1.00 39.00 EA	700.000		30,098			30,098		
8BA310A	418 Backhoe W/Attachme	1.00 156.00 HR	51.051				7,964	7,964		
8EX100	100 Excavator	1.00 156.00 HR	52.300				8,159	8,159		
FOCI	Civil Forman	1.00 156.00 MH	77.060	21,292						21,292
LAP	Labor Underground Water	1.00 156.00 MH	53.880	14,985						14,985
OPB	Operator - Backhoe	1.00 156.00 MH	74.560	20,612						20,612
OPE	Operator - Excavator	1.00 156.00 MH	74.560	20,612						20,612
\$138,985.68	16.0000 MH/EA	624.00 MH	[1680.36]	77,501	45,362			16,123		138,986
=====> Item Totals: 140 - INLET, TYPE 250B										
\$138,985.68	16.0000 MH/EA	624.00 MH	[1680.36]	77,501	45,362			16,123		138,986
3,563.735	39 EA			1,987.19	1,163.14			413.40		3,563.74

BID ITEM = 141	CLIENT# = 141		Land Item	SCHEDULE: 1	100					
Description =	EXTRA DEPTH, TYPE 204.5A MAINTENANCE HOL		Unit =	LF	Takeoff Quan:		3.000	Engr Quan:		3.000
141.01	EXTRA DEPTH, TYPE 204.5A MAINTENANCE HO		Quan:	3.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
UNM	Unerground Utilities 6 Man	3.00 CH	Prod:	3.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00		
2CPSED2045	EXTRA DEPTH MH@110.	1.00 3.00 LF	1.000		3			3		
3DEDU02D	Dirt Trucking and Dump	1.00 3.00 TCY	24.500			74		74		
8EX135A	135 Excavator W/Attach	1.00 3.00 HR	68.251				205	205		
8EX200	200 Excavator	1.00 3.00 HR	78.000				234	234		
8LO950	950 Loader	1.00 3.00 HR	81.500				244	244		
FOCI	Civil Forman	1.00 3.00 MH	77.060	302						302
LAP	Labor Underground Water	2.00 6.00 MH	53.880	426						426
OPE	Operator - Excavator	1.00 3.00 MH	74.560	292						292
OPL	Operator - Loader	1.00 3.00 MH	74.560	292						292
\$2,072.69	5.0000 MH/LF	15.00 MH	[367.337]	1,313	3	74	683			2,073
=====> Item Totals: 141 - EXTRA DEPTH, TYPE 204.5A MAINTENANCE HOL										
\$2,072.69	5.0000 MH/LF	15.00 MH	[367.337]	1,313	3	74	683			2,073
690.897	3 LF			437.55	1.10	24.50	227.74			690.90

BID ITEM = 142	CLIENT# = 142		Land Item	SCHEDULE: 1	100					
Description =	PIPE, CB CONN, D.I., CL 50, 8 IN		Unit =	LF	Takeoff Quan:		779.000	Engr Quan:		779.000

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment Contract	

BID ITEM = 142 CLIENT# = 142 Land Item SCHEDULE: 1 100
Description = PIPE, CB CONN, D.I., CL 50, 8 IN Unit = LF Takeoff Quan: 779.000 Engr Quan: 779.000

142.01 PIPE, CB CONN, D.I., CL 50, 8 IN Quan: 779.00 LF Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	165.74	CH	Prod:	165.7447	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2BI142PIPE	BID ITEM 142 P@110.25	1.00	0.97 LS	28,207.550		30,166				30,166
8BA310A	418 Backhoe W/Attachme	1.00	165.74 HR	51.051				8,461		8,461
8EX100	100 Excavator	1.00	165.74 HR	52.300				8,668		8,668
FOCI	Civil Forman	1.00	165.74 MH	77.060	22,621					22,621
LAP	Labor Underground Water	1.00	165.74 MH	53.880	15,921					15,921
OPB	Operator - Backhoe	1.00	165.74 MH	74.560	21,899					21,899
OPE	Operator - Excavator	1.00	165.74 MH	74.560	21,899					21,899
\$129,634.67	0.8510 MH/LF		662.96 MH	[89.378]	82,339	30,166		17,129		129,635

=====> **Item Totals: 142 - PIPE, CB CONN, D.I., CL 50, 8 IN**
 \$129,634.67 0.8510 MH/LF 662.96 MH [89.378] 82,339 30,166 17,129 **129,635**
 166.412 779 LF 105.70 38.72 21.99 166.41

BID ITEM = 143 CLIENT# = 143 Land Item SCHEDULE: 1 100
Description = PIPE, INLET CONN, D.I., CL 50, 8 IN Unit = LF Takeoff Quan: 1,286.000 Engr Quan: 1,286.000

143.01 PIPE, INLET CONN, D.I., CL 50, 8 IN Quan: 1,286.00 LF Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	212.00	CH	Prod:	212.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2BI143PIPE	BID ITEM 143 P@110.25	1.00	1.00 LS	37,985.920		41,879				41,879
8BA310A	418 Backhoe W/Attachme	1.00	212.00 HR	51.051				10,823		10,823
8EX100	100 Excavator	1.00	212.00 HR	52.300				11,088		11,088
FOCI	Civil Forman	1.00	212.00 MH	77.060	28,935					28,935
LAP	Labor Underground Water	1.00	212.00 MH	53.880	20,365					20,365
OPB	Operator - Backhoe	1.00	212.00 MH	74.560	28,011					28,011
OPE	Operator - Excavator	1.00	212.00 MH	74.560	28,011					28,011
\$169,111.20	0.6594 MH/LF		848.00 MH	[69.253]	105,321	41,879		21,910		169,111

=====> **Item Totals: 143 - PIPE, INLET CONN, D.I., CL 50, 8 IN**
 \$169,111.20 0.6594 MH/LF 848.00 MH [69.253] 105,321 41,879 21,910 **169,111**
 131.502 1286 LF 81.90 32.57 17.04 131.50

BID ITEM = 144 CLIENT# = 144 Land Item SCHEDULE: 1 100
Description = DROP CONNECTION, OUTSIDE, 8 IN Unit = VF Takeoff Quan: 14.000 Engr Quan: 14.000

144.01 DROP CONNECTION, OUTSIDE, 8 IN Quan: 14.00 VF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man	20.00	CH	Prod:	20.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI144PIPE	BID ITEM 144 P@110.25	1.00	1.00 LS	1,552.960		1,712				1,712
8EX135A	135 Excavator W/Attach	1.00	20.00 HR	68.251				1,365		1,365
8EX200	200 Excavator	1.00	20.00 HR	78.000				1,560		1,560
8LO950	950 Loader	1.00	20.00 HR	81.500				1,630		1,630
FOCI	Civil Forman	1.00	20.00 MH	77.060	2,013					2,013
LAP	Labor Underground Water	2.00	40.00 MH	53.880	2,840					2,840
OPE	Operator - Excavator	1.00	20.00 MH	74.560	1,949					1,949
OPL	Operator - Loader	1.00	20.00 MH	74.560	1,949					1,949
\$15,018.15	7.1428 MH/VF		100.00 MH	[524.763]	8,751	1,712		4,555		15,018

=====> **Item Totals: 144 - DROP CONNECTION, OUTSIDE, 8 IN**
 \$15,018.15 7.1428 MH/VF 100.00 MH [524.763] 8,751 1,712 4,555 **15,018**

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 144	CLIENT# = 144			Land Item	SCHEDULE: 1	100				
Description =	DROP CONNECTION, OUTSIDE, 8 IN		Unit =	VF	Takeoff Quan:		14.000	Engr Quan:		14.000
1,072.725	14 VF				625.07	122.30		325.36		1,072.73

BID ITEM = 145	CLIENT# = 145			Land Item	SCHEDULE: 1	100				
Description =	4 INCH DRAIN PIPE, GIP, SCH 40		Unit =	EA	Takeoff Quan:		59.000	Engr Quan:		59.000

145.01 4 INCH DRAIN PIPE, GIP, SCH 40 Quan: 59.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		59.00	CH	Prod:	59.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2BI145PIPE	BID ITEM 145 P@110.25	1.00	1.00	LS	28,483.000	31,403				31,403
8BA310A	418 Backhoe W/Attachme	1.00	59.00	HR	51.051			3,012		3,012
8EX100	100 Excavator	1.00	59.00	HR	52.300			3,086		3,086
FOCI	Civil Forman	1.00	59.00	MH	77.060	5,938				5,938
LAG	General Laborer	2.00	118.00	MH	52.910	8,232				8,232
OPE	Operator - Excavator	1.00	59.00	MH	74.560	5,750				5,750
\$57,419.66	4.0000 MH/EA		236.00	MH	[283.184]	19,919	31,403	6,098		57,420

====> Item Totals: 145 - 4 INCH DRAIN PIPE, GIP, SCH 40										
\$57,419.66	4.0000 MH/EA		236.00	MH	[283.184]	19,919	31,403	6,098		57,420
973.215	59 EA					337.62	532.25	103.35		973.21

BID ITEM = 146	CLIENT# = 146			Land Item	SCHEDULE: 1	100				
Description =	FLOW CONTROL DEVICE ASSEMBLY		Unit =	EA	Takeoff Quan:		3.000	Engr Quan:		3.000

146.01 FLOW CONTROL DEVICE ASSEMBLY Quan: 3.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		12.00	CH	Prod:	12.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI146PIPE	BID ITEM 146 P@110.25	1.00	1.00	LS	4,823.730	5,318				5,318
8EX135A	135 Excavator W/Attach	1.00	12.00	HR	68.251			819		819
8EX200	200 Excavator	1.00	12.00	HR	78.000			936		936
8LO950	950 Loader	1.00	12.00	HR	81.500			978		978
FOCI	Civil Forman	1.00	12.00	MH	77.060	1,208				1,208
LAP	Labor Underground Water	2.00	24.00	MH	53.880	1,704				1,704
OPE	Operator - Excavator	1.00	12.00	MH	74.560	1,169				1,169
OPL	Operator - Loader	1.00	12.00	MH	74.560	1,169				1,169
\$13,301.75	20.0000 MH/EA		60.00	MH	[1469.333]	5,251	5,318	2,733		13,302

====> Item Totals: 146 - FLOW CONTROL DEVICE ASSEMBLY										
\$13,301.75	20.0000 MH/EA		60.00	MH	[1469.333]	5,251	5,318	2,733		13,302
4,433.917	3 EA					1,750.20	1,772.72	911.00		4,433.92

BID ITEM = 147	CLIENT# = 147			Land Item	SCHEDULE: 1	100				
Description =	PIPE, DETENTION, CONC, 48 IN		Unit =	LF	Takeoff Quan:		105.000	Engr Quan:		105.000

147.01 PIPE, DETENTION, CONC, 48 IN Quan: 105.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	(Mod) Underground Utilities 6 Man		48.00	CH	Prod:	48.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	4.00
2CONPIPE48	CONCRETE PIPE @110.2	1.00	1.00	LS	31,136.000	34,327				34,327
8EX135A	135 Excavator W/Attach	1.00	48.00	HR	68.251			3,276		3,276
8EX200	200 Excavator	1.00	48.00	HR	78.000			3,744		3,744
8EX400	400 Excavator	1.00	48.00	HR	175.700			8,434		8,434
8LO950	950 Loader	1.00	48.00	HR	81.500			3,912		3,912

Activity	Desc	Quantity	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
BID ITEM	= 147	CLIENT# = 147	Land Item	SCHEDULE:	1	100				
Description =	PIPE, DETENTION, CONC, 48 IN		Unit =	LF	Takeoff	Quan:	105.000	Engr	Quan:	105.000
FOCI	Civil Forman	1.00	48.00 MH	77.060	4,831					4,831
LAP	Labor Underground Water	2.00	96.00 MH	53.880	6,816					6,816
OPE	Operator - Excavator	2.00	96.00 MH	74.560	9,355					9,355
OPL	Operator - Loader	1.00	48.00 MH	74.560	4,678					4,678
\$79,373.05	2.7428 MH/LF		288.00 MH	[205.417]	25,680	34,327		19,366		79,373
====> Item Totals: 147 - PIPE, DETENTION, CONC, 48 IN										
\$79,373.05	2.7428 MH/LF		288.00 MH	[205.417]	25,680	34,327		19,366		79,373
755.934	105 LF				244.57	326.93		184.43		755.93

BID ITEM	= 148	CLIENT# = 148	Land Item	SCHEDULE: 1	100	
Description =	PIPE, DETENTION, POLYPROPYLENE, 48 IN		Unit =	LF	Takeoff Quan: 210.000	Engr Quan: 210.000

148.01	PIPE, DETENTION, POLYPROPYLENE, 48 IN	Quan:	210.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
--------	---------------------------------------	-------	-----------	-----------	-------	------	-----	-----	-------

<u>UNM</u>	(Mod) Underground Utilities 6 Man	42.00	CH	Prod:	42.0000	CH	Lab Pcs:	6.00	Eqp Pcs:	4.00
2BI148PIPE	BID ITEM 148 P@110.25	1.00	1.00	LS	38,308.200	42,235				42,235
8EX135A	135 Excavator W/Attach	1.00	42.00	HR	68.251			2,867		2,867
8EX200	200 Excavator	1.00	42.00	HR	78.000			3,276		3,276
8EX400	400 Excavator	1.00	42.00	HR	175.700			7,379		7,379
8LO950	950 Loader	1.00	42.00	HR	81.500			3,423		3,423
FOCI	Civil Forman	1.00	42.00	MH	77.060	4,227				4,227
LAP	Labor Underground Water	2.00	84.00	MH	53.880	5,964				5,964
OPE	Operator - Excavator	2.00	84.00	MH	74.560	8,186				8,186
OPL	Operator - Loader	1.00	42.00	MH	74.560	4,093				4,093
\$81,649.68	1.2000 MH/LF		252.00	MH	[89.87]	22,470	42,235	16,945		81,650

=====	Item Totals:	148	- PIPE, DETENTION, POLYPROPYLENE, 48 IN				
\$81,649.68	1.2000 MH/LF	252.00 MH	[89.87]	22,470	42,235	16,945	81,650
388.808	210 LF			107.00	201.12	80.69	388.81

BID ITEM	= 149	CLIENT# = 149	Land Item	SCHEDULE: 1	100		
Description =	PIPE, DETENTION, STEEL REINFORCED POLYET	Unit =	LF	Takeoff Quan:	250.000	Engr Quan:	250.000

149.01	PIPE, DETENTION, STEEL REINFORCED POLYE	Quan:	250.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
--------	---	-------	-----------	-----------	-------	------	-----	-----	-------

UNM	(Mod) Unerground Utilities 6 Man		60.00	CH	Prod:	60.0000	CH	Lab Pcs:	6.00	Eqp Pcs:	4.00
2BI149PIPE	BID ITEM 149 P@110.25	1.00	1.00	LS	127,388.660		140,446				140,446
8EX135A	135 Excavator W/Attach	1.00	60.00	HR	68.251				4,095		4,095
8EX200	200 Excavator	1.00	60.00	HR	78.000				4,680		4,680
8EX400	400 Excavator	1.00	60.00	HR	175.700				10,542		10,542
8LO950	950 Loader	1.00	60.00	HR	81.500				4,890		4,890
FOCI	Civil Forman	1.00	60.00	MH	77.060	6,039					6,039
LAP	Labor Underground Water	2.00	120.00	MH	53.880	8,520					8,520
OPE	Operator - Excavator	2.00	120.00	MH	74.560	11,694					11,694
OPL	Operator - Loader	1.00	60.00	MH	74.560	5,847					5,847
\$196,753.02	1.4400 MH/LF		360.00	MH	[107.844]	32,100	140,446		24,207		196,753

=====	Item Totals:	149	- PIPE, DETENTION, STEEL REINFORCED POLYET					
\$196,753.02	1.4400 MH/LF		360.00 MH	[107.844]	32,100	140,446	24,207	196,753
787.012	250 LF				128.40	561.78	96.83	787.01

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	---------------	--------------------	-------------------	------------------	-------

BID ITEM = **150** CLIENT# = 150 Land Item SCHEDULE: 1 100
Description = PIPE,DETENTION PIPE OUTLET CONNECTION,D. Unit = LF Takeoff Quan: 297.000 Engr Quan: 297.000

150.01 PIPE,DETENTION PIPE OUTLET CONNECTION, Quan: 297.00 LF Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man	40.00	CH	Prod:	40.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI150PIPE	BID ITEM 150 P@110.25	1.00	1.00 LS	12,391.320	13,661				13,661
8EX135A	135 Excavator W/Attach	1.00	40.00 HR	68.251			2,730		2,730
8EX200	200 Excavator	1.00	40.00 HR	78.000			3,120		3,120
8LO950	950 Loader	1.00	40.00 HR	81.500			3,260		3,260
FOCI	Civil Forman	1.00	40.00 MH	77.060	4,026				4,026
LAP	Labor Underground Water	2.00	80.00 MH	53.880	5,680				5,680
OPE	Operator - Excavator	1.00	40.00 MH	74.560	3,898				3,898
OPL	Operator - Loader	1.00	40.00 MH	74.560	3,898				3,898
\$40,273.44	0.6734 MH/LF	200.00	MH	[49.473]	17,502	13,661		9,110	40,273

=====> **Item Totals: 150 - PIPE,DETENTION PIPE OUTLET CONNECTION,D.**
\$40,273.44 0.6734 MH/LF 200.00 MH [49.473] 17,502 13,661 9,110 **40,273**
135.601 297 LF 58.93 46.00 30.67 135.60

BID ITEM = **151** CLIENT# = 151 Land Item SCHEDULE: 1 100
Description = FLOW SPLITTER DEVICE ASSEMBLY Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

151.01 FLOW SPLITTER DEVICE ASSEMBLY Quan: 1.00 EA Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man	8.00	CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI151PIPE	BID ITEM 151 P@110.25	1.00	1.00 LS	3,820.140	4,212				4,212
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546		546
8EX200	200 Excavator	1.00	8.00 HR	78.000			624		624
8LO950	950 Loader	1.00	8.00 HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136				1,136
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780
\$9,534.10	40.0000 MH/EA	40.00	MH	[2938.68]	3,500	4,212		1,822	9,534

=====> **Item Totals: 151 - FLOW SPLITTER DEVICE ASSEMBLY**
\$9,534.10 40.0000 MH/EA 40.00 MH [2938.68] 3,500 4,212 1,822 **9,534**
9,534.100 1 EA 3,500.40 4,211.70 1,822.00 9,534.10

BID ITEM = **152** CLIENT# = 152 Land Item SCHEDULE: 1 100
Description = BEDDING, CL B, 8 IN PIPE Unit = LF Takeoff Quan: 2,090.000 Engr Quan: 2,090.000

152.01 BEDDING, CL B, 8 IN PIPE Quan: 2,090.00 LF Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

2AGS09	SEATTLE TYPE 9@110.2	1.00	1,051.96 TON	29.750	34,504				34,504
3DEDU02D	Dirt Trucking and Dump	1.00	743.08 TCY	24.500			18,205		18,205
\$52,709.09				[]	34,504	18,205			52,709

=====> **Item Totals: 152 - BEDDING, CL B, 8 IN PIPE**
\$52,709.09 [] 34,504 18,205 **52,709**
25.220 2090 LF 16.51 8.71 25.22

Activity	Resource	Desc	Pcs	Quantity	Unit	Unit Cost	Labor	Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
BID ITEM =	153	CLIENT# =	153	Land Item	SCHEDULE:	1	100					
Description =	BEDDING, CL B, 10 IN PIPE			Unit =	LF	Takeoff	Quan:		136.000	Engr Quan:		136.000
153.01	BEDDING, CL B, 10 IN PIPE			Quan:	136.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
2AGS09	SEATTLE TYPE 9@110.2	1.00	68.00 TON		29.750			2,230				2,230
3DEDU02D	Dirt Trucking and Dump	1.00	48.00 TCY		24.500				1,176			1,176
\$3,406.36					[]			2,230	1,176			3,406
====>	Item Totals:	153	- BEDDING, CL B, 10 IN PIPE									
\$3,406.36					[]			2,230	1,176			3,406
25.047		136 LF						16.40	8.65			25.05
BID ITEM =	154	CLIENT# =	154	Land Item	SCHEDULE:	1	100					
Description =	BEDDING, CL B, 12 IN PIPE			Unit =	LF	Takeoff	Quan:		1,526.000	Engr Quan:		1,526.000
154.01	BEDDING, CL B, 12 IN PIPE			Quan:	1,526.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
2AGS09	SEATTLE TYPE 9@110.2	1.00	960.00 TON		29.750			31,487				31,487
3DEDU02D	Dirt Trucking and Dump	1.00	678.00 TCY		24.500				16,611			16,611
\$48,098.40					[]			31,487	16,611			48,098
====>	Item Totals:	154	- BEDDING, CL B, 12 IN PIPE									
\$48,098.40					[]			31,487	16,611			48,098
31.519		1526 LF						20.63	10.89			31.52
BID ITEM =	155	CLIENT# =	155	Land Item	SCHEDULE:	1	100					
Description =	BEDDING, CL B, 24 IN PIPE			Unit =	LF	Takeoff	Quan:		14.000	Engr Quan:		14.000
155.01	BEDDING, CL B, 24 IN PIPE			Quan:	14.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
2AGS09	SEATTLE TYPE 9@110.2	1.00	8.00 TON		29.750			262				262
3DEDU02D	Dirt Trucking and Dump	1.00	7.00 TCY		24.500				172			172
\$433.90					[]			262	172			434
====>	Item Totals:	155	- BEDDING, CL B, 24 IN PIPE									
\$433.90					[]			262	172			434
30.993		14 LF						18.74	12.25			30.99
BID ITEM =	156	CLIENT# =	156	Land Item	SCHEDULE:	1	100					
Description =	BEDDING, CL B, 48 IN PIPE			Unit =	LF	Takeoff	Quan:		315.000	Engr Quan:		315.000
156.01	BEDDING, CL B, 48 IN PIPE			Quan:	315.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
2AGS09	SEATTLE TYPE 9@110.2	1.00	465.00 TON		29.750			15,252				15,252
3DEDU02D	Dirt Trucking and Dump	1.00	504.00 TCY		24.500				12,348			12,348
\$27,599.71					[]			15,252	12,348			27,600
====>	Item Totals:	156	- BEDDING, CL B, 48 IN PIPE									
\$27,599.71					[]			15,252	12,348			27,600
87.618		315 LF						48.42	39.20			87.62

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
-------------------	------	-----	---------------	-----------	-------	---------------	-----------------	------------	--------------	-------

BID ITEM = 157 CLIENT# = 157 Land Item SCHEDULE: 1 100
Description = BEDDING, CL B, 72 IN PIPE Unit = LF Takeoff Quan: 250.000 Engr Quan: 250.000

157.01 BEDDING, CL B, 72 IN PIPE Quan: 250.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

2AGS09	SEATTLE TYPE 9@110.2	1.00	814.00 TON	29.750		26,699				26,699
3DEDU02D	Dirt Trucking and Dump	1.00	888.00 TCY	24.500			21,756			21,756
\$48,454.69				[]		26,699	21,756			48,455

====> **Item Totals: 157 - BEDDING, CL B, 72 IN PIPE**
\$48,454.69 [] 26,699 21,756 **48,455**
193.819 250 LF 106.79 87.02 193.82

BID ITEM = 158 CLIENT# = 158 Land Item SCHEDULE: 1 100
Description = TELEVISION INSPECTION Unit = LF Takeoff Quan: 3,031.000 Engr Quan: 3,031.000

158.01 TELEVISION INSPECTION Quan: 3,031.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

3CCTV	TV INSPECTION	1.00	40.64 HR	250.000			10,160			10,160
FOCI	=> Civil Forman	1.00	40.64 MH	77.060	4,090					4,090
\$14,250.31	0.0134 MH/LF		40.64 MH	[1.137]	4,090		10,160			14,250

====> **Item Totals: 158 - TELEVISION INSPECTION**
\$14,250.31 0.0134 MH/LF 40.64 MH [1.137] 4,090 10,160 **14,250**
4.702 3031 LF 1.35 3.35 4.70

BID ITEM = 159 CLIENT# = 159 Land Item SCHEDULE: 1 100
Description = PIPE, PSD, CONC REINF, C76 CL III, 24 IN Unit = LF Takeoff Quan: 14.000 Engr Quan: 14.000

159.01 PIPE, PSD, CONC REINF, C76 CL III, 24 IN Quan: 14.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		2.00 CH	Prod:	2.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2CONPIPE24	24 " CONCRETE @110.25	1.00	1.00 LS	806.890		890				890
8EX135A	135 Excavator W/Attach	1.00	2.00 HR	68.251				136		136
8EX200	200 Excavator	1.00	2.00 HR	78.000				156		156
8LO950	950 Loader	1.00	2.00 HR	81.500				163		163
FOCI	Civil Forman	1.00	2.00 MH	77.060	201					201
LAP	Labor Underground Water	2.00	4.00 MH	53.880	284					284
OPE	Operator - Excavator	1.00	2.00 MH	74.560	195					195
OPL	Operator - Loader	1.00	2.00 MH	74.560	195					195
\$2,220.18	0.7142 MH/LF		10.00 MH	[52.476]	875	890		455		2,220

====> **Item Totals: 159 - PIPE, PSD, CONC REINF, C76 CL III, 24 IN**
\$2,220.18 0.7142 MH/LF 10.00 MH [52.476] 875 890 455 **2,220**
158.584 14 LF 62.51 63.54 32.54 158.58

BID ITEM = 160 CLIENT# = 160 Land Item SCHEDULE: 1 100
Description = PIPE, PSD, D.I., CL 50, 8 IN Unit = LF Takeoff Quan: 35.000 Engr Quan: 35.000

160.01 PIPE, PSD, D.I., CL 50, 8 IN Quan: 35.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		5.00 CH	Prod:	5.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI160PIPE	BID ITEM 160 P@110.25	1.00	1.00 LS	1,810.610		1,996				1,996

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 160	CLIENT# = 160									
Description =	PIPE, PSD, D.I., CL 50, 8 IN		Land Item Unit =	SCHEDULE: 1 100	LF	Takeoff Quan:	35.000	Engr Quan:		35.000
8EX135A	135 Excavator W/Attach	1.00	5.00 HR	68.251				341		341
8EX200	200 Excavator	1.00	5.00 HR	78.000				390		390
8LO950	950 Loader	1.00	5.00 HR	81.500				407		407
FOCI	Civil Forman	1.00	5.00 MH	77.060	503					503
LAP	Labor Underground Water	2.00	10.00 MH	53.880	710					710
OPE	Operator - Excavator	1.00	5.00 MH	74.560	487					487
OPL	Operator - Loader	1.00	5.00 MH	74.560	487					487
\$5,322.69	0.7142 MH/LF		25.00 MH	[52.476]	2,188	1,996		1,139		5,323
=====> Item Totals: 160 - PIPE, PSD, D.I., CL 50, 8 IN										
\$5,322.69	0.7142 MH/LF		25.00 MH	[52.476]	2,188	1,996		1,139		5,323
152.077	35 LF				62.51	57.03		32.54		152.08

BID ITEM = 161	CLIENT# = 161									
Description =	PIPE, PSD, D.I., CL 50, 12 IN		Land Item Unit =	SCHEDULE: 1 100	LF	Takeoff Quan:	1,228.000	Engr Quan:		1,228.000
161.01	PIPE, PSD, D.I., CL 50, 12 IN			Quan: 1,228.00 LF	Hrs/Shft: 10.00	Cal: 610	WC: WAAVG			
<u>UNM</u>	Underground Utilities 6 Man		200.00 CH	Prod: 200.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00		
2BI161PIPE	BID ITEM 161 P@110.25	1.00	1.00 LS	55,626.580	61,328					61,328
8EX135A	135 Excavator W/Attach	1.00	200.00 HR	68.251				13,650		13,650
8EX200	200 Excavator	1.00	200.00 HR	78.000				15,600		15,600
8LO950	950 Loader	1.00	200.00 HR	81.500				16,300		16,300
FOCI	Civil Forman	1.00	200.00 MH	77.060	21,325					21,325
LAP	Labor Underground Water	2.00	400.00 MH	53.880	30,072					30,072
OPE	Operator - Excavator	1.00	200.00 MH	74.560	20,646					20,646
OPL	Operator - Loader	1.00	200.00 MH	74.560	20,646					20,646
\$199,567.91	0.8143 MH/LF		1,000.00 MH	[63.454]	92,689	61,328		45,550		199,568
=====> Item Totals: 161 - PIPE, PSD, D.I., CL 50, 12 IN										
\$199,567.91	0.8143 MH/LF		1,000.00 MH	[63.454]	92,689	61,328		45,550		199,568
162.515	1228 LF				75.48	49.94		37.09		162.51

BID ITEM = 162	CLIENT# = 162									
Description =	PIPE, PS or PSS, PVC, D3034 SDR 35, 8 IN		Land Item Unit =	SCHEDULE: 1 100	LF	Takeoff Quan:	12.000	Engr Quan:		12.000
162.01	PIPE, PS or PSS, PVC, D3034 SDR 35, 8 IN			Quan: 12.00 LF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
<u>UNM</u>	Underground Utilities 6 Man		4.00 CH	Prod: 4.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00		
2BI162PIPE	BID ITEM 162 P@110.25	1.00	1.00 LS	329.800	364					364
8EX135A	135 Excavator W/Attach	1.00	4.00 HR	68.251				273		273
8EX200	200 Excavator	1.00	4.00 HR	78.000				312		312
8LO950	950 Loader	1.00	4.00 HR	81.500				326		326
FOCI	Civil Forman	1.00	4.00 MH	77.060	403					403
LAP	Labor Underground Water	2.00	8.00 MH	53.880	568					568
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390					390
OPL	Operator - Loader	1.00	4.00 MH	74.560	390					390
\$3,024.79	1.6666 MH/LF		20.00 MH	[122.443]	1,750	364		911		3,025
=====> Item Totals: 162 - PIPE, PS or PSS, PVC, D3034 SDR 35, 8 IN										
\$3,024.79	1.6666 MH/LF		20.00 MH	[122.443]	1,750	364		911		3,025
252.066	12 LF				145.85	30.30		75.92		252.07

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract

BID ITEM = 163 CLIENT# = 163 Land Item SCHEDULE: 1 100
Description = PIPE, PS OR PSS, PVC D3034 SDR 35, 10IN Unit = LF Takeoff Quan: 136.000 Engr Quan: 136.000

163.01 PIPE, PS OR PSS, PVC D3034 SDR 35, 10IN Quan: 136.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		18.00	CH	Prod:	18.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI163PIPE	BID ITEM 163 P@110.25	1.00	1.00	LS	2,546.080		2,807				2,807
8EX135A	135 Excavator W/Attach	1.00	18.00	HR	68.251				1,229		1,229
8EX200	200 Excavator	1.00	18.00	HR	78.000				1,404		1,404
8LO950	950 Loader	1.00	18.00	HR	81.500				1,467		1,467
FOCI	Civil Forman	1.00	18.00	MH	77.060	1,812					1,812
LAP	Labor Underground Water	2.00	36.00	MH	53.880	2,556					2,556
OPE	Operator - Excavator	1.00	18.00	MH	74.560	1,754					1,754
OPL	Operator - Loader	1.00	18.00	MH	74.560	1,754					1,754
\$14,782.45	0.6617 MH/LF		90.00	MH	[48.618]	7,876	2,807		4,100		14,782

=====> **Item Totals: 163 - PIPE, PS OR PSS, PVC D3034 SDR 35, 10IN**
 \$14,782.45 0.6617 MH/LF 90.00 MH [48.618] 7,876 2,807 4,100 **14,782**
 108.694 136 LF 57.91 20.64 30.14 108.69

BID ITEM = 164 CLIENT# = 164 Land Item SCHEDULE: 1 100
Description = TEE, 8 IN, CUT-IN EXISTING CONC PIPE Unit = EA Takeoff Quan: 23.000 Engr Quan: 23.000

164.01 TEE, 8 IN, CUT-IN EXISTING CONC PIPE Quan: 23.00 EA Hrs/Shft: 8.00 Cal: S08 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man		46.00	CH	Prod:	46.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
3SPUCORE	SPU CORE TAP	1.00	23.00	EA	150.000		3,450				3,450
8BA310A	418 Backhoe W/Attachme	1.00	46.00	HR	51.051				2,348		2,348
8EX100	100 Excavator	1.00	46.00	HR	52.300				2,406		2,406
FOCI	Civil Forman	1.00	46.00	MH	77.060	6,278					6,278
LAP	Labor Underground Water	1.00	46.00	MH	53.880	4,419					4,419
OPB	Operator - Backhoe	1.00	46.00	MH	74.560	6,078					6,078
OPE	Operator - Excavator	1.00	46.00	MH	74.560	6,078					6,078
\$31,056.86	8.0000 MH/EA		184.00	MH	[840.18]	22,853	3,450	4,754			31,057

=====> **Item Totals: 164 - TEE, 8 IN, CUT-IN EXISTING CONC PIPE**
 \$31,056.86 8.0000 MH/EA 184.00 MH [840.18] 22,853 3,450 4,754 **31,057**
 1,350.298 23 EA 993.60 150.00 206.70 1,350.30

BID ITEM = 165 CLIENT# = 165 Land Item SCHEDULE: 1 100
Description = CASING PIPE, PVC C905 DR 14, 18 IN Unit = LF Takeoff Quan: 18.000 Engr Quan: 18.000

165.01 CASING PIPE, PVC C905 DR 14, 18 IN Quan: 18.00 LF Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		4.00	CH	Prod:	4.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI165PIPE	BID ITEM 165 P@110.25	1.00	1.00	LS	2,493.610		2,749				2,749
8EX135A	135 Excavator W/Attach	1.00	4.00	HR	68.251				273		273
8EX200	200 Excavator	1.00	4.00	HR	78.000				312		312
8LO950	950 Loader	1.00	4.00	HR	81.500				326		326
FOCI	Civil Forman	1.00	4.00	MH	77.060	546					546
LAP	Labor Underground Water	2.00	8.00	MH	53.880	768					768
OPE	Operator - Excavator	1.00	4.00	MH	74.560	529					529
OPL	Operator - Loader	1.00	4.00	MH	74.560	529					529
\$6,031.66	1.1111 MH/LF		20.00	MH	[111.313]	2,371	2,749		911		6,032

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 165	CLIENT# = 165		Land Item	SCHEDULE: 1	100					
Description =	CASING PIPE, PVC C905 DR 14, 18 IN		Unit =	LF	Takeoff Quan:		18.000	Engr Quan:		18.000
=====> Item Totals:	165 - CASING PIPE, PVC C905 DR 14, 18 IN									
\$6,031.66	1.1111 MH/LF	20.00	MH	[111.313]	2,371	2,749		911		6,032
335.092	18 LF				131.75	152.73		50.61		335.09

BID ITEM = 166	CLIENT# = 166		Land Item	SCHEDULE: 1	100					
Description =	PERK FILTER CONCRETE CATCH BASIN TRIPLE		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
166.01	PERK FILTER CONCRETE CATCH BASIN TRIPL	Quan:	2.00	EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>UNS</u>	Underground Utilities 4 Man	16.00	CH	Prod:	16.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2BI166PIPE	BID ITEM 166 P@110.25	1.00	1.00	LS	29,172.000	32,162				32,162
3DEDU02D	Dirt Trucking and Dump	1.00	20.00	TCY	24.500		490			490
8BA310A	418 Backhoe W/Attachme	1.00	16.00	HR	51.051			817		817
8EX100	100 Excavator	1.00	16.00	HR	52.300			837		837
FOCI	Civil Forman	1.00	16.00	MH	77.060	1,610				1,610
LAP	Labor Underground Water	1.00	16.00	MH	53.880	1,136				1,136
OPB	Operator - Backhoe	1.00	16.00	MH	74.560	1,559				1,559
OPE	Operator - Excavator	1.00	16.00	MH	74.560	1,559				1,559
\$40,170.51	32.0000 MH/EA	64.00	MH	[2464.535]	5,865	32,162	490	1,654		40,171
=====> Item Totals:	166 - PERK FILTER CONCRETE CATCH BASIN TRIPLE									
\$40,170.51	32.0000 MH/EA	64.00	MH	[2464.535]	5,865	32,162	490	1,654		40,171
20,085.255	2 EA				2,932.39	16,081.07	245.00	826.80		20,085.26

BID ITEM = 167	CLIENT# = 167		Land Item	SCHEDULE: 1	100					
Description =	TEE, PVC, 10 IN		Unit =	EA	Takeoff Quan:		3.000	Engr Quan:		3.000
167.01	TEE, PVC, 10 IN	Quan:	3.00	EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>UNM</u>	Underground Utilities 6 Man	3.00	CH	Prod:	3.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI167PIPE	BID ITEM 167 P@110.25	1.00	1.00	LS	1,158.750	1,278				1,278
8EX135A	135 Excavator W/Attach	1.00	3.00	HR	68.251			205		205
8EX200	200 Excavator	1.00	3.00	HR	78.000			234		234
8LO950	950 Loader	1.00	3.00	HR	81.500			244		244
FOCI	Civil Forman	1.00	3.00	MH	77.060	302				302
LAP	Labor Underground Water	2.00	6.00	MH	53.880	426				426
OPE	Operator - Excavator	1.00	3.00	MH	74.560	292				292
OPL	Operator - Loader	1.00	3.00	MH	74.560	292				292
\$3,273.40	5.0000 MH/EA	15.00	MH	[367.337]	1,313	1,278		683		3,273
=====> Item Totals:	167 - TEE, PVC, 10 IN									
\$3,273.40	5.0000 MH/EA	15.00	MH	[367.337]	1,313	1,278		683		3,273
1,091.133	3 EA				437.55	425.84		227.74		1,091.13

BID ITEM = 168	CLIENT# = 168		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SEWER BYPASS		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
168.01	MH 1 TEMP BYPASS	Quan:	1.00	LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>UNM</u>	Underground Utilities 6 Man	8.00	CH	Prod:	8.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
3TBMH1	TEMP BYPASS PUMPS	1.00	1.00	LS	7,500.000		7,500			7,500

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 168	CLIENT# = 168								
Description =	TEMPORARY SEWER BYPASS			Unit =	LS	Takeoff Quan:	1.000	Engr Quan:	1.000
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546		546
8EX200	200 Excavator	1.00	8.00 HR	78.000			624		624
8LO950	950 Loader	1.00	8.00 HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136				1,136
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780
\$12,822.40	40.0000 MH/LS		40.00 MH	[2938.68]	3,500	7,500	1,822		12,822
168.02	MH 4 TEMP BYPASS			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG
<u>UNM</u>	Underground Utilities 6 Man		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
3TBMH4	TEMP BYPASS MH 4	1.00	1.00 LS	20,000.000		20,000			20,000
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546		546
8EX200	200 Excavator	1.00	8.00 HR	78.000			624		624
8LO950	950 Loader	1.00	8.00 HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136				1,136
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780
\$25,322.40	40.0000 MH/LS		40.00 MH	[2938.68]	3,500	20,000	1,822		25,322
168.03	MH 6 TEMP BYPASS			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG
<u>UNM</u>	Underground Utilities 6 Man		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
3TBMH6	MH 6 TEMP BYPASS	1.00	1.00 LS	7,500.000		7,500			7,500
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546		546
8EX200	200 Excavator	1.00	8.00 HR	78.000			624		624
8LO950	950 Loader	1.00	8.00 HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136				1,136
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780
\$12,822.40	40.0000 MH/LS		40.00 MH	[2938.68]	3,500	7,500	1,822		12,822
168.04	MH 17 TEMP BYPASS			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: S10	WC: WAAVG
<u>UNM</u>	Underground Utilities 6 Man		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
3TBMH17	MH 17 TEMP BYPASS	1.00	1.00 LS	15,000.000		15,000			15,000
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546		546
8EX200	200 Excavator	1.00	8.00 HR	78.000			624		624
8LO950	950 Loader	1.00	8.00 HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	1,092				1,092
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,537				1,537
OPE	Operator - Excavator	1.00	8.00 MH	74.560	1,057				1,057
OPL	Operator - Loader	1.00	8.00 MH	74.560	1,057				1,057
\$21,564.86	40.0000 MH/LS		40.00 MH	[4007.28]	4,743	15,000	1,822		21,565
168.05	MH 10C TEMP BYPASS			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG
<u>UNM</u>	Underground Utilities 6 Man		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
3TBMH10C	MH 10C TEMP BYPASS	1.00	1.00 LS	7,500.000		7,500			7,500
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546		546
8EX200	200 Excavator	1.00	8.00 HR	78.000			624		624
8LO950	950 Loader	1.00	8.00 HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136				1,136
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 168	CLIENT# = 168									
Description =	TEMPORARY SEWER BYPASS		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	1.000	Engr Quan:			1.000
\$12,822.40	40.0000 MH/LS		40.00 MH	[2938.68]	3,500		7,500	1,822		12,822
168.06	MH 12 TEMP BYPASS		Quan: 1.00 LS	Hrs/Shift: 10.00	Cal: 510	WC: WAAVG				
<u>UNM</u>	Underground Utilities 6 Man		8.00 CH	Prod: 8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00		
3TBMH12	TEMP BYPASS MH 12	1.00	1.00 LS	7,500.000		7,500				7,500
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546			546
8EX200	200 Excavator	1.00	8.00 HR	78.000			624			624
8LO950	950 Loader	1.00	8.00 HR	81.500			652			652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805					805
LAP	Labor Underground Water	2.00	16.00 MH	53.880	1,136					1,136
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780					780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780					780
\$12,822.40	40.0000 MH/LS		40.00 MH	[2938.68]	3,500		7,500	1,822		12,822
=====>	Item Totals: 168 - TEMPORARY SEWER BYPASS									
\$98,176.86	240.0000 MH/LS		240.00 MH	[18700.68]	22,245		65,000	10,932		98,177
98,176.860	1 LS				22,244.86		65,000.00	10,932.00		98,176.86
BID ITEM = 169	CLIENT# = 169									
Description =	ADJUST EXISTING MH, CB, OR VC		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	400.000	Engr Quan:			400.000
169.01	ADJUST EXISTING MH, CB, OR VC		Quan: 400.00 EA	Hrs/Shift: 10.00	Cal: 510	WC: WAAVG				
<u>EAS</u>	Earthwork 4 Man Crew		358.20 CH	Prod: 358.2090 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00		
8BA310A	418 Backhoe W/Attachme	1.00	358.21 HR	51.051			18,287			18,287
8EX100	100 Excavator	1.00	358.21 HR	52.300			18,734			18,734
FOCI	Civil Forman	1.00	358.21 MH	77.060	36,053					36,053
LAG	General Laborer	2.00	716.42 MH	52.910	49,978					49,978
OPE	Operator - Excavator	1.00	358.21 MH	74.560	34,908					34,908
\$157,959.51	3.5821 MH/EA		1,432.84 MH	[253.598]	120,938		37,021			157,960
=====>	Item Totals: 169 - ADJUST EXISTING MH, CB, OR VC									
\$157,959.51	3.5821 MH/EA		1,432.84 MH	[253.598]	120,938		37,021			157,960
394.899	400 EA				302.35		92.55			394.90
BID ITEM = 170	CLIENT# = 170									
Description =	ADJUST EXISTING INLET		Land Item Unit =	SCHEDULE: 1 100	Takeoff Quan:	33.000	Engr Quan:			33.000
170.01	ADJUST EXISTING INLET		Quan: 33.00 EA	Hrs/Shift: 10.00	Cal: 510	WC: WAAVG				
<u>EAS</u>	Earthwork 4 Man Crew		16.00 CH	Prod: 16.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00		
8BA310A	418 Backhoe W/Attachme	1.00	16.00 HR	51.051			817			817
8EX100	100 Excavator	1.00	16.00 HR	52.300			837			837
FOCI	Civil Forman	1.00	16.00 MH	77.060	1,610					1,610
LAG	General Laborer	2.00	32.00 MH	52.910	2,232					2,232
OPE	Operator - Excavator	1.00	16.00 MH	74.560	1,559					1,559
\$7,055.49	1.9393 MH/EA		64.00 MH	[137.302]	5,402		1,654			7,055
=====>	Item Totals: 170 - ADJUST EXISTING INLET									
\$7,055.49	1.9393 MH/EA		64.00 MH	[137.302]	5,402		1,654			7,055
213.803	33 EA				163.69		50.11			213.80

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract

BID ITEM = **171** CLIENT# = 171 Land Item SCHEDULE: 1 100
Description = ADJUST EXISTING VALVE BOX Unit = EA Takeoff Quan: 184.000 Engr Quan: 184.000

171.01 ADJUST EXISTING VALVE BOX Quan: 184.00 EA Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		64.64	CH	Prod:	64.6486	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	64.65	HR	51.051				3,300		3,300
8EX100	100 Excavator	1.00	64.65	HR	52.300				3,381		3,381
FOCI	Civil Forman	1.00	64.65	MH	77.060	6,507					6,507
LAG	General Laborer	2.00	129.30	MH	52.910	9,020					9,020
OPE	Operator - Excavator	1.00	64.65	MH	74.560	6,300					6,300
\$28,508.62	1.4054 MH/EA		258.60	MH	[99.499]	21,827			6,682		28,509

=====> **Item Totals: 171 - ADJUST EXISTING VALVE BOX**
\$28,508.62 1.4054 MH/EA 258.60 MH [99.499] 21,827 6,682 **28,509**
154.938 184 EA 118.63 36.31 154.94

BID ITEM = **172** CLIENT# = 172 Land Item SCHEDULE: 1 100
Description = ADJUST EXISTING HANDHOLE Unit = EA Takeoff Quan: 225.000 Engr Quan: 225.000

172.01 ADJUST EXISTING HANDHOLE Quan: 225.00 EA Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		112.00	CH	Prod:	112.0044	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	112.00	HR	51.051				5,718		5,718
8EX100	100 Excavator	1.00	112.00	HR	52.300				5,858		5,858
FOCI	Civil Forman	1.00	112.00	MH	77.060	11,273					11,273
LAG	General Laborer	2.00	224.01	MH	52.910	15,627					15,627
OPE	Operator - Excavator	1.00	112.00	MH	74.560	10,914					10,914
\$49,389.22	1.9911 MH/EA		448.01	MH	[140.965]	37,814			11,575		49,389

=====> **Item Totals: 172 - ADJUST EXISTING HANDHOLE**
\$49,389.22 1.9911 MH/EA 448.01 MH [140.965] 37,814 11,575 **49,389**
219.508 225 EA 168.06 51.45 219.51

BID ITEM = **173** CLIENT# = 173 Land Item SCHEDULE: 1 100
Description = UTILITY CASTING, TYPE 230 Unit = EA Takeoff Quan: 129.000 Engr Quan: 129.000

173.01 UTILITY CASTING, TYPE 230 Quan: 129.00 EA Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		64.00	CH	Prod:	64.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2CPSZ230	TYPE 230 CASTI@110.25	1.00	129.00	EA	785.000	111,645					111,645
8BA310A	418 Backhoe W/Attachme	1.00	64.00	HR	51.051				3,267		3,267
8EX100	100 Excavator	1.00	64.00	HR	52.300				3,347		3,347
FOCI	Civil Forman	1.00	64.00	MH	77.060	6,441					6,441
LAG	General Laborer	2.00	128.00	MH	52.910	8,929					8,929
OPE	Operator - Excavator	1.00	64.00	MH	74.560	6,237					6,237
\$139,866.67	1.9844 MH/EA		256.00	MH	[140.494]	21,608	111,645		6,614		139,867

=====> **Item Totals: 173 - UTILITY CASTING, TYPE 230**
\$139,866.67 1.9844 MH/EA 256.00 MH [140.494] 21,608 111,645 **139,867**
1,084.238 129 EA 167.50 865.46 51.27 1,084.24

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = **174** CLIENT# = 174 Land Item SCHEDULE: 1 100
Description = UTILITY CASTING, TYPE 361 (9 1/4-INCH DE Unit = EA Takeoff Quan: 29.000 Engr Quan: 29.000

174.01 UTILITY CASTING, TYPE 361 (9 1/4-INCH DE Quan: 29.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		14.00	CH	Prod:	14.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2CPSZ361	TYPE 361 CASTI@110.25	1.00	29.00	EA	800.000		25,578				25,578
8BA310A	418 Backhoe W/Attachme	1.00	14.00	HR	51.051			715			715
8EX100	100 Excavator	1.00	14.00	HR	52.300			732			732
FOCI	Civil Forman	1.00	14.00	MH	77.060	1,409					1,409
LAG	General Laborer	2.00	28.00	MH	52.910	1,953					1,953
OPE	Operator - Excavator	1.00	14.00	MH	74.560	1,364					1,364
\$31,751.56	1.9310 MH/EA		56.00	MH	[136.709]	4,727	25,578	1,447			31,752

====> **Item Totals: 174 - UTILITY CASTING, TYPE 361 (9 1/4-INCH DE**
\$31,751.56 1.9310 MH/EA 56.00 MH [136.709] 4,727 25,578 1,447 **31,752**
1,094.881 29 EA 162.99 882.00 49.89 1,094.88

BID ITEM = **175** CLIENT# = 175 Land Item SCHEDULE: 1 100
Description = UTILITY CASTING, TYPE 230 (13-INCH DEPTH Unit = EA Takeoff Quan: 3.000 Engr Quan: 3.000

175.01 UTILITY CASTING, TYPE 230 (13-INCH DEPTH Quan: 3.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		1.50	CH	Prod:	1.5000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2CPSZ230D	TYPE 230 DEEP @110.25	1.00	3.00	EA	800.000		2,646				2,646
8BA310A	418 Backhoe W/Attachme	1.00	1.50	HR	51.051			77			77
8EX100	100 Excavator	1.00	1.50	HR	52.300			78			78
FOCI	Civil Forman	1.00	1.50	MH	77.060	151					151
LAG	General Laborer	2.00	3.00	MH	52.910	209					209
OPE	Operator - Excavator	1.00	1.50	MH	74.560	146					146
\$3,307.45	2.0000 MH/EA		6.00	MH	[141.59]	506	2,646	155			3,307

====> **Item Totals: 175 - UTILITY CASTING, TYPE 230 (13-INCH DEPTH**
\$3,307.45 2.0000 MH/EA 6.00 MH [141.59] 506 2,646 155 **3,307**
1,102.483 3 EA 168.81 882.00 51.67 1,102.48

BID ITEM = **176** CLIENT# = 176 Land Item SCHEDULE: 1 100
Description = PIPE LINING, 6IN Unit = LF Takeoff Quan: 22.000 Engr Quan: 22.000

176.01 PIPE LINING, 6IN Quan: 22.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4LINE	PIPE LINING SUB	1.00	22.00	LF	300.000			6,600			6,600
-------	-----------------	------	-------	----	---------	--	--	-------	--	--	-------

BID ITEM = **177** CLIENT# = 177 Land Item SCHEDULE: 1 100
Description = PIPE LINING, 8IN Unit = LF Takeoff Quan: 84.000 Engr Quan: 84.000

177.01 PIPE LINING, 8IN Quan: 84.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4LINE	PIPE LINING SUB	1.00	84.00	LF	300.000			25,200			25,200
-------	-----------------	------	-------	----	---------	--	--	--------	--	--	--------

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment Contract	

BID ITEM = 178 CLIENT# = 178 Land Item SCHEDULE: 1 100
Description = CONSTRUCTION STORMWATER & EROSION CONTR Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

178.01 CONSTRUCTION STORMWATER & EROSION CO Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

3EROSION	EROSION CONTROL MA	1.00	1.00 LS	50,000.000		50,000			50,000
3SWEEPER	SWEEPER TRUCK	1.00	1,000.00 HR	225.000		225,000			225,000
\$275,000.00				[]		275,000			275,000

====> **Item Totals: 178 - CONSTRUCTION STORMWATER & EROSION CONTRO**
\$275,000.00 [] 275,000 **275,000**
275,000.000 1 LS 275,000.00 275,000.00

BID ITEM = 179 CLIENT# = 179 Land Item SCHEDULE: 1 100
Description = TREE, VEGETATION & SOIL PROTECTION PLAN Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

179.01 MAKE TREE BOXES Quan: 150.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>ZZZZ</u>	SITE FURNISHINGS CREW		50.00 CH	Prod:	50.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
3TREEBOX	TREE BOX	1.00	150.00 EA	150.000		22,500			22,500
LAG	General Laborer	2.00	100.00 MH	52.910	6,976				6,976
\$29,476.03	0.6666 MH/EA		100.00 MH	[38.801]	6,976	22,500			29,476

179.02 INSTALL TREE BOX Quan: 400.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>ZZZZ</u>	SITE FURNISHINGS CREW		80.00 CH	Prod:	80.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
LAG	General Laborer	2.00	160.00 MH	52.910	11,162				11,162
\$11,161.65	0.4000 MH/EA		160.00 MH	[23.28]	11,162				11,162

179.03 REMOVE TREE BOX Quan: 400.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>ZZZZ</u>	SITE FURNISHINGS CREW		80.00 CH	Prod:	80.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
LAG	General Laborer	2.00	160.00 MH	52.910	11,162				11,162
\$11,161.65	0.4000 MH/EA		160.00 MH	[23.28]	11,162				11,162

====> **Item Totals: 179 - TREE, VEGETATION & SOIL PROTECTION PLAN**
\$51,799.33 420.0000 MH/LS 420.00 MH [24444.42] 29,299 22,500 **51,799**
51,799.330 1 LS 29,299.33 22,500.00 51,799.33

BID ITEM = 180 CLIENT# = 180 Land Item SCHEDULE: 1 100
Description = SPILL PLAN (SP) Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

180.01 SPILL PLAN Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

3SP	SPILL PLAN	1.00	1.00 LS	5,000.000		5,000			5,000
-----	------------	------	---------	-----------	--	-------	--	--	-------

====> **Item Totals: 180 - SPILL PLAN (SP)**
\$5,000.00 [] 5,000 **5,000**
5,000.000 1 LS 5,000.00 5,000.00

BID ITEM = 181 CLIENT# = 181 Land Item SCHEDULE: 1 100
Description = TEMPORARY DISCHARGE PLAN (TDP) Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 181	CLIENT# = 181	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY DISCHARGE PLAN (TDP)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
181.01	TEMPORARY DISCHARGE PLAN (TDP)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
3TDP	TEMPORARY DISCHAR	1.00	1.00 LS	5,000.000			5,000			5,000
====>	Item Totals: 181 - TEMPORARY DISCHARGE PLAN (TDP)									
\$5,000.00				[]			5,000			5,000
5,000.000	1 LS						5,000.00			5,000.00
BID ITEM = 182	CLIENT# = 182	Land Item	SCHEDULE: 1	100						
Description =	SEEDED LAWN INSTALATIONS	Unit =	SF	Takeoff	Quan:		5,510.000	Engr Quan:		5,510.000
182.01	EROSION CONTROL, HYDRO-SEEDING	Quan:	5,510.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	5,510.00 SF	1.500				8,265		8,265
BID ITEM = 183	CLIENT# = 183	Land Item	SCHEDULE: 1	100						
Description =	TREE, DECIDUOUS, 1-1/2 IN TO 1-3/4 IN CA	Unit =	EA	Takeoff	Quan:		1.000	Engr Quan:		1.000
183.01	TREE, DECIDUOUS, 1-1/2 IN TO 1-3/4 IN CA	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	1.00 EA	750.000				750		750
BID ITEM = 184	CLIENT# = 184	Land Item	SCHEDULE: 1	100						
Description =	TREE, DECIDUOUS, 1-3/4 IN TO 2 IN CAL	Unit =	EA	Takeoff	Quan:		85.000	Engr Quan:		85.000
184.01	TREE, DECIDUOUS, 1-3/4 IN TO 2 IN CAL	Quan:	85.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	85.00 EA	750.000				63,750		63,750
BID ITEM = 185	CLIENT# = 185	Land Item	SCHEDULE: 1	100						
Description =	SHRUB, DECIDUOUS, 5 GAL	Unit =	EA	Takeoff	Quan:		450.000	Engr Quan:		450.000
185.01	SHRUB, DECIDUOUS, 5 GAL	Quan:	450.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	450.00 EA	45.000				20,250		20,250
BID ITEM = 186	CLIENT# = 186	Land Item	SCHEDULE: 1	100						
Description =	GROUND COVER, 4 IN POT	Unit =	EA	Takeoff	Quan:		732.000	Engr Quan:		732.000
186.01	GROUND COVER, 4 IN POT	Quan:	732.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	732.00 EA	5.000				3,660		3,660

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 187	CLIENT# = 187	Land Item	SCHEDULE: 1	100						
Description = TOPSOIL, TYPE A		Unit =	CY	Takeoff Quan:	354.000	Engr Quan:	354.000			
187.01	TOPSOIL, TYPE A	Quan:	354.00 CY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	354.00 CY	85.000				30,090	30,090	
BID ITEM = 188	CLIENT# = 188	Land Item	SCHEDULE: 1	100						
Description = GROUND COVER, 1 GAL		Unit =	EA	Takeoff Quan:	1,087.000	Engr Quan:	1,087.000			
188.01	GROUND COVER, 1 GAL	Quan:	1,087.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	1,087.00 EA	18.000				19,566	19,566	
BID ITEM = 189	CLIENT# = 189	Land Item	SCHEDULE: 1	100						
Description = GROUND COVER, 2 GAL		Unit =	EA	Takeoff Quan:	48.000	Engr Quan:	48.000			
189.01	GROUND COVER, 2 GAL	Quan:	48.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	48.00 EA	30.000				1,440	1,440	
BID ITEM = 190	CLIENT# = 190	Land Item	SCHEDULE: 1	100						
Description = MULCH, BARK		Unit =	CY	Takeoff Quan:	71.000	Engr Quan:	71.000			
190.01	MULCH, BARK	Quan:	71.00 CY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	71.00 CY	110.000				7,810	7,810	
BID ITEM = 191	CLIENT# = 191	Land Item	SCHEDULE: 1	100						
Description = TREE ROOT BARRIER		Unit =	LF	Takeoff Quan:	1,176.000	Engr Quan:	1,176.000			
191.01	TREE ROOT BARRIER	Quan:	1,176.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	1,176.00 LF	20.000				23,520	23,520	
BID ITEM = 192	CLIENT# = 192	Land Item	SCHEDULE: 1	100						
Description = LANDSCAPE ESTABLISHMENT, MIN. BID = \$40,		Unit =	LS	Takeoff Quan:	1.000	Engr Quan:	1.000			
192.01	LANDSCAPE ESTABLISHMENT, MIN. BID = \$40,	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	1.00 LS	40,000.000				40,000	40,000	
BID ITEM = 193	CLIENT# = 193	Land Item	SCHEDULE: 1	100						
Description = FLEXIBLE POROUS SURFACE TREATMENT		Unit =	SF	Takeoff Quan:	16,859.000	Engr Quan:	16,859.000			

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----	------------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 193 CLIENT# = 193 Land Item SCHEDULE: 1 100
Description = FLEXIBLE POROUS SURFACE TREATMENT Unit = SF Takeoff Quan: 16,859.000 Engr Quan: 16,859.000

193.01 FLEXIBLE POROUS SURFACE TREATMENT Quan: 16,859.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew		400.00	CH	Prod:	400.0000	CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2FLEXIPAVE	FLEXI PAVE MAT@110.2	1.00	1.00	LS	113,461.000		125,091				125,091
CEJ	Cement Mason	5.00	2,000.00	MH	64.980	170,395					170,395
FOCO	Concrete Forman	1.00	400.00	MH	68.980	36,125					36,125
\$331,611.03	0.1423 MH/SF		2,400.00	MH	[10.28]	206,520	125,091				331,611

====> **Item Totals: 193 - FLEXIBLE POROUS SURFACE TREATMENT**
\$331,611.03 0.1423 MH/SF 2,400.00 MH [10.28] 206,520 125,091 **331,611**
19.670 16859 SF 12.25 7.42 19.67

BID ITEM = 194 CLIENT# = 194 Land Item SCHEDULE: 1 100
Description = PEDESTRIAN ENHANCEMENTS ON MADISON ST I- Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

194.01 1-5 PLANTERS Quan: 50.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		8.00	CH	Prod:	8.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2PLANTERS	PLANTERS@110.25%	1.00	50.00	EA	2,730.980		150,545				150,545
8BA310A	418 Backhoe W/Attachme	1.00	8.00	HR	51.051			408			408
8EX100	100 Excavator	1.00	8.00	HR	52.300			418			418
FOCI	Civil Forman	1.00	8.00	MH	77.060	805					805
LAG	General Laborer	2.00	16.00	MH	52.910	1,116					1,116
OPE	Operator - Excavator	1.00	8.00	MH	74.560	780					780
\$154,073.02	0.6400 MH/EA		32.00	MH	[45.31]	2,701	150,545		827		154,073

194.02 1-5 DECRIITIVE PANELS Quan: 550.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>ZZZZ</u>	SITE FURNISHINGS CREW		32.00	CH	Prod:	32.0000	CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
2DECPANELS	DECRAITIVE PANE@110.	1.00	550.00	LF	100.520		60,953				60,953
LAG	General Laborer	2.00	64.00	MH	52.910	4,465					4,465
\$65,417.48	0.1163 MH/LF		64.00	MH	[6.772]	4,465	60,953				65,417

194.03 1-5 LANDSCAPING Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4LAND	Landscape sub	1.00	1.00	LS	30,000.000				30,000		30,000
-------	---------------	------	------	----	------------	--	--	--	--------	--	--------

====> **Item Totals: 194 - PEDESTRIAN ENHANCEMENTS ON MADISON ST I-**
\$249,490.50 96.0000 MH/LS 96.00 MH [5990.34] 7,166 211,498 827 30,000 **249,491**
249,490.500 1 LS 7,165.61 211,498.09 826.80 30,000.00 249,490.50

BID ITEM = 195 CLIENT# = 195 Land Item SCHEDULE: 1 100
Description = ROOT PRUNING AND TRIM VEGETATION Unit = FA Takeoff Quan: 50,000.000 Engr Quan: 50,000.000

195.01 ROOT PRUNING AND TRIM VEGETATION Quan: 50,000.00 FA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

9FORCE	FORCE ACCOUNT	1.00	50,000.00	FA	0.890		44,500				44,500
--------	---------------	------	-----------	----	-------	--	--------	--	--	--	--------

====> **Item Totals: 195 - ROOT PRUNING AND TRIM VEGETATION**
\$44,500.00 [] 44,500 **44,500**
0.890 50000 FA 0.89 0.89

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----	------------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 196 CLIENT# = 196 Land Item SCHEDULE: 1 100
Description = REPAIR IRRIGATION SYSTEM Unit = FA Takeoff Quan: 50,000.000 Engr Quan: 50,000.000

196.01 REPAIR IRRIGATION SYSTEM Quan: 50,000.00 FA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

9FORCE	FORCE ACCOUNT	1.00	50,000.00 FA	0.890			44,500			44,500
--------	---------------	------	--------------	-------	--	--	--------	--	--	--------

====> Item Totals: 196 - REPAIR IRRIGATION SYSTEM										
\$44,500.00				[]			44,500			44,500
0.890	50000 FA						0.89			0.89

BID ITEM = 197 CLIENT# = 197 Land Item SCHEDULE: 1 100
Description = CURB, CEM CONC W/ 25% POZZOLANS Unit = LF Takeoff Quan: 14,654.000 Engr Quan: 14,654.000

197.01 CURB, CEM CONC W/ 25% POZZOLANS Quan: 14,654.00 LF Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew		669.17 CH	Prod: 669.1795 CH		Lab Pcs: 6.00	Eqp Pcs: 0.00
2CR025	2500LB READY M@110.2	1.02	138.61 CY	115.350	17,628		17,628
2CRUBHOOP	CURB HOOPS@110.25%	1.00	4,885.01 EA	2.000	10,771		10,771
CEJ	Cement Mason	5.00	3,345.90 MH	64.980	301,923		301,923
FOCO	Concrete Forman	1.00	669.18 MH	68.980	64,016		64,016
\$394,337.97	0.2739 MH/LF		4,015.08 MH	[20.985]	365,939	28,399	394,338

====> Item Totals: 197 - CURB, CEM CONC W/ 25% POZZOLANS							
\$394,337.97	0.2739 MH/LF		4,015.08 MH	[20.985]	365,939	28,399	394,338
26.910	14654 LF				24.97	1.94	26.91

BID ITEM = 198 CLIENT# = 198 Land Item SCHEDULE: 1 100
Description = CURB AND GUTTER, CEM CONC W/ 25% POZZOL Unit = LF Takeoff Quan: 522.000 Engr Quan: 522.000

198.01 CURB AND GUTTER, CEM CONC W/ 25% POZZO Quan: 522.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew		40.00 CH	Prod: 40.0000 CH		Lab Pcs: 6.00	Eqp Pcs: 0.00
2CR030	3000LB READY M@110.2	1.02	43.86 CY	117.800	5,696		5,696
CEJ	Cement Mason	5.00	200.00 MH	64.980	17,039		17,039
FOCO	Concrete Forman	1.00	40.00 MH	68.980	3,613		3,613
\$26,348.32	0.4597 MH/LF		240.00 MH	[33.201]	20,652	5,696	26,348

====> Item Totals: 198 - CURB AND GUTTER, CEM CONC W/ 25% POZZOL							
\$26,348.32	0.4597 MH/LF		240.00 MH	[33.201]	20,652	5,696	26,348
50.476	522 LF				39.56	10.91	50.48

BID ITEM = 199 CLIENT# = 199 Land Item SCHEDULE: 1 100
Description = CURB, TRAFFIC, PRECAST Unit = LF Takeoff Quan: 64.000 Engr Quan: 64.000

199.01 CURB, TRAFFIC, PRECAST Quan: 64.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4STRI	Striping sub	1.00	64.00 LF	60.000			3,840	3,840
-------	--------------	------	----------	--------	--	--	-------	-------

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 200	CLIENT# = 200		Land Item	SCHEDULE: 1	100					
Description =	LANE MARKER, TYPE 2		Unit =	EA	Takeoff Quan:	685.000		Engr Quan:		685.000
200.01	LANE MARKER, TYPE 2		Quan:	685.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	685.00 EA	5.500				3,768		3,768
BID ITEM = 201	CLIENT# = 201		Land Item	SCHEDULE: 1	100					
Description =	FLEXIBLE DELINEATOR POST, 28"		Unit =	EA	Takeoff Quan:	110.000		Engr Quan:		110.000
201.01	FLEXIBLE DELINEATOR POST, 28"		Quan:	110.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	110.00 EA	145.000				15,950		15,950
BID ITEM = 202	CLIENT# = 202		Land Item	SCHEDULE: 1	100					
Description =	FLEXIBLE DELINEATOR POST, 48"		Unit =	EA	Takeoff Quan:	66.000		Engr Quan:		66.000
202.01	FLEXIBLE DELINEATOR POST, 48"		Quan:	66.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	66.00 EA	175.000				11,550		11,550
BID ITEM = 203	CLIENT# = 203		Land Item	SCHEDULE: 1	100					
Description =	FLEXIBLE DELINEATOR POST, 66"		Unit =	EA	Takeoff Quan:	9.000		Engr Quan:		9.000
203.01	FLEXIBLE DELINEATOR POST, 66"		Quan:	9.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	9.00 EA	200.000				1,800		1,800
BID ITEM = 204	CLIENT# = 204		Land Item	SCHEDULE: 1	100					
Description =	PLASTIC CURB WITH POST		Unit =	EA	Takeoff Quan:	141.000		Engr Quan:		141.000
204.01	PLASTIC CURB WITH POST		Quan:	141.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	141.00 EA	350.000				49,350		49,350
BID ITEM = 205	CLIENT# = 205		Land Item	SCHEDULE: 1	100					
Description =	RESET MONUMENT AND MONUMENT FRAME AND		Unit =	EA	Takeoff Quan:	43.000		Engr Quan:		43.000
205.01	RESET MONUMENT AND MONUMENT FRAME A		Quan:	43.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
EAS	Earthwork 4 Man Crew		21.00 CH	Prod:	21.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
4SURV	Surveying sub	1.00	43.00 EA	1,500.000				64,500	64,500	
8BA310A	418 Backhoe W/Attachme	1.00	21.00 HR	51.051				1,072	1,072	
8EX100	100 Excavator	1.00	21.00 HR	52.300				1,098	1,098	
FOCI	Civil Forman	1.00	21.00 MH	77.060	2,114				2,114	
LAG	General Laborer	2.00	42.00 MH	52.910	2,930				2,930	
OPE	Operator - Excavator	1.00	21.00 MH	74.560	2,046				2,046	
\$73,760.33	1.9534 MH/EA		84.00 MH	[138.299]	7,090			2,170	64,500	73,760

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 205	CLIENT# = 205		Land Item	SCHEDULE: 1	100					
Description =	RESET MONUMENT AND MONUMENT FRAME AND	Unit =	EA	Takeoff Quan:		43.000		Engr Quan:		43.000
====>	Item Totals: 205 - RESET MONUMENT AND MONUMENT FRAME AND CO									
\$73,760.33	1.9534 MH/EA	84.00 MH	[138.299]	7,090				2,170	64,500	73,760
1,715.357	43 EA			164.88				50.47	1,500.00	1,715.36

BID ITEM = 206	CLIENT# = 206		Land Item	SCHEDULE: 1	100					
Description =	CURB RAMP	Unit =	SY	Takeoff Quan:		2,085.000		Engr Quan:		2,085.000
206.01	CURB RAMP	Quan:	286.00 EA	Hrs/Shft:	10.00	Cal: S10	WC: WAAVG			
<u>COM</u>	Concrete 6 Man Crew	725.00 CH	Prod: 725.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00			
2CR025	2500LB READY M@110.2	1.00 349.00 CY	145.350	55,927			55,927			
CEJ	Cement Mason	5.00 3,625.00 MH	64.980	418,392			418,392			
FOCO	Concrete Forman	1.00 725.00 MH	68.980	88,736			88,736			
\$563,054.33	15.2097 MH/EA	4,350.00 MH	[1497.708]	507,128	55,927		563,054			
====>	Item Totals: 206 - CURB RAMP									
\$563,054.33	2.0863 MH/SY	4,350.00 MH	[205.441]	507,128	55,927		563,054			
270.050	2085 SY			243.23	26.82		270.05			

BID ITEM = 207	CLIENT# = 207		Land Item	SCHEDULE: 1	100					
Description =	DETECTABLE WARNING PLATE RETROFIT	Unit =	SF	Takeoff Quan:		13.000		Engr Quan:		13.000
207.01	DETECTABLE WARNING PLATE RETROFIT	Quan:	13.00 SF	Hrs/Shft:	10.00	Cal: S10	WC: WAAVG			
<u>COM</u>	Concrete 6 Man Crew	4.00 CH	Prod: 4.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00			
2TRUNK	TRUNKATED DOME@11	1.00 13.00 SF	13.850	199			199			
CEJ	Cement Mason	5.00 20.00 MH	64.980	2,308			2,308			
FOCO	Concrete Forman	1.00 4.00 MH	68.980	490			490			
\$2,996.46	1.8461 MH/SF	24.00 MH	[181.791]	2,798	199		2,996			
====>	Item Totals: 207 - DETECTABLE WARNING PLATE RETROFIT									
\$2,996.46	1.8461 MH/SF	24.00 MH	[181.791]	2,798	199		2,996			
230.497	13 SF			215.23	15.27		230.50			

BID ITEM = 208	CLIENT# = 208		Land Item	SCHEDULE: 1	100					
Description =	DETECTABLE WARNING PLATE	Unit =	SF	Takeoff Quan:		2,794.000		Engr Quan:		2,794.000
208.01	DETECTABLE WARNING PLATE	Quan:	2,794.00 SF	Hrs/Shft:	10.00	Cal: S10	WC: WAAVG			
2TRUNK	TRUNKATED DOME@11	1.00 2,794.00 SF	13.850	42,663			42,663			
====>	Item Totals: 208 - DETECTABLE WARNING PLATE									
\$42,663.33			[]	42,663			42,663			
15.270	2794 SF			15.27			15.27			

BID ITEM = 209	CLIENT# = 209		Land Item	SCHEDULE: 1	100					
Description =	SIDEWALK, CEM CONC W/ 25% POZZOLANS	Unit =	SY	Takeoff Quan:		17,608.000		Engr Quan:		17,608.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	--------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 209 CLIENT# = 209 Land Item SCHEDULE: 1 100
Description = SIDEWALK, CEM CONC W/ 25% POZZOLANS Unit = SY Takeoff Quan: 17,608.000 Engr Quan: 17,608.000

209.01 SIDEWALK, CEM CONC W/ 25% POZZOLANS Quan: 17,608.00 SY Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew		1,866.51	CH	Prod: 1,866.5197	CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR025	2500LB READY M@110.2	1.02	1,975.44	CY	115.350	251,223				251,223
CEJ	Cement Mason	5.00	9,332.60	MH	64.980	842,144				842,144
FOCO	Concrete Forman	1.00	1,866.52	MH	68.980	178,557				178,557
\$1,271,924.09	0.6360 MH/SY		11,199.12	MH	[48.713]	1,020,701	251,223			1,271,924

====> **Item Totals: 209 - SIDEWALK, CEM CONC W/ 25% POZZOLANS**
\$1,271,924.09 0.6360 MH/SY 11,199.12 MH [48.713] 1,020,701 251,223 **1,271,924**
72.236 17608 SY 57.97 14.27 72.24

BID ITEM = 210 CLIENT# = 210 Land Item SCHEDULE: 1 100
Description = SIDEWALK, THICKENED EDGE W/ 25% POZZOLAN Unit = LF Takeoff Quan: 18,647.000 Engr Quan: 18,647.000

210.01 SIDEWALK, THICKENED EDGE W/ 25% POZZOL Quan: 18,647.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

2CR025	2500LB READY M@110.2	1.50	1,294.39	CY	115.350	164,612				164,612
--------	----------------------	------	----------	----	---------	---------	--	--	--	---------

====> **Item Totals: 210 - SIDEWALK, THICKENED EDGE W/ 25% POZZOLAN**
\$164,611.94 [] 164,612 **164,612**
8.828 18647 LF 8.83 8.83

BID ITEM = 211 CLIENT# = 211 Land Item SCHEDULE: 1 100
Description = STREET NAME LETTER INLAY Unit = EA Takeoff Quan: 434.000 Engr Quan: 434.000

211.01 STREET NAME LETTER INLAY Quan: 434.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew		20.00	CH	Prod: 20.0000	CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2BRONZEINLEY	BRONZE INLEYS@110.2	1.00	434.00	EA	65.000	31,102				31,102
3SANDBLAST	SANDBLAST FINISH	1.00	1.00	LS	5,000.000		5,000			5,000
CEJ	Cement Mason	5.00	100.00	MH	64.980	8,520				8,520
FOCO	Concrete Forman	1.00	20.00	MH	68.980	1,806				1,806
\$46,427.55	0.2764 MH/EA		120.00	MH	[19.966]	10,326	31,102	5,000		46,428

====> **Item Totals: 211 - STREET NAME LETTER INLAY**
\$46,427.55 0.2764 MH/EA 120.00 MH [19.966] 10,326 31,102 5,000 **46,428**
106.976 434 EA 23.79 71.66 11.52 106.98

BID ITEM = 212 CLIENT# = 212 Land Item SCHEDULE: 1 100
Description = I-5 SPRING STREET CURB RAMP Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

212.01 REMOVE I-5 SPRING CURB RAMP Quan: 1.00 LS Hrs/Shft: 8.00 Cal: S08 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		8.00	CH	Prod: 8.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
4SAWC	Sawcutting	1.00	1.00	LS	0.580				1	1
8BA310A	418 Backhoe W/Attachme	1.00	8.00	HR	51.051			408		408
8EX100	100 Excavator	1.00	8.00	HR	52.300			418		418
FOCI	Civil Forman	1.00	8.00	MH	77.060	1,092				1,092
LAG	General Laborer	2.00	16.00	MH	52.910	1,510				1,510

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 212	CLIENT# = 212									
Description =	I-5 SPRING STREET CURB RAMP			Land Item Unit =	SCHEDULE: 1 100					
					LS Takeoff Quan:		1.000	Engr Quan:		1.000
OPE	Operator - Excavator	1.00	8.00 MH	74.560	1,057					1,057
\$4,486.16	32.0000 MH/LS		32.00 MH	[3089.28]	3,659			827	1	4,486
212.02	I-5 SPRING STREET CURB RAMP		Quan:	1.00 LS	Hrs/Shft:	8.00	Cal: S08	WC: WAAVG		
COM	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR025	2500LB READY M@110.2	1.00	10.00 CY	115.350		1,272				1,272
2TRUNK	TRUNKATED DOME@11	1.00	8.00 SF	13.850		122				122
CEJ	Cement Mason	5.00	40.00 MH	64.980	4,617					4,617
FOCO	Concrete Forman	1.00	8.00 MH	68.980	979					979
\$6,989.78	48.0000 MH/LS		48.00 MH	[4726.56]	5,596	1,394				6,990
====>	Item Totals: 212 - I-5 SPRING STREET CURB RAMP									
\$11,475.94	80.0000 MH/LS		80.00 MH	[7815.84]	9,255	1,394		827	1	11,476
11,475.940	1 LS				9,254.67	1,393.89		826.80	0.58	11,475.94
BID ITEM = 213	CLIENT# = 213									
Description =	BRICK PAVING			Land Item Unit =	SCHEDULE: 1 100					
					SY Takeoff Quan:		57.000	Engr Quan:		57.000
213.01	BRICK PAVING		Quan:	57.00 SY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
COM	Concrete 6 Man Crew		24.00 CH	Prod:	24.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2BRICK	BRICK PAVING M@110.2	1.00	1.00 LS	500.000		551				551
CEJ	Cement Mason	5.00	120.00 MH	64.980	10,224					10,224
FOCO	Concrete Forman	1.00	24.00 MH	68.980	2,168					2,168
\$12,942.47	2.5263 MH/SY		144.00 MH	[182.429]	12,391	551				12,942
====>	Item Totals: 213 - BRICK PAVING									
\$12,942.47	2.5263 MH/SY		144.00 MH	[182.429]	12,391	551				12,942
227.061	57 SY				217.39	9.67				227.06
BID ITEM = 214	CLIENT# = 214									
Description =	DRIVEWAY, CEM CONC, HES (24 HRS), 8 IN			Land Item Unit =	SCHEDULE: 1 100					
					SY Takeoff Quan:		1,692.000	Engr Quan:		1,692.000
214.01	DRIVEWAY, CEM CONC, HES (24 HRS), 8 IN		Quan:	1,692.00 SY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
COM	Concrete 6 Man Crew		314.00 CH	Prod:	314.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CRP1D	1 DAY PAVING M@110.2	1.02	431.46 CY	187.150		89,024				89,024
CEJ	Cement Mason	5.00	1,570.00 MH	64.980	133,760					133,760
FOCO	Concrete Forman	1.00	314.00 MH	68.980	28,358					28,358
\$251,142.80	1.1134 MH/SY		1,884.00 MH	[80.406]	162,118	89,024				251,143
====>	Item Totals: 214 - DRIVEWAY, CEM CONC, HES (24 HRS), 8 IN									
\$251,142.80	1.1134 MH/SY		1,884.00 MH	[80.406]	162,118	89,024				251,143
148.430	1692 SY				95.81	52.61				148.43
BID ITEM = 215	CLIENT# = 215									
Description =	SIGN, TRAFFIC, MAST ARM MOUNTED			Land Item Unit =	SCHEDULE: 1 100					
					EA Takeoff Quan:		69.000	Engr Quan:		69.000
215.01	SIGN, TRAFFIC, MAST ARM MOUNTED		Quan:	69.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 215	CLIENT# = 215									
Description =	SIGN, TRAFFIC, MAST ARM MOUNTED		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	69.000	Engr Quan:		69.000
2SIGNTMAST	TRAFFIC SIGN M@110.2	1.00	69.00 EA	110.000		8,368				8,368
4ELEC	Electrical sub	1.00	69.00 EA	340.000					23,460	23,460
\$31,827.98				[]		8,368			23,460	31,828
=====> Item Totals: 215 - SIGN, TRAFFIC, MAST ARM MOUNTED										
\$31,827.98				[]		8,368			23,460	31,828
461.275		69 EA				121.28			340.00	461.28

BID ITEM = 216	CLIENT# = 216									
Description =	SIGN, TRAFFIC, POLE MOUNTED		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	61.000	Engr Quan:		61.000
216.01	SIGN, TRAFFIC, POLE MOUNTED		Quan:	61.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZ</u>	SIGN CREW		30.00 CH	Prod:	30.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
2SIGNPM	SIGN TRAFFIC P@110.25	1.00	61.00 EA	110.000		7,398				7,398
LAG	General Laborer	1.00	30.00 MH	52.910	2,093					2,093
\$9,490.59	0.4918 MH/EA		30.00 MH	[28.623]	2,093	7,398				9,491
=====> Item Totals: 216 - SIGN, TRAFFIC, POLE MOUNTED										
\$9,490.59	0.4918 MH/EA		30.00 MH	[28.623]	2,093	7,398				9,491
155.583	61 EA				34.31	121.28				155.58

BID ITEM = 217	CLIENT# = 217									
Description =	SIGN, TRAFFIC, SPAN WIRE MOUNTED		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	13.000	Engr Quan:		13.000
217.01	SIGN, TRAFFIC, SPAN WIRE MOUNTED		Quan:	13.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
2SIGNTSP	TRAFFIC SIGN S@110.25	1.00	13.00 EA	100.000		1,433				1,433
4ELEC	Electrical sub	1.00	13.00 EA	340.000					4,420	4,420
\$5,853.25				[]		1,433			4,420	5,853
=====> Item Totals: 217 - SIGN, TRAFFIC, SPAN WIRE MOUNTED										
\$5,853.25				[]		1,433			4,420	5,853
450.250	13 EA					110.25			340.00	450.25

BID ITEM = 218	CLIENT# = 218									
Description =	SIGN, TRAFFIC, POST MOUNTED		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	446.000	Engr Quan:		446.000
218.01	SIGN, TRAFFIC		Quan:	446.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZ</u>	SIGN CREW		223.00 CH	Prod:	223.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
2SIGNTRAFFIC	TRAFFIC SIGN@110.25%	1.00	446.00 EA	70.000		34,420				34,420
LAG	General Laborer	1.00	223.00 MH	52.910	15,557					15,557
\$49,976.59	0.5000 MH/EA		223.00 MH	[29.1]	15,557	34,420				49,977
=====> Item Totals: 218 - SIGN, TRAFFIC, POST MOUNTED										
\$49,976.59	0.5000 MH/EA		223.00 MH	[29.1]	15,557	34,420				49,977
112.055	446 EA				34.88	77.18				112.06

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 219	CLIENT# = 219	Land Item	SCHEDULE: 1	100						
Description =	SIGN, STREET DESIGNATION, SPAN WIRE MOUN	Unit =	EA	Takeoff Quan:		2.000		Engr Quan:		2.000
219.01	SIGN, STREET DESIGNATION, SPAN WIRE MOU	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
2SIGNSDSP	SIGN STEET DES@110.25	1.00	2.00 EA	200.000		441				441
4ELEC	Electrical sub	1.00	2.00 EA	340.000				680		680
\$1,121.00			[]			441		680		1,121
====>	Item Totals: 219 - SIGN, STREET DESIGNATION, SPAN WIRE MOUN									
\$1,121.00			[]			441		680		1,121
560.500	2 EA					220.50		340.00		560.50
BID ITEM = 220	CLIENT# = 220	Land Item	SCHEDULE: 1	100						
Description =	SIGN, STREET DESIGNATION, MAST ARM MOUNT	Unit =	EA	Takeoff Quan:		52.000		Engr Quan:		52.000
220.01	SIGN, STREET DESIGNATION, MAST ARM MOU	Quan:	52.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
2SIGNSDMAS	SIGN STREET DE@110.2	1.00	52.00 EA	200.000		11,466				11,466
4ELEC	Electrical sub	1.00	52.00 EA	340.000				17,680		17,680
\$29,146.00			[]			11,466		17,680		29,146
====>	Item Totals: 220 - SIGN, STREET DESIGNATION, MAST ARM MOUNT									
\$29,146.00			[]			11,466		17,680		29,146
560.500	52 EA					220.50		340.00		560.50
BID ITEM = 221	CLIENT# = 221	Land Item	SCHEDULE: 1	100						
Description =	SIGN, STREET DESIGNATION, POLE MOUNTED	Unit =	EA	Takeoff Quan:		46.000		Engr Quan:		46.000
221.01	SIGN, STREET DESIGNATION, POLE MOUNTED	Quan:	46.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
<u>ZZZ</u>	SIGN CREW	23.00	CH	Prod: 23.0000 CH			Lab Pcs: 1.00	Eqp Pcs: 0.00		
2SIGNSDPM	SIGN STREET DE@110.2	1.00	46.00 EA	200.000		10,143				10,143
LAG	General Laborer	1.00	23.00 MH	52.910	1,604					1,604
\$11,747.48	0.5000 MH/EA	23.00	MH	[29.1]	1,604	10,143				11,747
====>	Item Totals: 221 - SIGN, STREET DESIGNATION, POLE MOUNTED									
\$11,747.48	0.5000 MH/EA	23.00	MH	[29.1]	1,604	10,143				11,747
255.380	46 EA				34.88	220.50				255.38
BID ITEM = 222	CLIENT# = 222	Land Item	SCHEDULE: 1	100						
Description =	SIGN, STREET NAME, OWNER FURNISHED, STEE	Unit =	EA	Takeoff Quan:		49.000		Engr Quan:		49.000
222.01	SIGN, STREET NAME, OWNER FURNISHED, STE	Quan:	49.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	49.00 EA	200.000				9,800		9,800
BID ITEM = 223	CLIENT# = 223	Land Item	SCHEDULE: 1	100						
Description =	SIGN, BUS ZONE, OWNER FURNISHED	Unit =	EA	Takeoff Quan:		8.000		Engr Quan:		8.000

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 223	CLIENT# = 223		Land Item	SCHEDULE: 1 100						
Description =	SIGN, BUS ZONE, OWNER FURNISHED		Unit =	EA	Takeoff Quan:		8.000	Engr Quan:		8.000
223.01	SIGN, BUS ZONE, OWNER FURNISHED		Quan:	8.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZ</u>	SIGN CREW		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	1.00	Eqp Pcs:		0.00
LAG	General Laborer	1.00	4.00 MH	52.910	279					279
\$279.04	0.5000 MH/EA		4.00 MH	[29.1]	279					279
====>	Item Totals: 223 - SIGN, BUS ZONE, OWNER FURNISHED									
\$279.04	0.5000 MH/EA		4.00 MH	[29.1]	279					279
34.880	8 EA				34.88					34.88
BID ITEM = 224	CLIENT# = 224		Land Item	SCHEDULE: 1 100						
Description =	SIGN, TRAFFIC, SIGNAL HEAD MOUNTED		Unit =	EA	Takeoff Quan:		8.000	Engr Quan:		8.000
224.01	SIGN, TRAFFIC, SIGNAL HEAD MOUNTED		Quan:	8.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	8.00 EA	150.000				1,200		1,200
BID ITEM = 225	CLIENT# = 225		Land Item	SCHEDULE: 1 100						
Description =	POST, TRAFFIC SIGN		Unit =	EA	Takeoff Quan:		223.000	Engr Quan:		223.000
225.01	POST, TRAFFIC SIGN		Quan:	223.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZ</u>	SIGN CREW		111.50 CH	Prod:	111.5000 CH	Lab Pcs:	1.00	Eqp Pcs:		0.00
2SIGNPOST	SIGN POST TRAF@110.2	1.00	223.00 EA	120.000	29,503					29,503
LAG	General Laborer	1.00	111.50 MH	52.910	7,778					7,778
\$37,281.18	0.5000 MH/EA		111.50 MH	[29.1]	7,778	29,503				37,281
====>	Item Totals: 225 - POST, TRAFFIC SIGN									
\$37,281.18	0.5000 MH/EA		111.50 MH	[29.1]	7,778	29,503				37,281
167.180	223 EA				34.88	132.30				167.18
BID ITEM = 226	CLIENT# = 226		Land Item	SCHEDULE: 1 100						
Description =	POST, STREET NAME		Unit =	EA	Takeoff Quan:		23.000	Engr Quan:		23.000
226.01	POST, STREET NAME		Quan:	23.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZ</u>	SIGN CREW		12.50 CH	Prod:	12.5000 CH	Lab Pcs:	1.00	Eqp Pcs:		0.00
2SIGNPOSTSN	SIGN POST STRE@110.2	1.00	23.00 EA	200.000	5,072					5,072
LAG	General Laborer	1.00	12.50 MH	52.910	872					872
\$5,943.51	0.5434 MH/EA		12.50 MH	[31.631]	872	5,072				5,944
====>	Item Totals: 226 - POST, STREET NAME									
\$5,943.51	0.5434 MH/EA		12.50 MH	[31.631]	872	5,072				5,944
258.413	23 EA				37.91	220.50				258.41
BID ITEM = 227	CLIENT# = 227		Land Item	SCHEDULE: 1 100						
Description =	POST, BUS ZONE		Unit =	EA	Takeoff Quan:		8.000	Engr Quan:		8.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 227	CLIENT# = 227									
Description =	POST, BUS ZONE		Land Item Unit =	SCHEDULE: 1 EA	100 Takeoff Quan:		8.000	Engr Quan:		8.000
227.01	POST, BUS ZONE			Quan:	8.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<u>ZZZ</u>	SIGN CREW		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
2SIGNPOSTBUS	SIGN POST BUS @110.25	1.00	8.00 EA	120.000		1,058				1,058
LAG	General Laborer	1.00	4.00 MH	52.910	279					279
\$1,337.44	0.5000 MH/EA		4.00 MH	[29.1]	279	1,058				1,337
=====> Item Totals:	227 - POST, BUS ZONE									
\$1,337.44	0.5000 MH/EA		4.00 MH	[29.1]	279	1,058				1,337
167.180	8 EA				34.88	132.30				167.18
BID ITEM = 228	CLIENT# = 228									
Description =	RELOCATE SIGN, TRAFFIC		Land Item Unit =	SCHEDULE: 1 EA	100 Takeoff Quan:		134.000	Engr Quan:		134.000
228.01	RELOCATE SIGN, TRAFFIC			Quan:	134.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<u>ZZZ</u>	SIGN CREW		134.00 CH	Prod:	134.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
LAG	General Laborer	1.00	134.00 MH	52.910	9,348					9,348
\$9,347.88	1.0000 MH/EA		134.00 MH	[58.201]	9,348					9,348
=====> Item Totals:	228 - RELOCATE SIGN, TRAFFIC									
\$9,347.88	1.0000 MH/EA		134.00 MH	[58.201]	9,348					9,348
69.760	134 EA				69.76					69.76
BID ITEM = 229	CLIENT# = 229									
Description =	RELOCATE SIGN, STREET NAME		Land Item Unit =	SCHEDULE: 1 EA	100 Takeoff Quan:		91.000	Engr Quan:		91.000
229.01	RELOCATE SIGN, STREET NAME			Quan:	91.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<u>ZZZ</u>	SIGN CREW		91.00 CH	Prod:	91.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
LAG	General Laborer	1.00	91.00 MH	52.910	6,348					6,348
\$6,348.19	1.0000 MH/EA		91.00 MH	[58.201]	6,348					6,348
=====> Item Totals:	229 - RELOCATE SIGN, STREET NAME									
\$6,348.19	1.0000 MH/EA		91.00 MH	[58.201]	6,348					6,348
69.760	91 EA				69.76					69.76
BID ITEM = 230	CLIENT# = 230									
Description =	RELOCATE SIGN, BUS ZONE		Land Item Unit =	SCHEDULE: 1 EA	100 Takeoff Quan:		2.000	Engr Quan:		2.000
230.01	RELOCATE SIGN, BUS ZONE			Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<u>ZZZ</u>	SIGN CREW		2.00 CH	Prod:	2.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
LAG	General Laborer	1.00	2.00 MH	52.910	140					140
\$139.52	1.0000 MH/EA		2.00 MH	[58.2]	140					140
=====> Item Totals:	230 - RELOCATE SIGN, BUS ZONE									
\$139.52	1.0000 MH/EA		2.00 MH	[58.2]	140					140
69.760	2 EA				69.76					69.76

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 231	CLIENT# = 231		Land Item	SCHEDULE: 1	100					
Description =	SIGN FOOTING, KCM, TYPE III		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
231.01	SIGN FOOTING, KCM, TYPE III		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	5.00 CY	121.150		668				668
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$4,798.24	48.0000 MH/EA		48.00 MH	[3466.14]	4,130	668				4,798
=====	Item Totals: 231 - SIGN FOOTING, KCM, TYPE III									
\$4,798.24	48.0000 MH/EA		48.00 MH	[3466.14]	4,130	668				4,798
4,798.240	1 EA				4,130.40	667.84				4,798.24
BID ITEM = 232	CLIENT# = 232		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, PAINT, 6 IN STRIPE		Unit =	LF	Takeoff Quan:		3,148.000	Engr Quan:		3,148.000
232.01	PAVEMENT MARKING, PAINT, 6 IN STRIPE		Quan:	3,148.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	3,148.00 LF	3.000				9,444		9,444
BID ITEM = 233	CLIENT# = 233		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, THERMOPLASTIC, 8 IN ST		Unit =	LF	Takeoff Quan:		44,997.000	Engr Quan:		44,997.000
233.01	PAVEMENT MARKING, THERMOPLASTIC, 8 IN		Quan:	44,997.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	44,997.00 LF	5.950				267,732		267,732
BID ITEM = 234	CLIENT# = 234		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, THERMOPLASTIC, LEGEND/		Unit =	EA	Takeoff Quan:		484.000	Engr Quan:		484.000
234.01	PAVEMENT MARKING, THERMOPLASTIC, LEG		Quan:	484.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	484.00 EA	200.000				96,800		96,800
BID ITEM = 235	CLIENT# = 235		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, THERMOPLASTIC, BIKE DE		Unit =	EA	Takeoff Quan:		100.000	Engr Quan:		100.000
235.01	PAVEMENT MARKING, THERMOPLASTIC, BIKE		Quan:	100.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	100.00 EA	125.000				12,500		12,500
BID ITEM = 236	CLIENT# = 236		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, MMA, 4 IN STRIPE		Unit =	LF	Takeoff Quan:		41,895.000	Engr Quan:		41,895.000
236.01	PAVEMENT MARKING, MMA, 4 IN STRIPE		Quan:	41,895.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 236	CLIENT# = 236		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, MMA, 4 IN STRIPE		Unit =	LF	Takeoff Quan:	41,895.000		Engr Quan:	41,895.000	
4STRI	Striping sub	1.00	41,895.00 LF	2.250				94,264	94,264	
BID ITEM = 237	CLIENT# = 237		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, MMA, 6 IN STRIPE		Unit =	LF	Takeoff Quan:	26,816.000		Engr Quan:	26,816.000	
237.01	PAVEMENT MARKING, MMA, 6 IN STRIPE		Quan: 26,816.00 LF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
4STRI	Striping sub	1.00	26,816.00 LF	2.750				73,744	73,744	
BID ITEM = 238	CLIENT# = 238		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, MMA, 8 IN STRIPE		Unit =	LF	Takeoff Quan:	5,209.000		Engr Quan:	5,209.000	
238.01	PAVEMENT MARKING, MMA, 8 IN STRIPE		Quan: 5,209.00 LF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
4STRI	Striping sub	1.00	5,209.00 LF	6.000				31,254	31,254	
BID ITEM = 239	CLIENT# = 239		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, MMA, LEGEND/SYMBOL		Unit =	EA	Takeoff Quan:	240.000		Engr Quan:	240.000	
239.01	PAVEMENT MARKING, MMA, LEGEND/SYMBOL		Quan: 240.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
4STRI	Striping sub	1.00	240.00 EA	200.000				48,000	48,000	
BID ITEM = 240	CLIENT# = 240		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, MMA, GREEN		Unit =	SF	Takeoff Quan:	7,778.000		Engr Quan:	7,778.000	
240.01	PAVEMENT MARKING, MMA, GREEN		Quan: 7,778.00 SF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
4STRI	Striping sub	1.00	7,778.00 SF	13.000				101,114	101,114	
BID ITEM = 241	CLIENT# = 241		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, MMA, RED		Unit =	SF	Takeoff Quan:	41,983.000		Engr Quan:	41,983.000	
241.01	PAVEMENT MARKING, MMA, RED		Quan: 41,983.00 SF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
4STRI	Striping sub	1.00	41,983.00 SF	10.500				440,822	440,822	
BID ITEM = 242	CLIENT# = 242		Land Item	SCHEDULE: 1	100					
Description =	PAVEMENT MARKING, MMA, BLACK		Unit =	SF	Takeoff Quan:	1,809.000		Engr Quan:	1,809.000	
242.01	PAVEMENT MARKING, MMA, BLACK		Quan: 1,809.00 SF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG				
4STRI	Striping sub	1.00	1,809.00 SF	15.000				27,135	27,135	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 243	CLIENT# = 243	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY PAVEMENT MARKING, PAINT, 4 IN	Unit =	LF	Takeoff Quan:	104,000.000	Engr Quan:	104,000.000			
243.01	TEMPORARY PAVEMENT MARKING, PAINT, 4 I	Quan:	104,000.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4STRI	Striping sub	1.00	104,000.00 LF	1.000				104,000		104,000
BID ITEM = 244	CLIENT# = 244	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY PAVEMENT MARKING, PAINT, LEGEN	Unit =	EA	Takeoff Quan:	50.000	Engr Quan:	50.000			
244.01	TEMPORARY PAVEMENT MARKING, PAINT, LE	Quan:	50.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4STRI	Striping sub	1.00	50.00 EA	65.000				3,250		3,250
BID ITEM = 245	CLIENT# = 245	Land Item	SCHEDULE: 1	100						
Description =	SIGN, PROJECT IDENTIFICATION, OWNER FURN	Unit =	EA	Takeoff Quan:	4.000	Engr Quan:	4.000			
245.01	SIGN, PROJECT IDENTIFICATION, OWNER FUR	Quan:	4.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>EAS</u>	Earthwork 4 Man Crew	2.00	CH	Prod:	2.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	2.00 HR	51.051				102		102
8EX100	100 Excavator	1.00	2.00 HR	52.300				105		105
FOCI	Civil Forman	1.00	2.00 MH	77.060	201					201
LAG	General Laborer	2.00	4.00 MH	52.910	279					279
OPE	Operator - Excavator	1.00	2.00 MH	74.560	195					195
\$881.92	2.0000 MH/EA		8.00 MH	[141.59]	675			207		882
=====>	Item Totals: 245 - SIGN, PROJECT IDENTIFICATION, OWNER FURN									
\$881.92	2.0000 MH/EA		8.00 MH	[141.59]	675			207		882
220.480	4 EA				168.81			51.67		220.48
BID ITEM = 246	CLIENT# = 246	Land Item	SCHEDULE: 1	100						
Description =	LUMINAIRE, LED, COLLECTOR ARTERIAL	Unit =	EA	Takeoff Quan:	65.000	Engr Quan:	65.000			
246.01	LUMINAIRE, LED, COLLECTOR ARTERIAL	Quan:	65.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	65.00 EA	810.000				52,650		52,650
BID ITEM = 247	CLIENT# = 247	Land Item	SCHEDULE: 1	100						
Description =	LUMINAIRE, LED, PRINCIPAL ARTERIAL	Unit =	EA	Takeoff Quan:	31.000	Engr Quan:	31.000			
247.01	LUMINAIRE, LED, PRINCIPAL ARTERIAL	Quan:	31.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	31.00 EA	1,120.000				34,720		34,720
BID ITEM = 248	CLIENT# = 248	Land Item	SCHEDULE: 1	100						
Description =	LUMINAIRE, LED, PEDESTRIAN SCALE	Unit =	EA	Takeoff Quan:	30.000	Engr Quan:	30.000			

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 248	CLIENT# = 248	Land Item	SCHEDULE: 1	100						
Description =	LUMINAIRE, LED, PEDESTRIAN SCALE	Unit =	EA	Takeoff	Quan:		30.000	Engr Quan:		30.000
248.01	LUMINAIRE, LED, PEDESTRIAN SCALE	Quan:	30.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	30.00 EA	3,650.000				109,500		109,500
BID ITEM = 249	CLIENT# = 249	Land Item	SCHEDULE: 1	100						
Description =	INSTALL GROUND ROD	Unit =	EA	Takeoff	Quan:		5.000	Engr Quan:		5.000
249.01	INSTALL GROUND ROD	Quan:	5.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	5.00 EA	340.000				1,700		1,700
BID ITEM = 250	CLIENT# = 250	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY STREET LIGHTING	Unit =	FA	Takeoff	Quan:		39,000.000	Engr Quan:		39,000.000
250.01	TEMPORARY STREET LIGHTING	Quan:	39,000.00 FA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
9FORCE	FORCE ACCOUNT	1.00	39,000.00 FA	0.890			34,710			34,710
=====	Item Totals: 250 - TEMPORARY STREET LIGHTING									
\$34,710.00				[]			34,710			34,710
0.890	39000 FA						0.89			0.89
BID ITEM = 251	CLIENT# = 251	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY STREET LIGHTING PLAN SUBMITTAL	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
251.01	TEMPORARY STREET LIGHTING PLAN SUBMIT	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	2,500.000				2,500		2,500
BID ITEM = 252	CLIENT# = 252	Land Item	SCHEDULE: 1	100						
Description =	RECONNECT EXISTING STREET LIGHTING SYSTE	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
252.01	RECONNECT EXISTING STREET LIGHTING SYS	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	30,300.000				30,300		30,300
BID ITEM = 253	CLIENT# = 253	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 1)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
253.01	WIRING, STREET LIGHTING, (SCHEMATIC 1)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	1,800.000				1,800		1,800

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 254	CLIENT# = 254	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 2)	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
254.01	WIRING, STREET LIGHTING, (SCHEMATIC 2)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	2,700.000				2,700		2,700
BID ITEM = 255	CLIENT# = 255	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 3)	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
255.01	WIRING, STREET LIGHTING, (SCHEMATIC 3)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	7,900.000				7,900		7,900
BID ITEM = 256	CLIENT# = 256	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 4)	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
256.01	WIRING, STREET LIGHTING, (SCHEMATIC 4)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	5,200.000				5,200		5,200
BID ITEM = 257	CLIENT# = 257	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 5)	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
257.01	WIRING, STREET LIGHTING, (SCHEMATIC 5)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,900.000				1,900		1,900
BID ITEM = 258	CLIENT# = 258	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 6)	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
258.01	WIRING, STREET LIGHTING, (SCHEMATIC 6)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	8,800.000				8,800		8,800
BID ITEM = 259	CLIENT# = 259	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 7)	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
259.01	WIRING, STREET LIGHTING, (SCHEMATIC 7)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	3,200.000				3,200		3,200
BID ITEM = 260	CLIENT# = 260	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 8)	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 260	CLIENT# = 260	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 8)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
260.01	WIRING, STREET LIGHTING, (SCHEMATIC 8)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	10,000.000				10,000	10,000	
BID ITEM = 261	CLIENT# = 261	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 9)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
261.01	WIRING, STREET LIGHTING, (SCHEMATIC 9)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	41,400.000				41,400	41,400	
BID ITEM = 262	CLIENT# = 262	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 10)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
262.01	WIRING, STREET LIGHTING, (SCHEMATIC 10)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	25,200.000				25,200	25,200	
BID ITEM = 263	CLIENT# = 263	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 11)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
263.01	WIRING, STREET LIGHTING, (SCHEMATIC 11)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	6,300.000				6,300	6,300	
BID ITEM = 264	CLIENT# = 264	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 12)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
264.01	WIRING, STREET LIGHTING, (SCHEMATIC 12)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	3,200.000				3,200	3,200	
BID ITEM = 265	CLIENT# = 265	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 13)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
265.01	WIRING, STREET LIGHTING, (SCHEMATIC 13)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	12,400.000				12,400	12,400	
BID ITEM = 266	CLIENT# = 266	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 14)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 266	CLIENT# = 266	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 14)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
266.01	WIRING, STREET LIGHTING, (SCHEMATIC 14)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	10,900.000				10,900	10,900	
BID ITEM = 267	CLIENT# = 267	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 15)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
267.01	WIRING, STREET LIGHTING, (SCHEMATIC 15)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	11,100.000				11,100	11,100	
BID ITEM = 268	CLIENT# = 268	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 16)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
268.01	WIRING, STREET LIGHTING, (SCHEMATIC 16)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	10,500.000				10,500	10,500	
BID ITEM = 269	CLIENT# = 269	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 17)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
269.01	WIRING, STREET LIGHTING, (SCHEMATIC 17)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	9,400.000				9,400	9,400	
BID ITEM = 270	CLIENT# = 270	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 18)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
270.01	WIRING, STREET LIGHTING, (SCHEMATIC 18)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	3,100.000				3,100	3,100	
BID ITEM = 271	CLIENT# = 271	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 19)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
271.01	WIRING, STREET LIGHTING, (SCHEMATIC 19)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	10,200.000				10,200	10,200	
BID ITEM = 272	CLIENT# = 272	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 20)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 272	CLIENT# = 272	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 20)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
272.01	WIRING, STREET LIGHTING, (SCHEMATIC 20)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	3,200.000				3,200		3,200
BID ITEM = 273	CLIENT# = 273	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 21)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
273.01	WIRING, STREET LIGHTING, (SCHEMATIC 21)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	5,500.000				5,500		5,500
BID ITEM = 274	CLIENT# = 274	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 22)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
274.01	WIRING, STREET LIGHTING, (SCHEMATIC 22)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	7,000.000				7,000		7,000
BID ITEM = 275	CLIENT# = 275	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 23)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
275.01	WIRING, STREET LIGHTING, (SCHEMATIC 23)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	500.000				500		500
BID ITEM = 276	CLIENT# = 276	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 24)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
276.01	WIRING, STREET LIGHTING, (SCHEMATIC 24)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	7,000.000				7,000		7,000
BID ITEM = 277	CLIENT# = 277	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 25)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
277.01	WIRING, STREET LIGHTING, (SCHEMATIC 25)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	8,600.000				8,600		8,600
BID ITEM = 278	CLIENT# = 278	Land Item	SCHEDULE: 1	100						
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 26)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 278	CLIENT# = 278		Land Item	SCHEDULE: 1	100					
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 26)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
278.01	WIRING, STREET LIGHTING, (SCHEMATIC 26)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	8,700.000				8,700		8,700
BID ITEM = 279	CLIENT# = 279		Land Item	SCHEDULE: 1	100					
Description =	WIRING, STREET LIGHTING, (SCHEMATIC 27)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
279.01	WIRING, STREET LIGHTING, (SCHEMATIC 27)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	1,200.000				1,200		1,200
BID ITEM = 280	CLIENT# = 280		Land Item	SCHEDULE: 1	100					
Description =	INSTALL OWNER FURN. TRAF. SIG. CNTRL. CA		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
280.01	INSTALL OWNER FURN. TRAF. SIG. CNTRL. CA	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	1,700.000				1,700		1,700
BID ITEM = 281	CLIENT# = 281		Land Item	SCHEDULE: 1	100					
Description =	INSTALL OWNER FURN. TRAF. SIG. CNTRL. CA		Unit =	EA	Takeoff Quan:		33.000	Engr Quan:		33.000
281.01	INSTALL OWNER FURN. TRAF. SIG. CNTRL. CA	Quan:	33.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	33.00 EA	2,570.000				84,810		84,810
BID ITEM = 282	CLIENT# = 282		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, VEHICLE, 3 SECTION 1-WAY		Unit =	EA	Takeoff Quan:		216.000	Engr Quan:		216.000
282.01	SIGNAL HEAD, VEHICLE, 3 SECTION 1-WAY	Quan:	216.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	216.00 EA	1,280.000				276,480		276,480
BID ITEM = 283	CLIENT# = 283		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, VEHICLE, 3 SECTION 1-WAY, O		Unit =	EA	Takeoff Quan:		6.000	Engr Quan:		6.000
283.01	SIGNAL HEAD, VEHICLE, 3 SECTION 1-WAY, O	Quan:	6.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	6.00 EA	2,150.000				12,900		12,900
BID ITEM = 284	CLIENT# = 284		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, BICYCLE, 3-SECTION 8"		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 284	CLIENT# = 284		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, BICYCLE, 3-SECTION 8"		Unit =	EA	Takeoff	Quan:	2.000	Engr Quan:		2.000
284.01	SIGNAL HEAD, BICYCLE, 3-SECTION 8"	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	2.00 EA	1,450.000				2,900		2,900
BID ITEM = 285	CLIENT# = 285		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, BICYCLE, 3-SECTION 4"		Unit =	EA	Takeoff	Quan:	2.000	Engr Quan:		2.000
285.01	SIGNAL HEAD, BICYCLE, 3-SECTION 4"	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	2.00 EA	1,450.000				2,900		2,900
BID ITEM = 286	CLIENT# = 286		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, VEHICLE, 3-SECTION 8"		Unit =	EA	Takeoff	Quan:	9.000	Engr Quan:		9.000
186.01	SIGNAL HEAD, VEHICLE, 3-SECTION 8"	Quan:	9.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	9.00 EA	1,240.000				11,160		11,160
BID ITEM = 287	CLIENT# = 287		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, TRANSIT, 3-SECTION 8"		Unit =	EA	Takeoff	Quan:	11.000	Engr Quan:		11.000
287.01	SIGNAL HEAD, TRANSIT, 3-SECTION 8"	Quan:	11.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	11.00 EA	1,530.000				16,830		16,830
BID ITEM = 288	CLIENT# = 288		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, VEHICLE, 4 SECTION 1-WAY		Unit =	EA	Takeoff	Quan:	10.000	Engr Quan:		10.000
288.01	SIGNAL HEAD, VEHICLE, 4 SECTION 1-WAY	Quan:	10.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	10.00 EA	1,600.000				16,000		16,000
BID ITEM = 289	CLIENT# = 289		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, VEHICLE, 4 SECTION 1-WAY, B		Unit =	EA	Takeoff	Quan:	5.000	Engr Quan:		5.000
289.01	SIGNAL HEAD, VEHICLE, 4 SECTION 1-WAY, B	Quan:	5.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	5.00 EA	1,600.000				8,000		8,000
BID ITEM = 290	CLIENT# = 290		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL HEAD, PEDESTRIAN COUNTDOWN, LED		Unit =	EA	Takeoff	Quan:	191.000	Engr Quan:		191.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 290	CLIENT# = 290	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL HEAD, PEDESTRIAN COUNTDOWN, LED	Unit =	EA	Takeoff	Quan:		191.000	Engr Quan:		191.000
290.01	SIGNAL HEAD, PEDESTRIAN COUNTDOWN, LE	Quan:	191.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	191.00 EA	790.000				150,890		150,890
BID ITEM = 291	CLIENT# = 291	Land Item	SCHEDULE: 1	100						
Description =	BICYCLE PUSHBUTTON ASSEMBLY	Unit =	EA	Takeoff	Quan:		3.000	Engr Quan:		3.000
291.01	BICYCLE PUSHBUTTON ASSEMBLY	Quan:	3.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	3.00 EA	1,230.000				3,690		3,690
BID ITEM = 292	CLIENT# = 292	Land Item	SCHEDULE: 1	100						
Description =	APS PEDESTRIAN PUSHBUTTON ASSEMBLY	Unit =	EA	Takeoff	Quan:		242.000	Engr Quan:		242.000
292.01	APS PEDESTRIAN PUSHBUTTON ASSEMBLY	Quan:	242.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	242.00 EA	1,390.000				336,380		336,380
BID ITEM = 293	CLIENT# = 293	Land Item	SCHEDULE: 1	100						
Description =	BOOM TRUCK AND OPERATOR FOR INSPECTOR	Unit =	HR	Takeoff	Quan:		20.000	Engr Quan:		20.000
293.01	BOOM TRUCK AND OPERATOR FOR INSPECTO	Quan:	20.00 HR	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	20.00 HR	160.000				3,200		3,200
BID ITEM = 294	CLIENT# = 294	Land Item	SCHEDULE: 1	100						
Description =	DETECTOR LOOP, 6 FT DIA.	Unit =	EA	Takeoff	Quan:		184.000	Engr Quan:		184.000
294.01	DETECTOR LOOP, 6 FT DIA.	Quan:	184.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	184.00 EA	1,630.000				299,920		299,920
BID ITEM = 295	CLIENT# = 295	Land Item	SCHEDULE: 1	100						
Description =	DETECTOR LOOP, PREFORMED, 6 FT DIA	Unit =	EA	Takeoff	Quan:		135.000	Engr Quan:		135.000
295.01	DETECTOR LOOP, PREFORMED, 6 FT DIA	Quan:	135.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	135.00 EA	1,300.000				175,500		175,500
BID ITEM = 296	CLIENT# = 296	Land Item	SCHEDULE: 1	100						
Description =	DETECTOR LOOP, PARALLELOGRAM	Unit =	EA	Takeoff	Quan:		8.000	Engr Quan:		8.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 296	CLIENT# = 296		Land Item	SCHEDULE: 1	100					
Description =	DETECTOR LOOP, PARALLELOGRAM		Unit =	EA	Takeoff Quan:		8.000	Engr Quan:		8.000
296.01	DETECTOR LOOP, PARALLELOGRAM	Quan:	8.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	8.00 EA	3,000.000				24,000		24,000
BID ITEM = 297	CLIENT# = 297		Land Item	SCHEDULE: 1	100					
Description =	DETECTOR LOOP, PREFORMED, PARALLELOGRAM		Unit =	EA	Takeoff Quan:		8.000	Engr Quan:		8.000
297.01	DETECTOR LOOP, PREFORMED, PARALLELOG	Quan:	8.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	8.00 EA	1,300.000				10,400		10,400
BID ITEM = 298	CLIENT# = 298		Land Item	SCHEDULE: 1	100					
Description =	AERIAL INNERDUCT		Unit =	LF	Takeoff Quan:		545.000	Engr Quan:		545.000
298.01	AERIAL INNERDUCT	Quan:	545.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	545.00 EA	20.000				10,900		10,900
BID ITEM = 299	CLIENT# = 299		Land Item	SCHEDULE: 1	100					
Description =	INTERCONNECT CABLE, AERIAL		Unit =	LF	Takeoff Quan:		235.000	Engr Quan:		235.000
299.01	INTERCONNECT CABLE, AERIAL	Quan:	235.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	235.00 LF	80.000				18,800		18,800
BID ITEM = 300	CLIENT# = 300		Land Item	SCHEDULE: 1	100					
Description =	INTERCONNECT CABLE, UNDERGROUND		Unit =	LF	Takeoff Quan:		175.000	Engr Quan:		175.000
300.01	INTERCONNECT CABLE, UNDERGROUND	Quan:	175.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	175.00 LF	100.000				17,500		17,500
BID ITEM = 301	CLIENT# = 301		Land Item	SCHEDULE: 1	100					
Description =	TERMINAL CABINET		Unit =	EA	Takeoff Quan:		88.000	Engr Quan:		88.000
301.01	TERMINAL CABINET	Quan:	88.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	88.00 EA	1,060.000				93,280		93,280
BID ITEM = 302	CLIENT# = 302		Land Item	SCHEDULE: 1	100					
Description =	SPAN WIRE		Unit =	LF	Takeoff Quan:		525.000	Engr Quan:		525.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 302		CLIENT# = 302	Land Item	SCHEDULE: 1	100					
Description = SPAN WIRE			Unit = LF	Takeoff	Quan:	525.000		Engr Quan:		525.000
302.01	SPAN WIRE		Quan:	525.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	525.00 LF	20.000				10,500		10,500
BID ITEM = 303		CLIENT# = 303	Land Item	SCHEDULE: 1	100					
Description = RELOCATE PEDESTRIAN SIGNAL HEAD			Unit = EA	Takeoff	Quan:	1.000		Engr Quan:		1.000
303.01	RELOCATE PEDESTRIAN SIGNAL HEAD		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 EA	400.000				400		400
BID ITEM = 304		CLIENT# = 304	Land Item	SCHEDULE: 1	100					
Description = RELOCATE CCTV CAMERA			Unit = EA	Takeoff	Quan:	2.000		Engr Quan:		2.000
304.01	RELOCATE CCTV CAMERA		Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	2.00 EA	5,700.000				11,400		11,400
BID ITEM = 305		CLIENT# = 305	Land Item	SCHEDULE: 1	100					
Description = RELOCATE EMERGENCY VEHICLE DETECTOR			Unit = EA	Takeoff	Quan:	1.000		Engr Quan:		1.000
305.01	RELOCATE EMERGENCY VEHICLE DETECTOR		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 EA	600.000				600		600
BID ITEM = 306		CLIENT# = 306	Land Item	SCHEDULE: 1	100					
Description = EMERGENCY VEHICLE PREEMPTION DETECTOR, O			Unit = EA	Takeoff	Quan:	38.000		Engr Quan:		38.000
306.01	EMERGENCY VEHICLE PREEMPTION DETECT		Quan:	38.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	38.00 EA	1,650.000				62,700		62,700
BID ITEM = 307		CLIENT# = 307	Land Item	SCHEDULE: 1	100					
Description = VIDEO DETECTION CAMERA			Unit = EA	Takeoff	Quan:	4.000		Engr Quan:		4.000
307.01	VIDEO DETECTION CAMERA		Quan:	4.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	4.00 EA	11,400.000				45,600		45,600
BID ITEM = 308		CLIENT# = 308	Land Item	SCHEDULE: 1	100					
Description = CCTV CAMERA, PTZ			Unit = EA	Takeoff	Quan:	10.000		Engr Quan:		10.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 308	CLIENT# = 308		Land Item	SCHEDULE: 1	100					
Description =	CCTV CAMERA, PTZ		Unit =	EA	Takeoff Quan:		10.000	Engr Quan:		10.000
308.01	CCTV CAMERA, PTZ		Quan:	10.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	10.00 EA	13,870.000				138,700		138,700
BID ITEM = 309	CLIENT# = 309		Land Item	SCHEDULE: 1	100					
Description =	WIRELESS SENSOR		Unit =	EA	Takeoff Quan:		174.000	Engr Quan:		174.000
309.01	WIRELESS SENSOR		Quan:	174.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	174.00 EA	1,470.000				255,780		255,780
BID ITEM = 310	CLIENT# = 310		Land Item	SCHEDULE: 1	100					
Description =	WIRELESS SENSOR ACCESS POINT		Unit =	EA	Takeoff Quan:		38.000	Engr Quan:		38.000
310.01	WIRELESS SENSOR ACCESS POINT		Quan:	38.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	38.00 EA	6,310.000				239,780		239,780
BID ITEM = 311	CLIENT# = 311		Land Item	SCHEDULE: 1	100					
Description =	WIRELESS SENSOR REPEATER		Unit =	EA	Takeoff Quan:		25.000	Engr Quan:		25.000
311.01	WIRELESS SENSOR REPEATER		Quan:	25.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	25.00 EA	4,420.000				110,500		110,500
BID ITEM = 312	CLIENT# = 312		Land Item	SCHEDULE: 1	100					
Description =	SERVICE CABINET		Unit =	EA	Takeoff Quan:		25.000	Engr Quan:		25.000
312.01	SERVICE CABINET		Quan:	25.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	25.00 EA	4,040.000				101,000		101,000
BID ITEM = 313	CLIENT# = 313		Land Item	SCHEDULE: 1	100					
Description =	SERVICE CABINET WITH STEP-DOWN TRANSFORM		Unit =	EA	Takeoff Quan:		5.000	Engr Quan:		5.000
313.01	SERVICE CABINET WITH STEP-DOWN TRANSF		Quan:	5.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	5.00 EA	10,700.000				53,500		53,500
BID ITEM = 314	CLIENT# = 314		Land Item	SCHEDULE: 1	100					
Description =	SERVICE WIRING (MADISON-MINOR)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 314	CLIENT# = 314	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-MINOR)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
314.01	SERVICE WIRING (MADISON-MINOR)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	5,700.000				5,700		5,700
BID ITEM = 315	CLIENT# = 315	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-BOYLSTON)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
315.01	SERVICE WIRING (MADISON-BOYLSTON)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	3,000.000				3,000		3,000
BID ITEM = 316	CLIENT# = 316	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-BROADWAY)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
316.01	SERVICE WIRING (MADISON-BROADWAY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,500.000				1,500		1,500
BID ITEM = 317	CLIENT# = 317	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-11TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
317.01	SERVICE WIRING (MADISON-11TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,100.000				1,100		1,100
BID ITEM = 318	CLIENT# = 318	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-12TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
318.01	SERVICE WIRING (MADISON-12TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	4,400.000				4,400		4,400
BID ITEM = 319	CLIENT# = 319	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-13TH MIDBLOCK)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
319.01	SERVICE WIRING (MADISON-13TH MIDBLOCK)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	2,100.000				2,100		2,100
BID ITEM = 320	CLIENT# = 320	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-14TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 320	CLIENT# = 320	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-14TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
320.01	SERVICE WIRING (MADISON-14TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,000.000				1,000		1,000
BID ITEM = 321	CLIENT# = 321	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-15TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
321.01	SERVICE WIRING (MADISON-15TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,300.000				1,300		1,300
BID ITEM = 322	CLIENT# = 322	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-16TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
322.01	SERVICE WIRING (MADISON-16TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,800.000				1,800		1,800
BID ITEM = 323	CLIENT# = 323	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-17TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
323.01	SERVICE WIRING (MADISON-17TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,600.000				1,600		1,600
BID ITEM = 324	CLIENT# = 324	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-18TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
324.01	SERVICE WIRING (MADISON-18TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,100.000				1,100		1,100
BID ITEM = 325	CLIENT# = 325	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-19TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
325.01	SERVICE WIRING (MADISON-19TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,500.000				1,500		1,500
BID ITEM = 326	CLIENT# = 326	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-20TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 326	CLIENT# = 326		Land Item	SCHEDULE: 1	100					
Description =	SERVICE WIRING (MADISON-20TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
326.01	SERVICE WIRING (MADISON-20TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS		1,300.000			1,300		1,300
BID ITEM = 327	CLIENT# = 327		Land Item	SCHEDULE: 1	100					
Description =	SERVICE WIRING (MADISON-E DENNY WAY)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
327.01	SERVICE WIRING (MADISON-E DENNY WAY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS		1,500.000			1,500		1,500
BID ITEM = 328	CLIENT# = 328		Land Item	SCHEDULE: 1	100					
Description =	SERVICE WIRING (MADISON-JOHN)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
328.01	SERVICE WIRING (MADISON-JOHN)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS		1,000.000			1,000		1,000
BID ITEM = 329	CLIENT# = 329		Land Item	SCHEDULE: 1	100					
Description =	SERVICE WIRING (MADISON-MLK WAY)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
329.01	SERVICE WIRING (MADISON-MLK WAY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS		1,500.000			1,500		1,500
BID ITEM = 330	CLIENT# = 330		Land Item	SCHEDULE: 1	100					
Description =	SERVICE WIRING (MLK WAY-HARRISON)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
330.01	SERVICE WIRING (MLK WAY-HARRISON)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS		2,000.000			2,000		2,000
BID ITEM = 331	CLIENT# = 331		Land Item	SCHEDULE: 1	100					
Description =	SERVICE WIRING (UNION-19TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
331.01	SERVICE WIRING (UNION-19TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS		1,200.000			1,200		1,200
BID ITEM = 332	CLIENT# = 332		Land Item	SCHEDULE: 1	100					
Description =	SERVICE WIRING (MADISON-10TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 332	CLIENT# = 332	Land Item	SCHEDULE: 1	100						
Description =	SERVICE WIRING (MADISON-10TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
332.01	SERVICE WIRING (MADISON-10TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	4,300.000				4,300	4,300	
BID ITEM = 333	CLIENT# = 333	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (SPRING-1ST)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
333.01	SIGNAL WIRING (SPRING-1ST)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	8,400.000				8,400	8,400	
BID ITEM = 334	CLIENT# = 334	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (SPRING-2ND)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
334.01	SIGNAL WIRING (SPRING-2ND)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,500.000				1,500	1,500	
BID ITEM = 335	CLIENT# = 335	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (SPRING-3RD)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
335.01	SIGNAL WIRING (SPRING-3RD)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	14,600.000				14,600	14,600	
BID ITEM = 336	CLIENT# = 336	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (SPRING-4TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
336.01	SIGNAL WIRING (SPRING-4TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,700.000				1,700	1,700	
BID ITEM = 337	CLIENT# = 337	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (SPRING-5TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
337.01	SIGNAL WIRING (SPRING-5TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	300.000				300	300	
BID ITEM = 338	CLIENT# = 338	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (SPRING-6TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 338	CLIENT# = 338		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (SPRING-6TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
338.01	SIGNAL WIRING (SPRING-6TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS		1,600.000			1,600		1,600
BID ITEM = 339	CLIENT# = 339		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (SPRING-7TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
339.01	SIGNAL WIRING (SPRING-7TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS		7,300.000			7,300		7,300
BID ITEM = 340	CLIENT# = 340		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (SPRING-8TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
340.01	SIGNAL WIRING (SPRING-8TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS		10,000.000			10,000		10,000
BID ITEM = 341	CLIENT# = 341		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (SPRING-9TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
341.01	SIGNAL WIRING (SPRING-9TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS		11,800.000			11,800		11,800
BID ITEM = 342	CLIENT# = 342		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-1ST)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
342.01	SIGNAL WIRING (MADISON-1ST)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS		9,800.000			9,800		9,800
BID ITEM = 343	CLIENT# = 343		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-2ND)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
343.01	SIGNAL WIRING (MADISON-2ND)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS		400.000			400		400
BID ITEM = 344	CLIENT# = 344		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-3RD)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 344	CLIENT# = 344	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-3RD)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
344.01	SIGNAL WIRING (MADISON-3RD)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	13,100.000				13,100	13,100	
BID ITEM = 345	CLIENT# = 345	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-4TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
345.01	SIGNAL WIRING (MADISON-4TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	2,500.000				2,500	2,500	
BID ITEM = 346	CLIENT# = 346	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-6TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
346.01	SIGNAL WIRING (MADISON-6TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	6,400.000				6,400	6,400	
BID ITEM = 347	CLIENT# = 347	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-7TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
347.01	SIGNAL WIRING (MADISON-7TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	13,800.000				13,800	13,800	
BID ITEM = 348	CLIENT# = 348	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-8TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
348.01	SIGNAL WIRING (MADISON-8TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	13,200.000				13,200	13,200	
BID ITEM = 349	CLIENT# = 349	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-9TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	
349.01	SIGNAL WIRING (MADISON-9TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	18,600.000				18,600	18,600	
BID ITEM = 350	CLIENT# = 350	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-TERRY)	Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 350	CLIENT# = 350	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-TERRY)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
350.01	SIGNAL WIRING (MADISON-TERRY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	13,300.000				13,300		13,300
BID ITEM = 351	CLIENT# = 351	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-BOREN)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
351.01	SIGNAL WIRING (MADISON-BOREN)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	31,900.000				31,900		31,900
BID ITEM = 352	CLIENT# = 352	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-MINOR)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
352.01	SIGNAL WIRING (MADISON-MINOR)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	11,300.000				11,300		11,300
BID ITEM = 353	CLIENT# = 353	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-SUMMIT)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
253.01	SIGNAL WIRING (MADISON-SUMMIT)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	11,400.000				11,400		11,400
BID ITEM = 354	CLIENT# = 354	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-BOYLSTON)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
154.01	SIGNAL WIRING (MADISON-BOYLSTON)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	18,900.000				18,900		18,900
BID ITEM = 355	CLIENT# = 355	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-BROADWAY)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
355.01	SIGNAL WIRING (MADISON-BROADWAY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	24,200.000				24,200		24,200
BID ITEM = 356	CLIENT# = 356	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-11TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 356	CLIENT# = 356		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-11TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
356.01	SIGNAL WIRING (MADISON-11TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS	10,600.000				10,600		10,600
BID ITEM = 357	CLIENT# = 357		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-12TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
357.01	SIGNAL WIRING (MADISON-12TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS	23,800.000				23,800		23,800
BID ITEM = 358	CLIENT# = 358		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-13TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
358.01	SIGNAL WIRING (MADISON-13TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS	13,000.000				13,000		13,000
BID ITEM = 359	CLIENT# = 359		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-14TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
359.01	SIGNAL WIRING (MADISON-14TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS	22,100.000				22,100		22,100
BID ITEM = 360	CLIENT# = 360		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-15TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
360.01	SIGNAL WIRING (MADISON-15TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS	12,400.000				12,400		12,400
BID ITEM = 361	CLIENT# = 361		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-16TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
361.01	SIGNAL WIRING (MADISON-16TH)		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 LS	10,300.000				10,300		10,300
BID ITEM = 362	CLIENT# = 362		Land Item	SCHEDULE: 1	100					
Description =	SIGNAL WIRING (MADISON-17TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 362	CLIENT# = 362	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-17TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
362.01	SIGNAL WIRING (MADISON-17TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	14,100.000				14,100		14,100
BID ITEM = 363	CLIENT# = 363	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-18TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
363.01	SIGNAL WIRING (MADISON-18TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	7,600.000				7,600		7,600
BID ITEM = 364	CLIENT# = 364	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-19TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
364.01	SIGNAL WIRING (MADISON-19TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	13,700.000				13,700		13,700
BID ITEM = 365	CLIENT# = 365	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-20TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
365.01	SIGNAL WIRING (MADISON-20TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	18,400.000				18,400		18,400
BID ITEM = 366	CLIENT# = 366	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-E DENNY WAY)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
366.01	SIGNAL WIRING (MADISON-E DENNY WAY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	10,700.000				10,700		10,700
BID ITEM = 367	CLIENT# = 367	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-23RD)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
367.01	SIGNAL WIRING (MADISON-23RD)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	4,500.000				4,500		4,500
BID ITEM = 368	CLIENT# = 368	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-JOHN)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 368	CLIENT# = 368	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-JOHN)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
368.01	SIGNAL WIRING (MADISON-JOHN)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	11,900.000				11,900	11,900	
BID ITEM = 369	CLIENT# = 369	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-MLK WAY)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
369.01	SIGNAL WIRING (MADISON-MLK WAY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	18,400.000				18,400	18,400	
BID ITEM = 370	CLIENT# = 370	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MLK WAY-HARRISON)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
370.01	SIGNAL WIRING (MLK WAY-HARRISON)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	8,000.000				8,000	8,000	
BID ITEM = 371	CLIENT# = 371	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (UNION-19TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
371.01	SIGNAL WIRING (UNION-19TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	10,700.000				10,700	10,700	
BID ITEM = 372	CLIENT# = 372	Land Item	SCHEDULE: 1	100						
Description =	SIGNAL WIRING (MADISON-10TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
372.01	SIGNAL WIRING (MADISON-10TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	4,300.000				4,300	4,300	
BID ITEM = 373	CLIENT# = 373	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (SPRING-1ST)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
373.01	TEMPORARY SIGNAL (SPRING-1ST)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	8,200.000				8,200	8,200	
BID ITEM = 374	CLIENT# = 374	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (SPRING-3RD)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 374	CLIENT# = 374	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (SPRING-3RD)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
374.01	TEMPORARY SIGNAL (SPRING-3RD)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	10,900.000				10,900		10,900
BID ITEM = 375	CLIENT# = 375	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (SPRING-5TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
375.01	TEMPORARY SIGNAL (SPRING-5TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	8,200.000				8,200		8,200
BID ITEM = 376	CLIENT# = 376	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (SPRING-7TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
376.01	TEMPORARY SIGNAL (SPRING-7TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	18,000.000				18,000		18,000
BID ITEM = 377	CLIENT# = 377	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-1ST)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
377.01	TEMPORARY SIGNAL (MADISON-1ST)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	19,000.000				19,000		19,000
BID ITEM = 378	CLIENT# = 378	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-3RD)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
378.01	TEMPORARY SIGNAL (MADISON-3RD)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	11,500.000				11,500		11,500
BID ITEM = 379	CLIENT# = 379	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-6TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000
379.01	TEMPORARY SIGNAL (MADISON-6TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	14,100.000				14,100		14,100
BID ITEM = 380	CLIENT# = 380	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-7TH)	Unit =	LS	Takeoff	Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 380	CLIENT# = 380		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-7TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
380.01	TEMPORARY SIGNAL (MADISON-7TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	32,200.000				32,200		32,200
BID ITEM = 381	CLIENT# = 381		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-8TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
381.01	TEMPORARY SIGNAL (MADISON-8TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	31,500.000				31,500		31,500
BID ITEM = 382	CLIENT# = 382		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-9TH)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
382.01	TEMPORARY SIGNAL (MADISON-9TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	31,500.000				31,500		31,500
BID ITEM = 383	CLIENT# = 383		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-TERRY)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
383.01	TEMPORARY SIGNAL (MADISON-TERRY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	24,800.000				24,800		24,800
BID ITEM = 384	CLIENT# = 384		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-BOREN)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
384.01	TEMPORARY SIGNAL (MADISON-BOREN)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	36,300.000				36,300		36,300
BID ITEM = 385	CLIENT# = 385		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-MINOR)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
385.01	TEMPORARY SIGNAL (MADISON-MINOR)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	23,000.000				23,000		23,000
BID ITEM = 386	CLIENT# = 386		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-SUMMIT)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 386	CLIENT# = 386	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-SUMMIT)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
386.01	TEMPORARY SIGNAL (MADISON-SUMMIT)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	15,600.000				15,600	15,600	
BID ITEM = 387	CLIENT# = 387	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-BOYLSTON)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
387.01	TEMPORARY SIGNAL (MADISON-BOYLSTON)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	18,200.000				18,200	18,200	
BID ITEM = 388	CLIENT# = 388	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-BROADWAY)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
388.01	TEMPORARY SIGNAL (MADISON-BROADWAY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	50,500.000				50,500	50,500	
BID ITEM = 389	CLIENT# = 389	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-11TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
389.01	TEMPORARY SIGNAL (MADISON-11TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	40,600.000				40,600	40,600	
BID ITEM = 390	CLIENT# = 390	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-12TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
390.01	TEMPORARY SIGNAL (MADISON-12TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	56,600.000				56,600	56,600	
BID ITEM = 391	CLIENT# = 391	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-13TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
391.01	TEMPORARY SIGNAL (MADISON-13TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	50,200.000				50,200	50,200	
BID ITEM = 392	CLIENT# = 392	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-14TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 392	CLIENT# = 392	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-14TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
392.01	TEMPORARY SIGNAL (MADISON-14TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	86,900.000				86,900	86,900	
BID ITEM = 393	CLIENT# = 393	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-15TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
393.01	TEMPORARY SIGNAL (MADISON-15TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	18,200.000				18,200	18,200	
BID ITEM = 394	CLIENT# = 394	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-16TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
394.01	TEMPORARY SIGNAL (MADISON-16TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	15,600.000				15,600	15,600	
BID ITEM = 395	CLIENT# = 395	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-17TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
395.01	TEMPORARY SIGNAL (MADISON-17TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	15,600.000				15,600	15,600	
BID ITEM = 396	CLIENT# = 396	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-19TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
396.01	TEMPORARY SIGNAL (MADISON-19TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	15,600.000				15,600	15,600	
BID ITEM = 397	CLIENT# = 397	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-20TH)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
397.01	TEMPORARY SIGNAL (MADISON-20TH)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	24,100.000				24,100	24,100	
BID ITEM = 398	CLIENT# = 398	Land Item	SCHEDULE: 1	100						
Description =	TEMPORARY SIGNAL (MADISON-DENNY)	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 398	CLIENT# = 398		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-DENNY)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
398.01	TEMPORARY SIGNAL (MADISON-DENNY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	20,800.000				20,800		20,800
BID ITEM = 399	CLIENT# = 399		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-23RD)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
399.01	TEMPORARY SIGNAL (MADISON-23RD)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	15,600.000				15,600		15,600
BID ITEM = 400	CLIENT# = 400		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-JOHN)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
400.01	TEMPORARY SIGNAL (MADISON-JOHN)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	36,500.000				36,500		36,500
BID ITEM = 401	CLIENT# = 401		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY SIGNAL (MADISON-MLK WAY)		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
401.01	TEMPORARY SIGNAL (MADISON-MLK WAY)	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	36,500.000				36,500		36,500
BID ITEM = 402	CLIENT# = 402		Land Item	SCHEDULE: 1	100					
Description =	DETECTION INDICATOR, LED BICYCLE BLUE LI		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
402.01	DETECTION INDICATOR, LED BICYCLE BLUE L	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	2.00 EA	600.000				1,200		1,200
BID ITEM = 403	CLIENT# = 403		Land Item	SCHEDULE: 1	100					
Description =	POLE, STEEL STRAIN, TYPE T		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
403.01	POLE, STEEL STRAIN, TYPE T	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	11,200.000				11,200		11,200
BID ITEM = 404	CLIENT# = 404		Land Item	SCHEDULE: 1	100					
Description =	POLE, STEEL STRAIN, TYPE X		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 404	CLIENT# = 404		Land Item	SCHEDULE: 1	100					
Description =	POLE, STEEL STRAIN, TYPE X		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
404.01	POLE, STEEL STRAIN, TYPE X		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 EA	18,800.000				18,800		18,800
BID ITEM = 405	CLIENT# = 405		Land Item	SCHEDULE: 1	100					
Description =	POLE, STEEL STRAIN, TYPE Z		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
405.01	POLE, STEEL STRAIN, TYPE Z		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 EA	21,400.000				21,400		21,400
BID ITEM = 406	CLIENT# = 406		Land Item	SCHEDULE: 1	100					
Description =	POLE, STEEL MAST ARM		Unit =	EA	Takeoff Quan:		32.000	Engr Quan:		32.000
406.01	POLE, STEEL MAST ARM		Quan:	32.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	32.00 EA	13,930.000				445,760		445,760
BID ITEM = 407	CLIENT# = 407		Land Item	SCHEDULE: 1	100					
Description =	POLE, STEEL DOUBLE MAST ARM		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
407.01	POLE, STEEL DOUBLE MAST ARM		Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	2.00 EA	19,800.000				39,600		39,600
BID ITEM = 408	CLIENT# = 408		Land Item	SCHEDULE: 1	100					
Description =	POLE, PEDESTRIAN, ALUMINUM LIGHTING, 14		Unit =	EA	Takeoff Quan:		30.000	Engr Quan:		30.000
408.01	POLE, PEDESTRIAN, ALUMINUM LIGHTING, 14		Quan:	30.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	30.00 EA	2,770.000				83,100		83,100
BID ITEM = 409	CLIENT# = 409		Land Item	SCHEDULE: 1	100					
Description =	POLE, STEEL LIGHTING 25 to 35 FT		Unit =	EA	Takeoff Quan:		20.000	Engr Quan:		20.000
409.01	POLE, STEEL LIGHTING 25 to 35 FT		Quan:	20.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	20.00 EA	4,600.000				92,000		92,000
BID ITEM = 410	CLIENT# = 410		Land Item	SCHEDULE: 1	100					
Description =	PEDESTAL, ALUMINUM, 10 FT		Unit =	EA	Takeoff Quan:		32.000	Engr Quan:		32.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 410	CLIENT# = 410		Land Item	SCHEDULE: 1	100					
Description =	PEDESTAL, ALUMINUM, 10 FT		Unit =	EA	Takeoff Quan:		32.000	Engr Quan:		32.000
410.01	PEDESTAL, ALUMINUM, 10 FT		Quan:	32.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	32.00 EA	3,680.000				117,760		117,760
BID ITEM = 411	CLIENT# = 411		Land Item	SCHEDULE: 1	100					
Description =	PEDESTAL, ALUMINUM, 12 FT		Unit =	EA	Takeoff Quan:		20.000	Engr Quan:		20.000
411.01	PEDESTAL, ALUMINUM, 12 FT		Quan:	20.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	20.00 EA	4,660.000				93,200		93,200
BID ITEM = 412	CLIENT# = 412		Land Item	SCHEDULE: 1	100					
Description =	PEDESTAL, ALUMINUM, 14 FT		Unit =	EA	Takeoff Quan:		3.000	Engr Quan:		3.000
412.01	PEDESTAL, ALUMINUM, 14 FT		Quan:	3.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	3.00 EA	4,930.000				14,790		14,790
BID ITEM = 413	CLIENT# = 413		Land Item	SCHEDULE: 1	100					
Description =	MAST ARM, 30 FT AND LESS		Unit =	EA	Takeoff Quan:		43.000	Engr Quan:		43.000
413.01	MAST ARM, 30 FT AND LESS		Quan:	43.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	43.00 EA	9,030.000				388,290		388,290
BID ITEM = 414	CLIENT# = 414		Land Item	SCHEDULE: 1	100					
Description =	MAST ARM, 31 FT TO 40 FT		Unit =	EA	Takeoff Quan:		18.000	Engr Quan:		18.000
414.01	MAST ARM, 31 FT TO 40 FT		Quan:	18.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	18.00 EA	10,760.000				193,680		193,680
BID ITEM = 415	CLIENT# = 415		Land Item	SCHEDULE: 1	100					
Description =	MAST ARM, 41 FT TO 50 FT		Unit =	EA	Takeoff Quan:		6.000	Engr Quan:		6.000
415.01	MAST ARM, 41 FT TO 50 FT		Quan:	6.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	6.00 EA	14,930.000				89,580		89,580
BID ITEM = 416	CLIENT# = 416		Land Item	SCHEDULE: 1	100					
Description =	PEDESTRIAN PUSH-BUTTON POST		Unit =	EA	Takeoff Quan:		112.000	Engr Quan:		112.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 416	CLIENT# = 416		Land Item	SCHEDULE: 1	100					
Description =	PEDESTRIAN PUSH-BUTTON POST		Unit =	EA	Takeoff Quan:		112.000	Engr Quan:		112.000
416.01	PEDESTRIAN PUSH-BUTTON POST		Quan:	112.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	112.00 EA		1,100.000			123,200		123,200
BID ITEM = 417	CLIENT# = 417		Land Item	SCHEDULE: 1	100					
Description =	PEDESTRIAN PUSH-BUTTON, BRIDGE MOUNT		Unit =	EA	Takeoff Quan:		5.000	Engr Quan:		5.000
417.01	PEDESTRIAN PUSH-BUTTON, BRIDGE MOUNT		Quan:	5.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	5.00 EA		400.000			2,000		2,000
BID ITEM = 418	CLIENT# = 418		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, JOINT SIGNAL CONTROLLER/SERV		Unit =	EA	Takeoff Quan:		21.000	Engr Quan:		21.000
418.01	FOUNDATION, JOINT SIGNAL CONTROLLER/SE		Quan:	21.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	21.00 EA		6,380.000			133,980		133,980
BID ITEM = 419	CLIENT# = 419		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, TRAFFIC SIGNAL CONTROL. CAB.		Unit =	EA	Takeoff Quan:		11.000	Engr Quan:		11.000
419.01	FOUNDATION, TRAFFIC SIGNAL CONTROL. CA		Quan:	11.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	11.00 EA		4,110.000			45,210		45,210
BID ITEM = 420	CLIENT# = 420		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, SERVICE CABINET		Unit =	EA	Takeoff Quan:		4.000	Engr Quan:		4.000
420.01	FOUNDATION, SERVICE CABINET		Quan:	4.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	4.00 EA		4,100.000			16,400		16,400
BID ITEM = 421	CLIENT# = 421		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, SERVICE CABINET WITH STEP- D		Unit =	EA	Takeoff Quan:		5.000	Engr Quan:		5.000
421.01	FOUNDATION, SERVICE CABINET WITH STEP-		Quan:	5.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	5.00 EA		4,100.000			20,500		20,500
BID ITEM = 422	CLIENT# = 422		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, POLE TYPE T		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 422	CLIENT# = 422		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, POLE TYPE T		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
422.01	FOUNDATION, POLE TYPE T	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	4,800.000				4,800		4,800
BID ITEM = 423	CLIENT# = 423		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, POLE TYPE X		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
423.01	FOUNDATION, POLE TYPE X	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	4,800.000				4,800		4,800
BID ITEM = 424	CLIENT# = 424		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, POLE TYPE Z		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
424.01	FOUNDATION, POLE TYPE Z	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	7,500.000				7,500		7,500
BID ITEM = 425	CLIENT# = 425		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, POLE PEDESTRIAN LIGHTING		Unit =	EA	Takeoff Quan:		30.000	Engr Quan:		30.000
425.01	FOUNDATION, POLE PEDESTRIAN LIGHTING	Quan:	30.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	30.00 EA	2,370.000				71,100		71,100
BID ITEM = 426	CLIENT# = 426		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, STREET LIGHT POLE		Unit =	EA	Takeoff Quan:		20.000	Engr Quan:		20.000
426.01	FOUNDATION, STREET LIGHT POLE	Quan:	20.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	20.00 EA	4,820.000				96,400		96,400
BID ITEM = 427	CLIENT# = 427		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, PEDESTAL		Unit =	EA	Takeoff Quan:		55.000	Engr Quan:		55.000
427.01	FOUNDATION, PEDESTAL	Quan:	55.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	55.00 EA	2,400.000				132,000		132,000
BID ITEM = 428	CLIENT# = 428		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, PEDESTRIAN PUSH BUTTON POST		Unit =	EA	Takeoff Quan:		112.000	Engr Quan:		112.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 428	CLIENT# = 428	Land Item	SCHEDULE: 1	100						
Description =	FOUNDATION, PEDESTRIAN PUSH BUTTON POST	Unit =	EA	Takeoff	Quan:	112.000	Engr	Quan:	112.000	
428.01	FOUNDATION, PEDESTRIAN PUSH BUTTON POS	Quan:	112.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	112.00 EA	1,400.000				156,800	156,800	
BID ITEM = 429	CLIENT# = 429	Land Item	SCHEDULE: 1	100						
Description =	FOUNDATION, POLE, MAST ARM 30 FT & LESS	Unit =	EA	Takeoff	Quan:	21.000	Engr	Quan:	21.000	
429.01	FOUNDATION, POLE, MAST ARM 30 FT & LESS	Quan:	21.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	21.00 EA	2,910.000				61,110	61,110	
BID ITEM = 430	CLIENT# = 430	Land Item	SCHEDULE: 1	100						
Description =	FOUNDATION, POLE, MAST ARM 31 FT TO 40 F	Unit =	EA	Takeoff	Quan:	10.000	Engr	Quan:	10.000	
430.01	FOUNDATION, POLE, MAST ARM 31 FT TO 40 F	Quan:	10.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	10.00 EA	4,200.000				42,000	42,000	
BID ITEM = 431	CLIENT# = 431	Land Item	SCHEDULE: 1	100						
Description =	FOUNDATION, POLE, MAST ARM 41 FT TO 50 F	Unit =	EA	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
431.01	FOUNDATION, POLE, MAST ARM 41 FT TO 50 F	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 EA	4,200.000				4,200	4,200	
BID ITEM = 432	CLIENT# = 432	Land Item	SCHEDULE: 1	100						
Description =	FOUNDATION, POLE DOUBLE MAST ARM	Unit =	EA	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
432.01	FOUNDATION, POLE DOUBLE MAST ARM	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 EA	4,200.000				4,200	4,200	
BID ITEM = 433	CLIENT# = 433	Land Item	SCHEDULE: 1	100						
Description =	REMOVE FOUNDATION OBSTRUCTIONS	Unit =	FA	Takeoff	Quan:	92,000.000	Engr	Quan:	92,000.000	
433.01	REMOVE FOUNDATION OBSTRUCTIONS	Quan:	92,000.00 FA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
9FORCE	FORCE ACCOUNT	1.00	92,000.00 FA	0.890			81,880		81,880	
====>	Item Totals: 433 - REMOVE FOUNDATION OBSTRUCTIONS									
\$81,880.00				[]			81,880		81,880	
0.890		92000 FA					0.89		0.89	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM	=	434	CLIENT# = 434	Land Item	SCHEDULE:	1	100			
Description =		TEMPORARY POLE SUPPORT	Unit =	FA	Takeoff Quan:	18,000.000	Engr Quan:	18,000.000		
434.01	TEMPORARY POLE SUPPORT	Quan:	18,000.00 FA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
9FORCE	FORCE ACCOUNT	1.00	18,000.00 FA	0.890		16,020				16,020
====>	Item Totals:	434	- TEMPORARY POLE SUPPORT							
	\$16,020.00			[]		16,020				16,020
	0.890		18000 FA			0.89				0.89
BID ITEM	=	435	CLIENT# = 435	Land Item	SCHEDULE:	1	100			
Description =		GROUT EXISTING POLE	Unit =	FA	Takeoff Quan:	20,000.000	Engr Quan:	20,000.000		
435.01	GROUT EXISTING POLE	Quan:	20,000.00 FA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
9FORCE	FORCE ACCOUNT	1.00	20,000.00 FA	0.890		17,800				17,800
====>	Item Totals:	435	- GROUT EXISTING POLE							
	\$17,800.00			[]		17,800				17,800
	0.890		20000 FA			0.89				0.89
BID ITEM	=	436	CLIENT# = 436	Land Item	SCHEDULE:	1	100			
Description =		INSTALL POLE, KCM SA-201X/SA-201X(C), OW	Unit =	EA	Takeoff Quan:	2.000	Engr Quan:	2.000		
436.01	INSTALL POLE, KCM SA-201X/SA-201X(C), OW	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	2.00 EA	2,000.000				4,000		4,000
BID ITEM	=	437	CLIENT# = 437	Land Item	SCHEDULE:	1	100			
Description =		INSTALL POLE, KCM SA-201Z/SA-201Z(C), OW	Unit =	EA	Takeoff Quan:	8.000	Engr Quan:	8.000		
437.01	INSTALL POLE, KCM SA-201Z/SA-201Z(C), OW	Quan:	8.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	8.00 EA	1,980.000				15,840		15,840
BID ITEM	=	438	CLIENT# = 438	Land Item	SCHEDULE:	1	100			
Description =		INSTALL POLE, KCM SA-201ZZ, OWNER FURNIS	Unit =	EA	Takeoff Quan:	8.000	Engr Quan:	8.000		
438.02	INSTALL POLE, KCM SA-201ZZ, OWNER FURNIS	Quan:	8.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	8.00 EA	1,980.000				15,840		15,840
BID ITEM	=	439	CLIENT# = 439	Land Item	SCHEDULE:	1	100			
Description =		INSTALL POLE, KCM SA-201ZZZ, OWNER FURNI	Unit =	EA	Takeoff Quan:	3.000	Engr Quan:	3.000		
439.01	INSTALL POLE, KCM SA-201ZZZ, OWNER FURNI	Quan:	3.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 439	CLIENT# = 439	Land Item	SCHEDULE: 1	100						
Description =	INSTALL POLE, KCM SA-201ZZZ, OWNER FURNI	Unit =	EA	Takeoff	Quan:		3.000	Engr	Quan:	3.000
4ELEC	Electrical sub	1.00	3.00 EA	1,970.000					5,910	5,910
BID ITEM = 440	CLIENT# = 440	Land Item	SCHEDULE: 1	100						
Description =	CHIEF SEATTLE BASE AND COLLAR, CAST ALUM	Unit =	EA	Takeoff	Quan:		2.000	Engr	Quan:	2.000
440.01	CHIEF SEATTLE BASE AND COLLAR, CAST ALU	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	2.00 EA	22,050.000					44,100	44,100
BID ITEM = 441	CLIENT# = 441	Land Item	SCHEDULE: 1	100						
Description =	CHIEF SEATTLE BASE AND COLLAR, CAST ALUM	Unit =	EA	Takeoff	Quan:		4.000	Engr	Quan:	4.000
441.01	CHIEF SEATTLE BASE AND COLLAR, CAST ALU	Quan:	4.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	4.00 EA	22,050.000					88,200	88,200
BID ITEM = 442	CLIENT# = 442	Land Item	SCHEDULE: 1	100						
Description =	BRACKET ARM, 15 FT	Unit =	EA	Takeoff	Quan:		1.000	Engr	Quan:	1.000
442.01	BRACKET ARM, 15 FT	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	1,500.000					1,500	1,500
BID ITEM = 443	CLIENT# = 443	Land Item	SCHEDULE: 1	100						
Description =	ALADDIN BRACKET ARM ASSEMBLY, 8 FT	Unit =	EA	Takeoff	Quan:		4.000	Engr	Quan:	4.000
443.01	ALADDIN BRACKET ARM ASSEMBLY, 8 FT	Quan:	4.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	4.00 EA	2,550.000					10,200	10,200
BID ITEM = 444	CLIENT# = 444	Land Item	SCHEDULE: 1	100						
Description =	BRACKET ARM, 6 FT, STEEL	Unit =	EA	Takeoff	Quan:		14.000	Engr	Quan:	14.000
444.01	BRACKET ARM, 6 FT, STEEL	Quan:	14.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	14.00 EA	690.000					9,660	9,660
BID ITEM = 445	CLIENT# = 445	Land Item	SCHEDULE: 1	100						
Description =	BRACKET ARM, 8 FT, STEEL	Unit =	EA	Takeoff	Quan:		69.000	Engr	Quan:	69.000
445.01	BRACKET ARM, 8 FT, STEEL	Quan:	69.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	69.00 EA	780.000					53,820	53,820

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 446	CLIENT# = 446		Land Item	SCHEDULE: 1	100					
Description =	BRACKET ARM, 10 FT, STEEL		Unit =	EA	Takeoff Quan:		4.000	Engr Quan:		4.000
446.01	BRACKET ARM, 10 FT, STEEL		Quan:	4.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	4.00 EA	900.000				3,600		3,600
BID ITEM = 447	CLIENT# = 447		Land Item	SCHEDULE: 1	100					
Description =	BRACKET ARM, 12 FT, STEEL		Unit =	EA	Takeoff Quan:		4.000	Engr Quan:		4.000
447.01	BRACKET ARM, 12 FT, STEEL		Quan:	4.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	4.00 EA	1,280.000				5,120		5,120
BID ITEM = 448	CLIENT# = 448		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, BICYCLE PUSHBUTTON POST		Unit =	EA	Takeoff Quan:		3.000	Engr Quan:		3.000
448.01	FOUNDATION, BICYCLE PUSHBUTTON POST		Quan:	3.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	3.00 EA	1,400.000				4,200		4,200
BID ITEM = 449	CLIENT# = 449		Land Item	SCHEDULE: 1	100					
Description =	BICYCLE PUSHBUTTON POST		Unit =	EA	Takeoff Quan:		3.000	Engr Quan:		3.000
449.01	BICYCLE PUSHBUTTON POST		Quan:	3.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	3.00 EA	1,170.000				3,510		3,510
BID ITEM = 450	CLIENT# = 450		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, POLE, JU/STEEL MAST ARM		Unit =	EA	Takeoff Quan:		30.000	Engr Quan:		30.000
450.01	FOUNDATION, POLE, JU/STEEL MAST ARM		Quan:	30.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	30.00 EA	8,370.000				251,100		251,100
BID ITEM = 451	CLIENT# = 451		Land Item	SCHEDULE: 1	100					
Description =	POLE, KCM SA-201X/SA-201X(C)		Unit =	EA	Takeoff Quan:		26.000	Engr Quan:		26.000
451.01	POLE, KCM SA-201X/SA-201X(C)		Quan:	26.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	26.00 EA	17,170.000				446,420		446,420
BID ITEM = 452	CLIENT# = 452		Land Item	SCHEDULE: 1	100					
Description =	POLE, KCM SA-201Z/SA-201Z(C)		Unit =	EA	Takeoff Quan:		22.000	Engr Quan:		22.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 452	CLIENT# = 452		Land Item	SCHEDULE: 1	100					
Description = POLE, KCM SA-201Z/SA-201Z(C)			Unit = EA	Takeoff	Quan:		22.000	Engr Quan:		22.000
451.01	POLE, KCM SA-201Z/SA-201Z(C)		Quan:	22.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	22.00 EA	23,380.000				514,360		514,360
BID ITEM = 453	CLIENT# = 453		Land Item	SCHEDULE: 1	100					
Description = POLE, KCM SA-201ZZ			Unit = EA	Takeoff	Quan:		32.000	Engr Quan:		32.000
453.01	POLE, KCM SA-201ZZ		Quan:	32.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	32.00 EA	26,910.000				861,120		861,120
BID ITEM = 454	CLIENT# = 454		Land Item	SCHEDULE: 1	100					
Description = POLE, KCM SA-201ZZZ			Unit = EA	Takeoff	Quan:		10.000	Engr Quan:		10.000
454.01	POLE, KCM SA-201ZZZ		Quan:	10.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	10.00 EA	34,630.000				346,300		346,300
BID ITEM = 455	CLIENT# = 455		Land Item	SCHEDULE: 1	100					
Description = FOUNDATION, KCM SA-213D			Unit = EA	Takeoff	Quan:		26.000	Engr Quan:		26.000
455.01	FOUNDATION, KCM SA-213D		Quan:	26.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	26.00 EA	4,670.000				121,420		121,420
BID ITEM = 456	CLIENT# = 456		Land Item	SCHEDULE: 1	100					
Description = FOUNDATION, KCM SA-213F			Unit = EA	Takeoff	Quan:		41.000	Engr Quan:		41.000
456.01	FOUNDATION, KCM SA-213F		Quan:	41.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	41.00 EA	7,360.000				301,760		301,760
BID ITEM = 457	CLIENT# = 457		Land Item	SCHEDULE: 1	100					
Description = FOUNDATION, KCM SA-213H			Unit = EA	Takeoff	Quan:		8.000	Engr Quan:		8.000
457.01	FOUNDATION, KCM SA-213H		Quan:	8.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	8.00 EA	12,510.000				100,080		100,080
BID ITEM = 458	CLIENT# = 458		Land Item	SCHEDULE: 1	100					
Description = OFFSET FOUNDATION, KCM SA-211			Unit = EA	Takeoff	Quan:		4.000	Engr Quan:		4.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 458	CLIENT# = 458		Land Item	SCHEDULE: 1	100					
Description =	OFFSET FOUNDATION, KCM SA-211		Unit =	EA	Takeoff Quan:		4.000	Engr Quan:		4.000
458.01	OFFSET FOUNDATION, KCM SA-211	Quan:	4.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	4.00 EA	6,200.000				24,800		24,800
BID ITEM = 459	CLIENT# = 459		Land Item	SCHEDULE: 1	100					
Description =	PEDESTAL, ALUMINUM, 20 FT		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
459.01	PEDESTAL, ALUMINUM, 20 FT	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	6,500.000				6,500		6,500
BID ITEM = 460	CLIENT# = 460		Land Item	SCHEDULE: 1	100					
Description =	OFFSET FOUNDATION, POLE, JU/STEEL MAST A		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
460.01	OFFSET FOUNDATION, POLE, JU/STEEL MAST	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	7,500.000				7,500		7,500
BID ITEM = 461	CLIENT# = 461		Land Item	SCHEDULE: 1	100					
Description =	INSTALL MAST ARM, 30 FT AND LESS, OWNER		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
461.01	INSTALL MAST ARM, 30 FT AND LESS, OWNER	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 EA	1,300.000				1,300		1,300
BID ITEM = 462	CLIENT# = 462		Land Item	SCHEDULE: 1	100					
Description =	CONDUIT, PVC, 1 IN		Unit =	LF	Takeoff Quan:		1,950.000	Engr Quan:		1,950.000
462.01	CONDUIT, PVC, 1 IN	Quan:	1,950.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1,950.00 LF	11.600				22,620		22,620
BID ITEM = 463	CLIENT# = 463		Land Item	SCHEDULE: 1	100					
Description =	CONDUIT, PVC, 2 IN		Unit =	LF	Takeoff Quan:		41,694.000	Engr Quan:		41,694.000
463.01	CONDUIT, PVC, 2 IN	Quan:	41,694.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	41,694.00 LF	13.600				567,038		567,038
BID ITEM = 464	CLIENT# = 464		Land Item	SCHEDULE: 1	100					
Description =	CONDUIT, PVC, 3 IN		Unit =	LF	Takeoff Quan:		62,883.000	Engr Quan:		62,883.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 464	CLIENT# = 464	Land Item	SCHEDULE: 1	100						
Description =	CONDUIT, PVC, 3 IN	Unit =	LF	Takeoff	Quan:	62,883.000	Engr	Quan:	62,883.000	
464.01	CONDUIT, PVC, 3 IN	Quan:	62,883.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	62,883.00 LF	21.300				1,339,408	1,339,408	
BID ITEM = 465	CLIENT# = 465	Land Item	SCHEDULE: 1	100						
Description =	CONDUIT, PVC, 4 IN	Unit =	LF	Takeoff	Quan:	382.000	Engr	Quan:	382.000	
465.01	CONDUIT, PVC, 4 IN	Quan:	382.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	382.00 LF	33.000				12,606	12,606	
BID ITEM = 466	CLIENT# = 466	Land Item	SCHEDULE: 1	100						
Description =	CONDUIT, RGS, 3/4 IN	Unit =	LF	Takeoff	Quan:	130.000	Engr	Quan:	130.000	
466.01	CONDUIT, RGS, 3/4 IN	Quan:	130.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	130.00 LF	34.600				4,498	4,498	
BID ITEM = 467	CLIENT# = 467	Land Item	SCHEDULE: 1	100						
Description =	CONDUIT, RGS, 1 IN	Unit =	LF	Takeoff	Quan:	1,800.000	Engr	Quan:	1,800.000	
467.01	CONDUIT, RGS, 1 IN	Quan:	1,800.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1,800.00 LF	19.800				35,640	35,640	
BID ITEM = 468	CLIENT# = 468	Land Item	SCHEDULE: 1	100						
Description =	CONDUIT, RGS, 2 IN	Unit =	LF	Takeoff	Quan:	3,835.000	Engr	Quan:	3,835.000	
468.01	CONDUIT, RGS, 2 IN	Quan:	3,835.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	3,835.00 LF	32.800				125,788	125,788	
BID ITEM = 469	CLIENT# = 469	Land Item	SCHEDULE: 1	100						
Description =	CONDUIT, RGS, 3 IN	Unit =	LF	Takeoff	Quan:	865.000	Engr	Quan:	865.000	
469.01	CONDUIT, RGS, 3 IN	Quan:	865.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	865.00 LF	60.800				52,592	52,592	
BID ITEM = 470	CLIENT# = 470	Land Item	SCHEDULE: 1	100						
Description =	CONDUIT, RGS, 4 IN	Unit =	LF	Takeoff	Quan:	20.000	Engr	Quan:	20.000	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 470	CLIENT# = 470		Land Item	SCHEDULE: 1	100					
Description =	CONDUIT, RGS, 4 IN		Unit =	LF	Takeoff Quan:	20.000		Engr Quan:		20.000
470.01	CONDUIT, RGS, 4 IN		Quan:	20.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	20.00 LF	160.000				3,200		3,200
BID ITEM = 471	CLIENT# = 471		Land Item	SCHEDULE: 1	100					
Description =	TRENCHING, SCL SERVICE, CONDUIT		Unit =	LF	Takeoff Quan:	1,805.000		Engr Quan:		1,805.000
471.01	TRENCHING, SCL SERVICE, CONDUIT		Quan:	1,805.00 LF	Hrs/Shft:	10.00	Cal: 610	WC: WAAVG		
4ELEC	Electrical sub	1.00	1,805.00 LF	0.001				2		2
4TREN	TRENCHING SUB	1.00	1,805.00 LF	27.750				50,089		50,089
\$50,090.56				[]				50,091		50,091
====>	Item Totals:	471	- TRENCHING, SCL SERVICE, CONDUIT							
\$50,090.56				[]				50,091		50,091
27.751		1805 LF						27.75		27.75
BID ITEM = 472	CLIENT# = 472		Land Item	SCHEDULE: 1	100					
Description =	TRENCHING, SDOT, CONDUIT		Unit =	LF	Takeoff Quan:	26,891.000		Engr Quan:		26,891.000
172.01	TRENCHING, SDOT, CONDUIT		Quan:	26,891.00 LF	Hrs/Shft:	10.00	Cal: 610	WC: WAAVG		
4TREN	TRENCHING SUB	1.00	26,891.00 LF	27.750				746,225		746,225
BID ITEM = 473	CLIENT# = 473		Land Item	SCHEDULE: 1	100					
Description =	TRENCHING, SCL LIGHTING, CONDUIT		Unit =	LF	Takeoff Quan:	10,485.000		Engr Quan:		10,485.000
473.01	TRENCHING, SCL LIGHTING, CONDUIT		Quan:	10,485.00 LF	Hrs/Shft:	10.00	Cal: 610	WC: WAAVG		
4ELEC	Electrical sub	1.00	10,485.00 LF	0.001				10		10
4TREN	TRENCHING SUB	1.00	10,485.00 LF	27.750				290,959		290,959
\$290,969.24				[]				290,969		290,969
====>	Item Totals:	473	- TRENCHING, SCL LIGHTING, CONDUIT							
\$290,969.24				[]				290,969		290,969
27.751		10485 LF						27.75		27.75
BID ITEM = 474	CLIENT# = 474		Land Item	SCHEDULE: 1	100					
Description =	TRENCHING, SDOT/SCL LIGHTING, CONDUIT		Unit =	LF	Takeoff Quan:	1,150.000		Engr Quan:		1,150.000
474.01	TRENCHING, SDOT/SCL LIGHTING, CONDUIT		Quan:	1,150.00 LF	Hrs/Shft:	10.00	Cal: 610	WC: WAAVG		
4ELEC	Electrical sub	1.00	1,150.00 LF	0.001				1		1
4TREN	TRENCHING SUB	1.00	1,150.00 LF	27.750				31,913		31,913
\$31,913.65				[]				31,914		31,914
====>	Item Totals:	474	- TRENCHING, SDOT/SCL LIGHTING, CONDUIT							
\$31,913.65				[]				31,914		31,914

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 474	CLIENT# = 474		Land Item	SCHEDULE: 1	100					
Description =	TRENCHING, SDOT/SCL LIGHTING, CONDUIT		Unit =	LF	Takeoff	Quan:	1,150.000	Engr Quan:		1,150.000
27.751	1150 LF							27.75		27.75
BID ITEM = 475	CLIENT# = 475		Land Item	SCHEDULE: 1	100					
Description =	TRENCHING, KCM, CONDUIT		Unit =	LF	Takeoff	Quan:	4,309.000	Engr Quan:		4,309.000
475.01	TRENCHING, KCM, CONDUIT		Quan:	4,309.00 LF	Hrs/Shft:	10.00	Cal: 610	WC: WAAVG		
4TREN	TRENCHING SUB	1.00	4,309.00 LF	27.750				119,575		119,575
BID ITEM = 476	CLIENT# = 476		Land Item	SCHEDULE: 1	100					
Description =	CONDUIT RISER, 2 IN		Unit =	EA	Takeoff	Quan:	6.000	Engr Quan:		6.000
476.01	CONDUIT RISER, 2 IN		Quan:	6.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	6.00 EA	1,200.000				7,200		7,200
BID ITEM = 477	CLIENT# = 477		Land Item	SCHEDULE: 1	100					
Description =	CONDUIT RISER, 3 IN		Unit =	EA	Takeoff	Quan:	48.000	Engr Quan:		48.000
477.01	CONDUIT RISER, 3 IN		Quan:	48.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	48.00 EA	1,790.000				85,920		85,920
BID ITEM = 478	CLIENT# = 478		Land Item	SCHEDULE: 1	100					
Description =	HANDHOLE, TYPE 1		Unit =	EA	Takeoff	Quan:	11.000	Engr Quan:		11.000
478.01	HANDHOLE, TYPE 1		Quan:	11.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	11.00 EA	1,090.000				11,990		11,990
BID ITEM = 479	CLIENT# = 479		Land Item	SCHEDULE: 1	100					
Description =	HANDHOLE, TYPE 2		Unit =	EA	Takeoff	Quan:	235.000	Engr Quan:		235.000
479.01	HANDHOLE, TYPE 2		Quan:	235.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	235.00 EA	1,490.000				350,150		350,150
BID ITEM = 480	CLIENT# = 480		Land Item	SCHEDULE: 1	100					
Description =	HANDHOLE, TYPE 3		Unit =	EA	Takeoff	Quan:	177.000	Engr Quan:		177.000
480.01	HANDHOLE, TYPE 3		Quan:	177.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	177.00 EA	2,980.000				527,460		527,460

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 481	CLIENT# = 481		Land Item	SCHEDULE: 1	100					
Description =	HANDHOLE, TYPE 5		Unit =	EA	Takeoff Quan:	145.000		Engr Quan:		145.000
481.01	HANDHOLE, TYPE 5		Quan:	145.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	145.00 EA	3,030.000				439,350		439,350
BID ITEM = 482	CLIENT# = 482		Land Item	SCHEDULE: 1	100					
Description =	HANDHOLE, TYPE 6		Unit =	EA	Takeoff Quan:	11.000		Engr Quan:		11.000
482.01	HANDHOLE, TYPE 6		Quan:	11.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	11.00 EA	4,630.000				50,930		50,930
BID ITEM = 483	CLIENT# = 483		Land Item	SCHEDULE: 1	100					
Description =	HANDHOLE, TYPE 2R		Unit =	EA	Takeoff Quan:	30.000		Engr Quan:		30.000
483.01	HANDHOLE, TYPE 2R		Quan:	30.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	30.00 EA	1,640.000				49,200		49,200
BID ITEM = 484	CLIENT# = 484		Land Item	SCHEDULE: 1	100					
Description =	HANDHOLE, TYPE 3R		Unit =	EA	Takeoff Quan:	16.000		Engr Quan:		16.000
484.01	HANDHOLE, TYPE 3R		Quan:	16.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	16.00 EA	3,150.000				50,400		50,400
BID ITEM = 485	CLIENT# = 485		Land Item	SCHEDULE: 1	100					
Description =	HANDHOLE, TYPE 5R		Unit =	EA	Takeoff Quan:	16.000		Engr Quan:		16.000
485.01	HANDHOLE, TYPE 5R		Quan:	16.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	16.00 EA	3,810.000				60,960		60,960
BID ITEM = 486	CLIENT# = 486		Land Item	SCHEDULE: 1	100					
Description =	LID, HANDHOLE, TYPE 6		Unit =	EA	Takeoff Quan:	5.000		Engr Quan:		5.000
486.01	LID, HANDHOLE, TYPE 6		Quan:	5.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	5.00 EA	2,800.000				14,000		14,000
BID ITEM = 487	CLIENT# = 487		Land Item	SCHEDULE: 1	100					
Description =	LID, HANDHOLE, TYPE 5		Unit =	EA	Takeoff Quan:	4.000		Engr Quan:		4.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 487	CLIENT# = 487		Land Item	SCHEDULE: 1	100					
Description =	LID, HANDHOLE, TYPE 5		Unit =	EA	Takeoff	Quan:	4.000	Engr Quan:		4.000
487.01	LID, HANDHOLE, TYPE 5		Quan:	4.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	4.00 EA	2,150.000				8,600		8,600
BID ITEM = 488	CLIENT# = 488		Land Item	SCHEDULE: 1	100					
Description =	CONDUIT ENCASEMENT SYSTEM		Unit =	LF	Takeoff	Quan:	458.000	Engr Quan:		458.000
488.01	CONDUIT ENCASEMENT SYSTEM		Quan:	458.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	458.00 LF	125.000				57,250		57,250
BID ITEM = 489	CLIENT# = 489		Land Item	SCHEDULE: 1	100					
Description =	CONDUIT, RGS, 3 IN, AREAWAY		Unit =	LF	Takeoff	Quan:	20.000	Engr Quan:		20.000
489.01	CONDUIT, RGS, 3 IN, AREAWAY		Quan:	20.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	20.00 LF	140.000				2,800		2,800
BID ITEM = 490	CLIENT# = 490		Land Item	SCHEDULE: 1	100					
Description =	UTILITY VAULT 7' 2"X 4' 10" X 5' 2"		Unit =	EA	Takeoff	Quan:	1.000	Engr Quan:		1.000
490.01	UTILITY VAULT, FURNISH AND INSTALL		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	1.00 EA	13,000.000				13,000		13,000
BID ITEM = 491	CLIENT# = 491		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM SPRING AND 3RD AVENUE E		Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:		1.000
491.01	TRUNCATED DOMES		Quan:	110.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
2TRUNK	TRUNKATED DOME@11	1.00	110.00 SF	13.850		1,680				1,680
491.02	WHEEL GUID		Quan:	55.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:		0.00
2WHEEL	STATION WHEEL @110.	1.00	55.00 LF	109.260		6,625				6,625
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$7,741.42	0.2909 MH/LF		16.00 MH	[16.931]	1,116	6,625				7,741
491.03	STATION FOUNDATIONS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	8.00 CY	121.150		1,069				1,069
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,329.36	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	1,069				9,329

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----	------------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 491 CLIENT# = 491 Land Item SCHEDULE: 1 100
Description = STATION PLATFORM SPRING AND 3RD AVENUE E Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

491.04 SIDEWALKS **Quan: 30.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		8.00	CH	Prod: 8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	11.00	CY	121.150		1,469		1,469
CEJ	Cement Mason	5.00	40.00	MH	64.980	3,408			3,408
FOCO	Concrete Forman	1.00	8.00	MH	68.980	723			723
\$5,599.65	1.6000 MH/SY		48.00	MH	[115.538]	4,130	1,469		5,600

491.05 FOUNDATION STEM WALLS **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		8.00	CH	Prod: 8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	1.00	CY	121.150		134		134
CEJ	Cement Mason	5.00	40.00	MH	64.980	3,408			3,408
FOCO	Concrete Forman	1.00	8.00	MH	68.980	723			723
\$4,263.97	48.0000 MH/LS		48.00	MH	[3466.14]	4,130	134		4,264

491.06 STATION CHANALIZATION **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

4STRI	Striping sub	1.00	1.00	LS	500.000			500	500
-------	--------------	------	------	----	---------	--	--	-----	-----

491.07 REBAR PURCHASE **Quan: 122.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2RB5	#5 REBAR@110.25%	1.00	122.00		2.000	269			269
------	------------------	------	--------	--	-------	-----	--	--	-----

====> **Item Totals: 491 - STATION PLATFORM SPRING AND 3RD AVENUE E**

\$29,383.07	208.0000 MH/LS		208.00	MH	[14795.79]	17,638	11,245	500	29,383
29,383.070	1 LS					17,637.79	11,245.28	500.00	29,383.07

BID ITEM = 492 CLIENT# = 492 Land Item SCHEDULE: 1 100
Description = STATION PLATFORM SPRING AND 4TH AVENUE E Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

492.01 TRUNCATED DOMES **Quan: 126.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2TRUNK	TRUNKATED DOME@11	1.00	126.00	SF	13.850	1,924			1,924
--------	-------------------	------	--------	----	--------	-------	--	--	-------

492.02 WHEEL GUIDE **Quan: 64.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00	CH	Prod: 8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
2WHEEL	STATION WHEEL @110.	1.00	64.00	LF	109.260		7,709		7,709
LAG	General Laborer	2.00	16.00	MH	52.910	1,116			1,116
\$8,825.56	0.2500 MH/LF		16.00	MH	[14.55]	1,116	7,709		8,826

492.03 STATION FOUNDATION **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		16.00	CH	Prod: 16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	12.00	CY	121.150		1,603		1,603
CEJ	Cement Mason	5.00	80.00	MH	64.980	6,816			6,816
FOCO	Concrete Forman	1.00	16.00	MH	68.980	1,445			1,445
\$9,863.63	96.0000 MH/LS		96.00	MH	[6932.29]	8,261	1,603		9,864

492.04 SIDEWALKS **Quan: 45.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		8.00	CH	Prod: 8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	11.00	CY	121.150		1,469		1,469
CEJ	Cement Mason	5.00	40.00	MH	64.980	3,408			3,408
FOCO	Concrete Forman	1.00	8.00	MH	68.980	723			723

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
-------------------	------	-----	---------------	-----------	-------	---------------	-----------------	------------	--------------	-------

BID ITEM = 492 CLIENT# = 492 Land Item SCHEDULE: 1 100
Description = STATION PLATFORM SPRING AND 4TH AVENUE E Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000
\$5,599.65 1.0666 MH/SY 48.00 MH [77.025] 4,130 1,469 5,600

492.05 FOUNDATION STEM WALLS Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

COM	Concrete 6 Man Crew		8.00	CH	Prod: 8.0000	CH	Lab Pcs: 6.00	Eqp Pcs: 0.00	
2CR040	4000LB READY M@110.2	1.00	1.00	CY	121.150	134			134
CEJ	Cement Mason	5.00	40.00	MH	64.980	3,408			3,408
FOCO	Concrete Forman	1.00	8.00	MH	68.980	723			723
\$4,263.97	48.0000 MH/LS		48.00	MH	[3466.14]	4,130	134		4,264

492.06 STATION CHANALIZATION Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4STRI	Striping sub	1.00	1.00	LS	500.000			500	500
-------	--------------	------	------	----	---------	--	--	-----	-----

492.07 LEAN RAIL Quan: 6.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

ZZZZ	SITE FURNISHINGS CREW		8.00	CH	Prod: 8.0000	CH	Lab Pcs: 2.00	Eqp Pcs: 0.00	
2LEAN	LEAN RAIL@110.25%	1.00	6.00	LF	176.770	1,169			1,169
LAG	General Laborer	2.00	16.00	MH	52.910	1,116			1,116
\$2,285.50	2.6666 MH/LF		16.00	MH	[155.203]	1,116	1,169		2,286

492.08 REBAR PURCHASE Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

2RB4	#4 REBAR@110.25%	1.00	43.00		1.500	71			71
2RB5	#5 REBAR@110.25%	1.00	122.00	LF	2.000	269			269
\$340.12					[]	340			340

====> **Item Totals: 492 - STATION PLATFORM SPRING AND 4TH AVENUE E**
\$33,602.40 224.0000 MH/LS 224.00 MH [15727.01] 18,754 14,348 500 **33,602**
33,602.400 1 LS 18,753.96 14,348.44 500.00 33,602.40

BID ITEM = 493 CLIENT# = 493 Land Item SCHEDULE: 1 100
Description = STATION PLATFORM SPRING AND 8TH AVENUE E Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

493.01 TRUNCATED DOMES Quan: 123.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

2TRUNK	TRUNKATED DOME@11	1.00	123.00	SF	13.850	1,878			1,878
--------	-------------------	------	--------	----	--------	-------	--	--	-------

493.02 WHEEL GUIDE Quan: 62.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

ZZZZ	SITE FURNISHINGS CREW		8.00	CH	Prod: 8.0000	CH	Lab Pcs: 2.00	Eqp Pcs: 0.00	
2WHEEL	STATION WHEEL @110.	1.00	62.00	LF	109.260	7,468			7,468
LAG	General Laborer	2.00	16.00	MH	52.910	1,116			1,116
\$8,584.64	0.2580 MH/LF		16.00	MH	[15.02]	1,116	7,468		8,585

493.03 STATION FOUNDATIONS Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

COM	Concrete 6 Man Crew		24.00	CH	Prod: 24.0000	CH	Lab Pcs: 6.00	Eqp Pcs: 0.00	
2CR040	4000LB READY M@110.2	1.00	19.00	CY	121.150	2,538			2,538
CEJ	Cement Mason	5.00	120.00	MH	64.980	10,224			10,224
FOCO	Concrete Forman	1.00	24.00	MH	68.980	2,168			2,168
\$14,929.01	144.0000 MH/LS		144.00	MH	[10398.43]	12,391	2,538		14,929

493.04 SIDEWALKS Quan: 26.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

COM	Concrete 6 Man Crew		8.00	CH	Prod: 8.0000	CH	Lab Pcs: 6.00	Eqp Pcs: 0.00	
2CR040	4000LB READY M@110.2	1.00	8.10	CY	121.150	1,082			1,082

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 493 CLIENT# = 493 Land Item SCHEDULE: 1 100										
Description =	STATION PLATFORM SPRING AND 8TH AVENUE E		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$5,212.30	1.8461 MH/SY		48.00 MH	[133.313]	4,130	1,082				5,212
493.05 FOUNDATION STEM WALL Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
COM	Concrete 6 Man Crew		8.00 CH	Prod: 8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00		
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150	134					134
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$4,263.97	48.0000 MH/LS		48.00 MH	[3466.14]	4,130	134				4,264
493.06 STATION CHANALIZATION Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
4STRI	Striping sub	1.00	1.00 LS	500.000				500		500
493.07 REBAR PURCHASE Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000	269					269
====> Item Totals: 493 - STATION PLATFORM SPRING AND 8TH AVENUE E										
\$35,637.09	256.0000 MH/LS		256.00 MH	[18261.93]	21,768	13,369		500		35,637
35,637.090	1 LS				21,768.19	13,368.90		500.00		35,637.09
BID ITEM = 494 CLIENT# = 494 Land Item SCHEDULE: 1 100										
Description =	STATION PLATFORM MADISON AND 3RD AVENUE		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
494.01 TRUNCATED DOMES Quan: 100.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
2TRUNK	TRUNKATED DOME@11	1.00	100.00 SF	13.850	1,527					1,527
494.02 WHEEL GUIDE Quan: 56.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
ZZZZ	SITE FURNISHINGS CREW		8.00 CH	Prod: 8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00		
2WHEEL	STATION WHEEL @110.	1.00	56.00 LF	109.260	6,746					6,746
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$7,861.88	0.2857 MH/LF		16.00 MH	[16.629]	1,116	6,746				7,862
494.03 STATION FOUNDATIONS Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
COM	Concrete 6 Man Crew		16.00 CH	Prod: 16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00		
2CR040	4000LB READY M@110.2	1.00	6.00 CY	121.150	801					801
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,062.23	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	801				9,062
494.04 SIDEWALKS Quan: 32.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
COM	Concrete 6 Man Crew		8.00 CH	Prod: 8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00		
2CR040	4000LB READY M@110.2	1.00	9.00 CY	121.150	1,202					1,202
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$5,332.51	1.5000 MH/SY		48.00 MH	[108.317]	4,130	1,202				5,333
494.05 FOUNDATION STEM WALL Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
COM	Concrete 6 Man Crew		8.00 CH	Prod: 8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00		

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 494	CLIENT# = 494		Land Item	SCHEDULE: 1 100						
Description =	STATION PLATFORM MADISON AND 3RD AVENUE	Unit =	LS	Takeoff Quan:		1.000	Engr Quan:			1.000
2CR040	4000LB READY M@110.2	1.00	2.20 CY	121.150		294				294
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$4,424.25	48.0000 MH/LS		48.00 MH	[3466.14]	4,130	294				4,424
494.06	STATION CHANALIZATION		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
4STRI	Striping sub	1.00	1.00 LS	500.000					500	500
494.07	REBAR PURCHASE		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
2RB4	#4 REBAR@110.25%	1.00	48.00 LF	1.500		79				79
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000		269				269
\$348.39				[]		348				348
====> Item Totals: 494	- STATION PLATFORM MADISON AND 3RD AVENUE									
\$29,056.22	208.0000 MH/LS		208.00 MH	[14795.79]	17,638	10,918			500	29,056
29,056.220	1 LS				17,637.79	10,918.43			500.00	29,056.22
BID ITEM = 495	CLIENT# = 495		Land Item	SCHEDULE: 1 100						
Description =	STATION PLATFORM MADISON AND 5TH AVENUE	Unit =	LS	Takeoff Quan:		1.000	Engr Quan:			1.000
495.01	TRUNCATED DOME		Quan:	117.00 SF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
2TRUNK	TRUNKATED DOME@11	1.00	117.00 SF	13.850		1,787				1,787
495.02	WHEEL GUIDE		Quan:	62.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:		0.00
2WHEEL	STATION WHEEL @110.	1.00	62.00 LF	109.260		7,468				7,468
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$8,584.64	0.2580 MH/LF		16.00 MH	[15.02]	1,116	7,468				8,585
495.03	STATION FOUNDATIONS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	9.00 CY	121.150		1,202				1,202
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,462.93	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	1,202				9,463
495.04	STATION SIDEWALKS		Quan:	111.00 SY	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	20.00 CY	121.150		2,671				2,671
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$10,932.18	0.8648 MH/SY		96.00 MH	[62.453]	8,261	2,671				10,932
495.05	FOUNDATION STEM WALL		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150		134				134
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$4,263.97	48.0000 MH/LS		48.00 MH	[3466.14]	4,130	134				4,264

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 495	CLIENT# = 495		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM MADISON AND 5TH AVENUE		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
495.06	STATION CHANALIZATION		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	1.00 LS	500.000				500		500
495.07	REBAR PURCHASE		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
2RB5	#5 REBAR@110.25%	1.00	186.00 LF	2.000		410				410
===== Item Totals: 495 - STATION PLATFORM MADISON AND 5TH AVENUE										
\$35,940.40	256.0000 MH/LS		256.00 MH	[18261.94]	21,768	13,672		500		35,940
35,940.400	1 LS				21,768.21	13,672.19		500.00		35,940.40
BID ITEM = 496	CLIENT# = 496		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM MADISON AND 8TH AVENUE		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
496.01	TRUNCATED DOMES		Quan:	165.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
2TRUNK	TRUNKATED DOME@11	1.00	165.00 SF	13.850		2,519				2,519
496.02	WHEEL GUIDE		Quan:	65.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:		0.00
2WHEEL	STATION WHEEL @110.	1.00	65.00 LF	109.260		7,830				7,830
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$8,946.01	0.2461 MH/LF		16.00 MH	[14.326]	1,116	7,830				8,946
496.03	STATION FOUNDATIONS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	10.00 CY	121.150		1,336				1,336
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,596.50	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	1,336				9,597
496.04	STATION SIDEWALKS		Quan:	32.00 SY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	29.00 CY	121.150		3,873				3,873
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$8,003.87	1.5000 MH/SY		48.00 MH	[108.317]	4,130	3,873				8,004
496.05	FOUNDATION STEM WALLS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150		134				134
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$4,263.97	48.0000 MH/LS		48.00 MH	[3466.14]	4,130	134				4,264
496.06	STATION CHANALIZATION		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	1.00 LS	500.000				500		500
496.07	ISLAND NOSING		Quan:	6.00 SY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 496 CLIENT# = 496 Land Item SCHEDULE: 1 100									
Description =	STATION PLATFORM MADISON AND 8TH AVENUE		Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:	1.000
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	5.00 CY	121.150		668			668
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408				3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723				723
\$4,798.24	8.0000 MH/SY		48.00 MH	[577.69]	4,130	668			4,798
496.08	BARRIER RAIL		Quan:	87.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
2BARE	BARRIER RAIL@110.25%	1.00	87.00 LF	269.880		25,886			25,886
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
\$27,002.38	0.1839 MH/LF		16.00 MH	[10.704]	1,116	25,886			27,002
496.09	BARRIER RAIL W HANDRAIL		Quan:	32.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
2BAREH	BARRIER RAIL W@110.2	1.00	32.00 LF	294.610		10,394			10,394
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
\$11,510.01	0.5000 MH/LF		16.00 MH	[29.101]	1,116	10,394			11,510
496.10	REBAR PURCHASE		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
2RB4	#4 REBAR@110.25%	1.00	614.00 LF	1.500		1,015			1,015
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000		269			269
\$1,284.41				[]		1,284			1,284
====> Item Totals: 496 - STATION PLATFORM MADISON AND 8TH AVENUE									
\$78,424.88	288.0000 MH/LS		288.00 MH	[20124.37]	24,001	53,924		500	78,425
78,424.880	1 LS				24,000.53	53,924.35		500.00	78,424.88

BID ITEM = 497 CLIENT# = 497 Land Item SCHEDULE: 1 100									
Description =	STATION PLATFORM MADISON AND TERRY AVENUE		Unit =	LS	Takeoff	Quan:	1.000	Engr Quan:	1.000
497.01	TRUNKATED DOME		Quan:	192.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
2TRUNK	TRUNKATED DOME@11	1.00	192.00 SF	13.850		2,932			2,932
497.02	WHEEL GUIDE		Quan:	200.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<u>ZZZZ</u>	SITE FURNISHINGS CREW		24.00 CH	Prod:	24.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
2WHEEL	STATION WHEEL @110.	1.00	200.00 LF	109.260		24,092			24,092
LAG	General Laborer	2.00	48.00 MH	52.910	3,349				3,349
\$27,440.33	0.2400 MH/LF		48.00 MH	[13.968]	3,349	24,092			27,440
497.03	STATION FOUNDATIONS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<u>COM</u>	Concrete 6 Man Crew		24.00 CH	Prod:	24.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	19.00 CY	121.150		2,538			2,538
CEJ	Cement Mason	5.00	120.00 MH	64.980	10,224				10,224
FOCO	Concrete Forman	1.00	24.00 MH	68.980	2,168				2,168
\$14,929.01	144.0000 MH/LS		144.00 MH	[10398.43]	12,391	2,538			14,929
497.04	STATION SIDEWALKS		Quan:	97.00 SY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	31.00 CY	121.150		4,141			4,141

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 497 CLIENT# = 497 Land Item SCHEDULE: 1 100										
Description =	STATION PLATFORM MADISON AND TERRY AVENU	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$12,401.42	0.9896 MH/SY	96.00	MH	[71.467]	8,261	4,141				12,401
497.05 FOUNDATION STEM WALLS Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150	134					134
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$4,263.97	48.0000 MH/LS	48.00	MH	[3466.14]	4,130	134				4,264
497.06 STATION CHANALIZATION Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
4STRI	Striping sub	1.00	1.00 LS	500.000				500		500
497.07 ISLAND NOSING Quan: 30.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	10.00 CY	121.150	1,336					1,336
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$5,466.08	1.6000 MH/SY	48.00	MH	[115.538]	4,130	1,336				5,466
497.08 LEANING RAIL Quan: 6.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
<u>ZZZ</u>	SIGN CREW		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
2LEAN	LEAN RAIL@110.25%	1.00	6.00 LF	176.770	1,169					1,169
LAG	General Laborer	1.00	4.00 MH	52.910	279					279
\$1,448.37	0.6666 MH/LF	4.00	MH	[38.8]	279	1,169				1,448
497.09 BARRIER RAIL Quan: 158.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
<u>ZZZ</u>	SIGN CREW		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	1.00	Eqp Pcs:	0.00	
2BARE	BARRIER RAIL@110.25%	1.00	158.00 LF	269.880	47,012					47,012
LAG	General Laborer	1.00	16.00 MH	52.910	1,116					1,116
\$48,127.92	0.1012 MH/LF	16.00	MH	[5.894]	1,116	47,012				48,128
497.10 BARRIER RAIL WITH HANDRAIL Quan: 56.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2BAREH	BARRIER RAIL W@110.2	1.00	56.00 LF	294.610	18,189					18,189
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$19,305.39	0.2857 MH/LF	16.00	MH	[16.629]	1,116	18,189				19,305
497.11 REBAR PURCHASE Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
2RB4	#4 REBAR@110.25%	1.00	1,350.00 LF	1.500	2,233					2,233
2RB5	#5 REBAR@110.25%	1.00	308.00 LF	2.000	679					679
\$2,911.70				[]	2,912					2,912
====> Item Totals: 497 - STATION PLATFORM MADISON AND TERRY AVENU										
\$139,725.96	420.0000 MH/LS	420.00	MH	[29151.89]	34,773	104,453		500		139,726
139,725.960	1 LS				34,772.72	104,453.24		500.00		139,725.96

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----	------------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 498 CLIENT# = 498 Land Item SCHEDULE: 1 100
Description = STATION PLATFORM MADISON AND BOYLSTON AV Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

498.01 TRUNCATED DOMES **Quan: 332.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2TRUNK	TRUNKATED DOME@11	1.00	332.00 SF	13.850		5,070				5,070
--------	-------------------	------	-----------	--------	--	-------	--	--	--	-------

498.02 WHEEL GUIDE **Quan: 425.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>ZZZZ</u>	SITE FURNISHINGS CREW		32.00 CH	Prod:	32.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2WHEEL	STATION WHEEL @110.	1.00	425.00 LF	109.260	51,195					51,195
LAG	General Laborer	2.00	64.00 MH	52.910	4,465					4,465
\$55,659.80	0.1505 MH/LF		64.00 MH	[8.764]	4,465	51,195				55,660

498.03 STATION FOUNDATION **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		32.00 CH	Prod:	32.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	29.00 CY	121.150	3,873					3,873
CEJ	Cement Mason	5.00	160.00 MH	64.980	13,632					13,632
FOCO	Concrete Forman	1.00	32.00 MH	68.980	2,890					2,890
\$20,395.10	192.0000 MH/LS		192.00 MH	[13864.58]	16,522	3,873				20,395

498.04 STATION SIDEWALKS **Quan: 248.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		24.00 CH	Prod:	24.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	71.36 CY	121.150	9,531					9,531
CEJ	Cement Mason	5.00	120.00 MH	64.980	10,224					10,224
FOCO	Concrete Forman	1.00	24.00 MH	68.980	2,168					2,168
\$21,922.62	0.5806 MH/SY		144.00 MH	[41.929]	12,391	9,531				21,923

498.05 FOUNDATION STEM WALLS **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150	134					134
CEJ	Cement Mason	5.00	20.00 MH	64.980	1,704					1,704
FOCO	Concrete Forman	1.00	4.00 MH	68.980	361					361
\$2,198.77	24.0000 MH/LS		24.00 MH	[1733.07]	2,065	134				2,199

498.06 STATION CHANALIZATION **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

4STRI	Striping sub	1.00	1.00 LS	500.000					500	500
-------	--------------	------	---------	---------	--	--	--	--	-----	-----

498.07 ISLAND NOSING **Quan: 12.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	4.00 CY	121.150	534					534
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$4,664.67	4.0000 MH/SY		48.00 MH	[288.845]	4,130	534				4,665

498.08 BARRIER RAIL **Quan: 342.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>ZZZZ</u>	SITE FURNISHINGS CREW		24.00 CH	Prod:	24.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2BARE	BARRIER RAIL@110.25%	1.00	342.00 LF	269.880	101,760					101,760
LAG	General Laborer	2.00	48.00 MH	52.910	3,349					3,349
\$105,108.10	0.1403 MH/LF		48.00 MH	[8.169]	3,349	101,760				105,108

498.09 BARRIER RAIL W HANDRAIL **Quan: 91.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2BAREH	BARRIER RAIL W@110.2	1.00	91.00 LF	294.610	29,557					29,557

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 498 CLIENT# = 498 Land Item SCHEDULE: 1 100										
Description =	STATION PLATFORM MADISON AND BOYLSTON AV	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$30,673.65	0.1758 MH/LS		16.00 MH	[10.233]	1,116	29,557				30,674
498.10 REBAR PURCHASE Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
2RB4	#4 REBAR@110.25%	1.00	2,360.00 LF	1.500		3,903				3,903
2RB5	#5 REBAR@110.25%	1.00	372.00 LF	2.000		820				820
\$4,723.11				[]		4,723				4,723
===== Item Totals: 498 - STATION PLATFORM MADISON AND BOYLSTON AV										
\$250,915.34	536.0000 MH/LS		536.00 MH	[36911.95]	44,038	206,378		500		250,915
250,915.340	1 LS				44,037.78	206,377.56		500.00		250,915.34
BID ITEM = 499 CLIENT# = 499 Land Item SCHEDULE: 1 100										
Description =	STATION PLATFORM MADISON AND EAST UNION	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
499.01 TRUNKATED DOME Quan: 184.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
2TRUNK	TRUNKATED DOME@11	1.00	184.00 SF	13.850		2,810				2,810
499.02 WHEEL GUIDE Quan: 301.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
<u>ZZZZ</u>	SITE FURNISHINGS CREW		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2WHEEL	STATION WHEEL @110.	1.00	301.00 LF	109.260		36,258				36,258
LAG	General Laborer	2.00	32.00 MH	52.910	2,232					2,232
\$38,490.53	0.1063 MH/LF		32.00 MH	[6.187]	2,232	36,258				38,491
499.03 STATION FOUNDATIONS Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
<u>COM</u>	Concrete 6 Man Crew		32.00 CH	Prod:	32.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	20.00 CY	121.150		2,671				2,671
CEJ	Cement Mason	5.00	160.00 MH	64.980	13,632					13,632
FOCO	Concrete Forman	1.00	32.00 MH	68.980	2,890					2,890
\$19,192.99	192.0000 MH/LS		192.00 MH	[13864.58]	16,522	2,671				19,193
499.04 STATION SIDEWALKS Quan: 241.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
<u>COM</u>	Concrete 6 Man Crew		24.00 CH	Prod:	24.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	63.00 CY	121.150		8,415				8,415
CEJ	Cement Mason	5.00	120.00 MH	64.980	10,224					10,224
FOCO	Concrete Forman	1.00	24.00 MH	68.980	2,168					2,168
\$20,806.00	0.5975 MH/SY		144.00 MH	[43.147]	12,391	8,415				20,806
499.05 FOUNDATION STEM WALLS Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150		134				134
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$4,263.97	48.0000 MH/LS		48.00 MH	[3466.14]	4,130	134				4,264
499.06 STATION CHANALIZATION Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
4STRI	Striping sub	1.00	1.00 LS	500.000				500		500

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 499	CLIENT# = 499		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM MADISON AND EAST UNION		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
499.07	ISLAND NOSING			Quan:	12.00 SY	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>COM</u>	Concrete 6 Man Crew		6.00 CH	Prod:	6.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	1.50 CY	121.150		200				200
CEJ	Cement Mason	5.00	30.00 MH	64.980	2,556					2,556
FOCO	Concrete Forman	1.00	6.00 MH	68.980	542					542
\$3,298.15	3.0000 MH/SY		36.00 MH	[216.634]	3,098	200				3,298
499.08	LEANING RAIL			Quan:	7.00 LF	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>ZZZZ</u>	SITE FURNISHINGS CREW		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2LEAN	LEAN RAIL@110.25%	1.00	7.00 LF	176.770		1,364				1,364
LAG	General Laborer	2.00	8.00 MH	52.910	558					558
\$1,922.30	1.1428 MH/LF		8.00 MH	[66.516]	558	1,364				1,922
499.09	BARRIER RAIL			Quan:	350.00 LS	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>ZZZZ</u>	SITE FURNISHINGS CREW		24.00 CH	Prod:	24.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2BARE	BARRIER RAIL@110.25%	1.00	350.00 LF	269.880		104,140				104,140
LAG	General Laborer	2.00	48.00 MH	52.910	3,349					3,349
\$107,488.45	0.1371 MH/LS		48.00 MH	[7.982]	3,349	104,140				107,488
499.10	BARRIER RAIL W HANDRAIL			Quan:	160.00 LS	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>ZZZZ</u>	SITE FURNISHINGS CREW		12.00 CH	Prod:	12.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2BAREH	BARRIER RAIL W@110.2	1.00	160.00 LF	294.610		51,969				51,969
LAG	General Laborer	2.00	24.00 MH	52.910	1,674					1,674
\$53,643.44	0.1500 MH/LS		24.00 MH	[8.73]	1,674	51,969				53,643
499.11	REBAR PURCHASE			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
2RB4	#4 REBAR@110.25%	1.00	2,731.00 LF	1.500		4,516				4,516
2RB5	#5 REBAR@110.25%	1.00	244.00 LF	2.000		538				538
\$5,054.41				[]		5,054				5,054
====>	Item Totals:	499	- STATION PLATFORM MADISON AND EAST UNION							
\$257,469.85	532.0000 MH/LS		532.00 MH	[36847.27]	43,954	213,016		500	257,470	
257,469.850	1 LS				43,954.20	213,015.65		500.00	257,469.85	

BID ITEM = 500	CLIENT# = 500		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM MADISON AND 17TH AVENUE		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
500.01	TRUNCATED DOME			Quan:	100.00 SF	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
2TRUNK	TRUNKATED DOME@11	1.00	100.00 SF	13.850		1,527				1,527
500.02	WHEEL GUIDE			Quan:	54.00 LF	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2WHEEL	STATION WHEEL @110.	1.00	54.00 LF	109.260		6,505				6,505
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$7,620.96	0.2962 MH/LF		16.00 MH	[17.245]	1,116	6,505				7,621
500.03	STATION FOUNDATIONS			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM	= 500	CLIENT# = 500		Land Item	SCHEDULE: 1	100				
Description =	STATION PLATFORM MADISON AND 17TH AVENUE	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
2CR040	4000LB READY M@110.2	1.00	11.00 CY	121.150		1,469				1,469
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,730.07	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	1,469				9,730
500.04	STATION SIDEWALKS			Quan:	104.00 SY	Hrs/Shift:	10.00	Cal:	510	WC: WAAVG
<u>COM</u>	Concrete 6 Man Crew		12.00 CH	Prod:	12.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	15.00 CY	121.150		2,004				2,004
CEJ	Cement Mason	5.00	60.00 MH	64.980	5,112					5,112
FOCO	Concrete Forman	1.00	12.00 MH	68.980	1,084					1,084
\$8,199.13	0.6923 MH/SY		72.00 MH	[49.993]	6,196	2,004				8,199
500.05	FOUNDATION STEM WALLS			Quan:	1.00 LS	Hrs/Shift:	10.00	Cal:	510	WC: WAAVG
<u>COM</u>	Concrete 6 Man Crew		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150		134				134
CEJ	Cement Mason	5.00	20.00 MH	64.980	1,704					1,704
FOCO	Concrete Forman	1.00	4.00 MH	68.980	361					361
\$2,198.77	24.0000 MH/LS		24.00 MH	[1733.07]	2,065	134				2,199
500.06	STATION CHANALIZATION			Quan:	1.00 LS	Hrs/Shift:	10.00	Cal:	510	WC: WAAVG
4STRI	Striping sub	1.00	1.00 LS	500.000					500	500
500.07	REBAR PURCHASE			Quan:	1.00 LS	Hrs/Shift:	10.00	Cal:	510	WC: WAAVG
2RB4	#4 REBAR@110.25%	1.00	27.00 LF	1.500		45				45
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000		269				269
\$313.66				[]		314				314
=====	Item Totals:	500	- STATION PLATFORM MADISON AND 17TH AVENUE							
\$30,089.55	208.0000 MH/LS		208.00 MH	[14795.8]	17,638	11,952			500	30,090
30,089.550	1 LS				17,637.80	11,951.75			500.00	30,089.55

BID ITEM	= 501	CLIENT# = 501		Land Item	SCHEDULE: 1	100				
Description =	STATION PLATFORM MADISON AND 17TH AVENUE	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
501.01	TRUNKATED DOME			Quan:	99.00 SF	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
2TRUNK	TRUNKATED DOME@11	1.00	99.00 SF	13.850		1,512				1,512
501.02	WHEEL GUIDE			Quan:	54.00 LF	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2WHEEL	STATION WHEEL @110.	1.00	54.00 LF	109.260		6,505				6,505
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$7,620.96	0.2962 MH/LF		16.00 MH	[17.245]	1,116	6,505				7,621
501.03	STATION FOUNDATIONS			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	12.00 CY	121.150		1,603				1,603
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,863.63	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	1,603				9,864

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 501	CLIENT# = 501		Land Item	SCHEDULE: 1 100						
Description =	STATION PLATFORM MADISON AND 17TH AVENUE		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
501.04	STATION SIDEWALKS		Quan:	106.00 SY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		12.00 CH	Prod:	12.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	15.00 CY	121.150		2,004			2,004	
CEJ	Cement Mason	5.00	60.00 MH	64.980	5,112				5,112	
FOCO	Concrete Forman	1.00	12.00 MH	68.980	1,084				1,084	
\$8,199.13	0.6792 MH/SY		72.00 MH	[49.049]	6,196	2,004			8,199	
501.05	FOUNDATION STEM WALLS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150		134			134	
CEJ	Cement Mason	5.00	20.00 MH	64.980	1,704				1,704	
FOCO	Concrete Forman	1.00	4.00 MH	68.980	361				361	
\$2,198.77	24.0000 MH/LS		24.00 MH	[1733.07]	2,065	134			2,199	
501.06	STATION CHANALIZATION		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	1.00 LS	500.000				500	500	
501.07	REBAR PURCHASE		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
2RB4	#4 REBAR@110.25%	1.00	27.00 LF	1.500		45			45	
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000		269			269	
\$313.66				[]		314			314	
===== Item Totals: 501 - STATION PLATFORM MADISON AND 17TH AVENUE										
\$30,207.84	208.0000 MH/LS		208.00 MH	[14795.8]	17,638	12,070		500	30,208	
30,207.840	1 LS				17,637.80	12,070.04		500.00	30,207.84	

BID ITEM = 502	CLIENT# = 502		Land Item	SCHEDULE: 1 100						
Description =	STATION PLATFORM MADISON AND EAST DENNY		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
502.01	TRUNCATED DOMES		Quan:	120.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
2TRUNK	TRUNKATED DOME@11	1.00	120.00 SF	13.850		1,832			1,832	
502.02	WHEEL GUIDE		Quan:	56.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2WHEEL	STATION WHEEL @110.	1.00	56.00 LF	109.260		6,746			6,746	
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116	
\$7,861.88	0.2857 MH/LF		16.00 MH	[16.629]	1,116	6,746			7,862	
502.03	STATION FOUNDATIONS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	16.00 CY	121.150		2,137			2,137	
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816				6,816	
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445				1,445	
\$10,397.91	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	2,137			10,398	
502.04	STATION SIDEWALKS		Quan:	60.00 SY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	10.00 CY	121.150		1,336			1,336	

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 502	CLIENT# = 502		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM MADISON AND EAST DENNY	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$5,466.08	0.8000 MH/SY	48.00 MH	[57.769]	4,130	1,336					5,466
502.05	FOUNDATION STEM WALLS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150		134				134
CEJ	Cement Mason	5.00	20.00 MH	64.980	1,704					1,704
FOCO	Concrete Forman	1.00	4.00 MH	68.980	361					361
\$2,198.77	24.0000 MH/LS	24.00 MH	[1733.07]	2,065	134					2,199
502.06	STATION CHANALIZATION		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4STRI	Striping sub	1.00	1.00 LS	500.000					500	500
502.07	REBAR PURCHASE		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
2RB4	#4 REBAR@110.25%	1.00	27.00 LF	1.500		45				45
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000		269				269
\$313.66			[]		314					314
====>	Item Totals: 502		- STATION PLATFORM MADISON AND EAST DENNY							
\$28,570.66	184.0000 MH/LS	184.00 MH	[13062.72]	15,573	12,498			500	28,571	
28,570.660	1 LS			15,572.59	12,498.07			500.00	28,570.66	

BID ITEM = 503	CLIENT# = 503		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM MADISON AND EAST DENNY	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000	
503.01	TRUNCATED DOMES		Quan:	121.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
2TRUNK	TRUNKATED DOME@11	1.00	121.00 SF	13.850	1,848					1,848
503.02	WHEEL GUIDE		Quan:	64.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00	
2WHEEL	STATION WHEEL @110.	1.00	64.00 LF	109.260		7,709				7,709
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$8,825.56	0.2500 MH/LF	16.00 MH	[14.55]	1,116	7,709					8,826
503.03	STATION FOUNDATIONS		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	8.00 CY	121.150		1,069				1,069
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,329.36	96.0000 MH/LS	96.00 MH	[6932.29]	8,261	1,069					9,329
503.04	STATION SIDEWALKS		Quan:	67.00 SY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	14.00 CY	121.150		1,870				1,870
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$6,000.35	0.7164 MH/SY	48.00 MH	[51.733]	4,130	1,870					6,000

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----	------------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 503 CLIENT# = 503 Land Item SCHEDULE: 1 100
Description = STATION PLATFORM MADISON AND EAST DENNY Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

503.05 FOUNDATION STEM WALL **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		4.00	CH	Prod:	4.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	1.00	CY	121.150	134				134
CEJ	Cement Mason	5.00	20.00	MH	64.980	1,704				1,704
FOCO	Concrete Forman	1.00	4.00	MH	68.980	361				361
\$2,198.77	24.0000 MH/LS		24.00	MH	[1733.07]	2,065	134			2,199

503.06 STATION CHANALIZATION **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

4STRI	Striping sub	1.00	1.00	LS	500.000				500	500
-------	--------------	------	------	----	---------	--	--	--	-----	-----

503.07 REBAR PURCHASE **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2RB5	#5 REBAR@110.25%	1.00	122.00	LF	2.000	269				269
------	------------------	------	--------	----	-------	-----	--	--	--	-----

====> **Item Totals: 503 - STATION PLATFORM MADISON AND EAST DENNY**
 \$28,970.67 184.0000 MH/LS 184.00 MH [13062.72] 15,573 12,898 500 **28,971**
 28,970.670 1 LS 15,572.59 12,898.08 500.00 28,970.67

BID ITEM = 504 CLIENT# = 504 Land Item SCHEDULE: 1 100
Description = STATION PLATFORM MADISON AND 23RD AVENUE Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

504.01 TRUNCATED DOMES **Quan: 74.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2TRUNK	TRUNKATED DOME@11	1.00	74.00	SF	13.850	1,130				1,130
--------	-------------------	------	-------	----	--------	-------	--	--	--	-------

504.02 WHEEL GUIDE **Quan: 65.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00	CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
2WHEEL	STATION WHEEL @110.	1.00	65.00	LF	109.260	7,830				7,830
LAG	General Laborer	2.00	16.00	MH	52.910	1,116				1,116
\$8,946.01	0.2461 MH/LF		16.00	MH	[14.326]	1,116	7,830			8,946

504.03 STATION FOUNDATION **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		16.00	CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	8.00	CY	121.150	1,069				1,069
CEJ	Cement Mason	5.00	80.00	MH	64.980	6,816				6,816
FOCO	Concrete Forman	1.00	16.00	MH	68.980	1,445				1,445
\$9,329.36	96.0000 MH/LS		96.00	MH	[6932.29]	8,261	1,069			9,329

504.04 STATION SIDEWALKS **Quan: 70.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		8.00	CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	13.00	CY	121.150	1,736				1,736
CEJ	Cement Mason	5.00	40.00	MH	64.980	3,408				3,408
FOCO	Concrete Forman	1.00	8.00	MH	68.980	723				723
\$5,866.78	0.6857 MH/SY		48.00	MH	[49.516]	4,130	1,736			5,867

504.05 FOUNDATION STEM WALL **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		8.00	CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	1.00	CY	121.150	134				134
CEJ	Cement Mason	5.00	40.00	MH	64.980	3,408				3,408
FOCO	Concrete Forman	1.00	8.00	MH	68.980	723				723

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 504 CLIENT# = 504 Land Item SCHEDULE: 1 100									
Description =	STATION PLATFORM MADISON AND 23RD AVENUE	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
\$4,263.97	48.0000 MH/LS	48.00	MH	[3466.14]	4,130	134			4,264
504.06	STATION CHANALIZATION	Quan:	1.00 LS	Hrs/Shift:	10.00	Cal:	510	WC:	WAAVG
4STRI	Striping sub	1.00	1.00 LS	500.000				500	500
504.07	REBAR PURCHASE	Quan:	1.00 LS	Hrs/Shift:	10.00	Cal:	510	WC:	WAAVG
2RB4	#4 REBAR@110.25%	1.00	27.00 LF	1.500		45			45
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000		269			269
\$313.66				[]		314			314
====> Item Totals: 504 - STATION PLATFORM MADISON AND 23RD AVENUE									
\$30,349.73	208.0000 MH/LS	208.00	MH	[14795.79]	17,638	12,212		500	30,350
30,349.730	1 LS				17,637.79	12,211.94		500.00	30,349.73
BID ITEM = 505 CLIENT# = 505 Land Item SCHEDULE: 1 100									
Description =	STATION PLATFORM MADISON AND 24TH AVENUE	Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
505.01	TRUNCATED DOMES	Quan:	117.00 SF	Hrs/Shift:	10.00	Cal:	510	WC:	WAAVG
2TRUNK	TRUNKATED DOME@11	1.00	117.00 SF	13.850		1,787			1,787
505.02	WHEEL GUIDE	Quan:	71.00 LF	Hrs/Shift:	10.00	Cal:	510	WC:	WAAVG
<u>ZZZZ</u>	SITE FURNISHINGS CREW	8.00	CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
\$1,116.17	0.2253 MH/LF	16.00	MH	[13.116]	1,116				1,116
505.03	STATION FOUNDATIONS	Quan:	1.00 LS	Hrs/Shift:	10.00	Cal:	510	WC:	WAAVG
<u>COM</u>	Concrete 6 Man Crew	16.00	CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	14.00 CY	121.150	1,870				1,870
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816				6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445				1,445
\$10,130.77	96.0000 MH/LS	96.00	MH	[6932.29]	8,261	1,870			10,131
505.04	STATION SIDEWALKS	Quan:	92.00 SY	Hrs/Shift:	10.00	Cal:	510	WC:	WAAVG
<u>COM</u>	Concrete 6 Man Crew	12.00	CH	Prod:	12.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	17.00 CY	121.150	2,271				2,271
CEJ	Cement Mason	5.00	60.00 MH	64.980	5,112				5,112
FOCO	Concrete Forman	1.00	12.00 MH	68.980	1,084				1,084
\$8,466.26	0.7826 MH/SY	72.00	MH	[56.513]	6,196	2,271			8,466
505.05	FOUNDATION STEM WALLS	Quan:	1.00 LS	Hrs/Shift:	10.00	Cal:	510	WC:	WAAVG
<u>COM</u>	Concrete 6 Man Crew	8.00	CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150	134				134
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408				3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723				723
\$4,263.97	48.0000 MH/LS	48.00	MH	[3466.14]	4,130	134			4,264
505.06	STATION CHANALIZATION	Quan:	1.00 LS	Hrs/Shift:	10.00	Cal:	510	WC:	WAAVG
4STRI	Striping sub	1.00	1.00 LS	500.000				500	500

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 505 CLIENT# = 505 Land Item SCHEDULE: 1 100
Description = STATION PLATFORM MADISON AND 24TH AVENUE Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

505.07 REBAR PURCHASE **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2RB4	#4 REBAR@110.25%	1.00	27.00 LF	1.500		45				45
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000		269				269
\$313.66				[]		314				314

====> **Item Totals: 505 - STATION PLATFORM MADISON AND 24TH AVENUE**
\$26,577.38 232.0000 MH/LS 232.00 MH [16528.87] 19,703 6,374 500 **26,577**
26,577.380 1 LS 19,703.00 6,374.38 500.00 26,577.38

BID ITEM = 506 CLIENT# = 506 Land Item SCHEDULE: 1 100
Description = STATION PLATFORM MADISON AND MLK WAY Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

506.01 TRUNCATED DOMES **Quan: 117.00 SF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2TRUNK	TRUNKATED DOME@11	1.00	117.00 SF	13.850		1,787				1,787
--------	-------------------	------	-----------	--------	--	-------	--	--	--	-------

506.02 WHEEL GUIDE **Quan: 65.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
2WHEEL	STATION WHEEL @110.	1.00	65.00 LF	109.260		7,830			7,830
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
\$8,946.01	0.2461 MH/LF		16.00 MH	[14.326]	1,116	7,830			8,946

506.03 STATION FOUNDATIONS **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	9.00 CY	121.150		1,202			1,202
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816				6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445				1,445
\$9,462.93	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	1,202			9,463

506.04 STATION SIDEWALKS **Quan: 73.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	12.00 CY	121.150		1,603			1,603
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408				3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723				723
\$5,733.21	0.6575 MH/SY		48.00 MH	[47.481]	4,130	1,603			5,733

506.05 FOUNDATION STEM WALLS **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>COM</u>	Concrete 6 Man Crew		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150		134			134
CEJ	Cement Mason	5.00	20.00 MH	64.980	1,704				1,704
FOCO	Concrete Forman	1.00	4.00 MH	68.980	361				361
\$2,198.77	24.0000 MH/LS		24.00 MH	[1733.07]	2,065	134			2,199

506.06 STATION CHANALIZATION **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

4STRI	Striping sub	1.00	1.00 LS	500.000					500	500
-------	--------------	------	---------	---------	--	--	--	--	-----	-----

506.07 REBAR PURCHASE **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2RB4	#4 REBAR@110.25%	1.00	27.00 LF	1.500		45				45
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000		269				269

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 506	CLIENT# = 506		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM MADISON AND MLK WAY		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
\$313.66				[]		314				314
====> Item Totals: 506 - STATION PLATFORM MADISON AND MLK WAY										
\$28,941.13	184.0000 MH/LS	184.00	MH	[13062.72]	15,573	12,869		500		28,941
28,941.130	1 LS				15,572.59	12,868.54		500.00		28,941.13

BID ITEM = 507	CLIENT# = 507		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM EAST UNION AND 12TH AVE		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
507.01 STATION FOUNDATION										
			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>COM</u>	Concrete 6 Man Crew		8.00	CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	3.00	CY	121.150		401			401
CEJ	Cement Mason	5.00	40.00	MH	64.980	3,408				3,408
FOCO	Concrete Forman	1.00	8.00	MH	68.980	723				723
\$4,531.10	48.0000 MH/LS	48.00	MH	[3466.14]	4,130	401				4,531
507.02 STATION SIDEWALKS										
			Quan:	82.00 SY	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>COM</u>	Concrete 6 Man Crew		8.00	CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	9.00	CY	121.150		1,202			1,202
CEJ	Cement Mason	5.00	40.00	MH	64.980	3,408				3,408
FOCO	Concrete Forman	1.00	8.00	MH	68.980	723				723
\$5,332.51	0.5853 MH/SY	48.00	MH	[42.27]	4,130	1,202				5,333
507.03 BARRIER RAIL										
			Quan:	44.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00	CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
2BARE	BARRIER RAIL@110.25%	1.00	44.00	LF	269.880		13,092			13,092
LAG	General Laborer	2.00	16.00	MH	52.910	1,116				1,116
\$14,208.05	0.3636 MH/LF	16.00	MH	[21.164]	1,116	13,092				14,208
====> Item Totals: 507 - STATION PLATFORM EAST UNION AND 12TH AVE										
\$24,071.66	112.0000 MH/LS	112.00	MH	[7863.5]	9,377	14,695				24,072
24,071.660	1 LS				9,376.97	14,694.69				24,071.66

BID ITEM = 508	CLIENT# = 508		Land Item	SCHEDULE: 1	100					
Description =	STATION PLATFORM EAST MADISON STREET AND		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
508.01 TRUNCATED DOMES										
			Quan:	108.00 SF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
2TRUNK	TRUNKATED DOME@11	1.00	108.00	SF	13.850		1,649			1,649
508.02 WHEEL GUIDE										
			Quan:	57.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>ZZZZ</u>	SITE FURNISHINGS CREW		8.00	CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00
2WHEEL	STATION WHEEL @110.	1.00	57.00	LF	109.260		6,866			6,866
LAG	General Laborer	2.00	16.00	MH	52.910	1,116				1,116
\$7,982.34	0.2807 MH/LF	16.00	MH	[16.337]	1,116	6,866				7,982
508.03 STATION FOUNDATION										
			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>COM</u>	Concrete 6 Man Crew		16.00	CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	6.00	CY	121.150		801			801

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 508 CLIENT# = 508 Land Item SCHEDULE: 1 100										
Description =	STATION PLATFORM EAST MADISON STREET AND		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,062.23	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	801				9,062
508.04 STATION SIDEWALKS Quan: 42.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
COM	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	10.00 CY	121.150	1,336					1,336
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$5,466.08	1.1428 MH/SY		48.00 MH	[82.527]	4,130	1,336				5,466
508.05 FOUNDATION STEM WALL Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
COM	Concrete 6 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150	134					134
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408					3,408
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723					723
\$4,263.97	48.0000 MH/LS		48.00 MH	[3466.14]	4,130	134				4,264
508.06 STATION CHANALIZATION Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
4STRI	Striping sub	1.00	1.00 LS	500.000				500		500
508.07 REBAR PURCHASE Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000	269					269
====> Item Totals: 508 - STATION PLATFORM EAST MADISON STREET AND										
\$29,192.75	208.0000 MH/LS		208.00 MH	[14795.79]	17,638	11,055		500		29,193
29,192.750	1 LS				17,637.79	11,054.96		500.00		29,192.75

BID ITEM = 509 CLIENT# = 509 Land Item SCHEDULE: 1 100										
Description =	STATION PLATFORM MADISON AND 1ST AVE NB		Unit =	LS	Takeoff	Quan:	1.000	Engr	Quan:	1.000
509.01 WHEEL GUIDE Quan: 61.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
ZZZZ	SITE FURNISHINGS CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	2.00	Eqp Pcs:		0.00
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
\$1,116.17	0.2622 MH/LF		16.00 MH	[15.266]	1,116					1,116
509.02 STATION FOUNDATION Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
COM	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	10.00 CY	121.150	1,336					1,336
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,596.50	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	1,336				9,597
509.03 STATION SIDEWALKS Quan: 112.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG										
COM	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:		0.00
2CR040	4000LB READY M@110.2	1.00	13.00 CY	121.150	1,736					1,736
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$9,997.20	0.8571 MH/SY		96.00 MH	[61.895]	8,261	1,736				9,997

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 509	CLIENT# = 509	Land Item	SCHEDULE: 1	100						
Description =	STATION PLATFORM MADISON AND 1ST AVE NB	Unit =	LS	Takeoff	Quan:		1.000	Engr	Quan:	1.000
509.04	FOUNDATION STEM WALLS	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>COM</u>	Concrete 6 Man Crew	8.00	CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	1.00 CY	121.150		134			134	
CEJ	Cement Mason	5.00	40.00 MH	64.980	3,408				3,408	
FOCO	Concrete Forman	1.00	8.00 MH	68.980	723				723	
\$4,263.97	48.0000 MH/LS	48.00	MH	[3466.14]	4,130	134			4,264	
509.05	STATION CHANALIZATION	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4STRI	Striping sub	1.00	1.00 LS	500.000				500		500
509.06	REBAR PURCHASE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
2RB4	#4 REBAR@110.25%	1.00	27.00 LF	1.500		45			45	
2RB5	#5 REBAR@110.25%	1.00	122.00 LF	2.000		269			269	
\$313.66				[]		314			314	
=====	Item Totals: 509 - STATION PLATFORM MADISON AND 1ST AVE NB									
\$25,787.50	256.0000 MH/LS	256.00	MH	[18261.94]	21,768	3,519		500	25,788	
25,787.500	1 LS				21,768.21	3,519.29		500.00	25,787.50	

BID ITEM = 510	CLIENT# = 510	Land Item	SCHEDULE: 1	100						
Description =	EXTRA LAMINATED TEMPERED GLASS PANELS	Unit =	EA	Takeoff	Quan:		20.000	Engr	Quan:	20.000
510.01	EXTRA LAMINATED TEMPERED GLASS PANEL	Quan:	20.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4GLAS	GLASS INSTALLER	1.00	20.00 EA	325.000				6,500		6,500
BID ITEM = 511	CLIENT# = 511	Land Item	SCHEDULE: 1	100						
Description =	FURNISH AND INSTALL RAPIDRIDE SHELTER, R	Unit =	EA	Takeoff	Quan:		3.000	Engr	Quan:	3.000
511.01	FURNISH AND INSTALL RAPIDRIDE SHELTER, R	Quan:	3.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>ZZZZZ</u>	(Mod) SHELTER CREW	30.00	CH	Prod:	30.0000 CH	Lab Pcs:	3.00	Eqp Pcs:	0.00	
2SHEL208	SHELTER TYPE 2@110.2	1.00	3.00 EA	36,100.000		119,401			119,401	
3BOOM	BOOM TRUCK	1.00	30.00 HR	250.000		7,500			7,500	
4GLAS	GLASS INSTALLER	1.00	3.00 EA	5,409.000				16,227	16,227	
LAG	General Laborer	3.00	90.00 MH	52.910	6,278				6,278	
\$149,406.18	30.0000 MH/EA	90.00	MH	[1746.03]	6,278	119,401	7,500	16,227	149,406	
=====	Item Totals: 511 - FURNISH AND INSTALL RAPIDRIDE SHELTER, R									
\$149,406.18	30.0000 MH/EA	90.00	MH	[1746.03]	6,278	119,401	7,500	16,227	149,406	
49,802.060	3 EA				2,092.81	39,800.25	2,500.00	5,409.00	49,802.06	

BID ITEM = 512	CLIENT# = 512	Land Item	SCHEDULE: 1	100						
Description =	FURNISH AND INSTALL RAPIDRIDE SHELTER, R	Unit =	EA	Takeoff	Quan:		5.000	Engr	Quan:	5.000
512.01	FURNISH AND INSTALL RAPIDRIDE SHELTER, R	Quan:	5.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	

Activity	Desc	Quantity	Unit	Unit Cost	Labor	Perm	Constr	Equip	Sub-	Total
Resource	Pcs					Material	Matl/Exp	Ment	Contract	
BID ITEM =	512	CLIENT# = 512	Land Item	SCHEDULE:	1	100				
Description =	FURNISH AND INSTALL RAPIDRIDE SHELTER, R	Unit =	EA	Takeoff	Quan:		5.000	Engr	Quan:	5.000
ZZZZZ	(Mod) SHELTER CREW	50.00	CH	Prod:	50.0000	CH	Lab Pcs:	3.00	Eqp Pcs:	0.00
2SHEL206	SHELTER TYPE 2@110.2	1.00	EA	34,625.000		190,870				190,870
3BOOM	BOOM TRUCK	1.00	HR	250.000			12,500			12,500
4GLAS	GLASS INSTALLER	1.00	EA	5,409.000				27,045		27,045
LAG	General Laborer	3.00	MH	52.910	10,464					10,464
\$240,879.36	30.0000 MH/EA	150.00	MH	[1746.03]	10,464	190,870	12,500		27,045	240,879
====>	Item Totals:	512	- FURNISH AND INSTALL RAPIDRIDE SHELTER, R							
\$240,879.36	30.0000 MH/EA	150.00	MH	[1746.03]	10,464	190,870	12,500		27,045	240,879
48,175.872	5 EA				2,092.81	38,174.06	2,500.00		5,409.00	48,175.87
BID ITEM =	513	CLIENT# = 513	Land Item	SCHEDULE:	1	100				
Description =	FURNISH AND INSTALL RAPIDRIDE SHELTER, R	Unit =	EA	Takeoff	Quan:		8.000	Engr	Quan:	8.000
513.01	FURNISH AND INSTALL RAPIDRIDE SHELTER,	Quan:	8.00	EA	Hrs/Shift:	10.00	Cal: 510	WC: WAAVG		
ZZZZZ	(Mod) SHELTER CREW	80.00	CH	Prod:	80.0000	CH	Lab Pcs:	3.00	Eqp Pcs:	0.00
2SHEL206LP	SHELTER TYPE 2@110.2	1.00	EA	33,805.000		298,160				298,160
3BOOM	BOOM TRUCK	1.00	HR	250.000			20,000			20,000
4GLAS	GLASS INSTALLER	1.00	EA	5,409.000				43,272		43,272
LAG	General Laborer	3.00	MH	52.910	16,742					16,742
\$378,174.57	30.0000 MH/EA	240.00	MH	[1746.03]	16,742	298,160	20,000		43,272	378,175
====>	Item Totals:	513	- FURNISH AND INSTALL RAPIDRIDE SHELTER, R							
\$378,174.57	30.0000 MH/EA	240.00	MH	[1746.03]	16,742	298,160	20,000		43,272	378,175
47,271.821	8 EA				2,092.81	37,270.01	2,500.00		5,409.00	47,271.82
BID ITEM =	514	CLIENT# = 514	Land Item	SCHEDULE:	1	100				
Description =	FURNISH AND INSTALL RAPIDRIDE SHELTER, R	Unit =	EA	Takeoff	Quan:		8.000	Engr	Quan:	8.000
514.01	FURNISH AND INSTALL RAPIDRIDE SHELTER,	Quan:	8.00	EA	Hrs/Shift:	10.00	Cal: 510	WC: WAAVG		
ZZZZZ	(Mod) SHELTER CREW	80.00	CH	Prod:	80.0000	CH	Lab Pcs:	3.00	Eqp Pcs:	0.00
2SHEL126	SHELTER TYPE 1@110.2	1.00	EA	20,780.000		183,280				183,280
3BOOM	BOOM TRUCK	1.00	HR	250.000			20,000			20,000
4GLAS	GLASS INSTALLER	1.00	EA	5,409.000				43,272		43,272
LAG	General Laborer	3.00	MH	52.910	16,742					16,742
\$263,294.07	30.0000 MH/EA	240.00	MH	[1746.03]	16,742	183,280	20,000		43,272	263,294
====>	Item Totals:	514	- FURNISH AND INSTALL RAPIDRIDE SHELTER, R							
\$263,294.07	30.0000 MH/EA	240.00	MH	[1746.03]	16,742	183,280	20,000		43,272	263,294
32,911.759	8 EA				2,092.81	22,909.95	2,500.00		5,409.00	32,911.76
BID ITEM =	515	CLIENT# = 515	Land Item	SCHEDULE:	1	100				
Description =	INSTALL OWNER FURNISHED, METRO ROUTE SIG	Unit =	EA	Takeoff	Quan:		22.000	Engr	Quan:	22.000
515.01	INSTALL OWNER FURNISHED, METRO ROUTE	Quan:	22.00	EA	Hrs/Shift:	10.00	Cal: 510	WC: WAAVG		
ZZZ	SIGN CREW	11.00	CH	Prod:	11.0000	CH	Lab Pcs:	1.00	Eqp Pcs:	0.00
LAG	General Laborer	1.00	MH	52.910	767					767
\$767.36	0.5000 MH/EA	11.00	MH	[29.1]	767		</			

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Ment	Contract	Total
BID ITEM = 515	CLIENT# = 515	Land Item	SCHEDULE: 1	100						
Description =	INSTALL OWNER FURNISHED, METRO ROUTE SIG	Unit =	EA	Takeoff	Quan:	22.000	Engr	Quan:		22.000
====>	Item Totals: 515 - INSTALL OWNER FURNISHED, METRO ROUTE SIG									
\$767.36	0.5000 MH/EA	11.00 MH	[29.1]	767						767
34.880	22 EA			34.88						34.88

BID ITEM = 516	CLIENT# = 516	Land Item	SCHEDULE: 1	100						
Description =	INSTALL OWNER FURNISHED, TRASH RECEPTACL	Unit =	EA	Takeoff	Quan:	19.000	Engr	Quan:		19.000
516.01	INSTALL OWNER FURNISHED, TRASH RECEPT	Quan:	19.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
<u>ZZZZ</u>	SITE FURNISHINGS CREW	15.00 CH	Prod:	15.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00		
LAG	General Laborer	2.00 30.00 MH	52.910	2,093				2,093		
\$2,092.81	1.5789 MH/EA	30.00 MH	[91.896]	2,093				2,093		
====>	Item Totals: 516 - INSTALL OWNER FURNISHED, TRASH RECEPTACL									
\$2,092.81	1.5789 MH/EA	30.00 MH	[91.896]	2,093				2,093		
110.148	19 EA			110.15				110.15		

BID ITEM = 517	CLIENT# = 517	Land Item	SCHEDULE: 1	100						
Description =	INSTALL OWNER FURNISHED, TICKET VENDING	Unit =	EA	Takeoff	Quan:	3.000	Engr	Quan:		3.000
517.01	INSTALL OWNER FURNISHED, TICKET VENDIN	Quan:	3.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00 3.00 EA	1,600.000					4,800		4,800

BID ITEM = 518	CLIENT# = 518	Land Item	SCHEDULE: 1	100						
Description =	INSTALL OWNER FURNISHED, TECH PYLON WITH	Unit =	EA	Takeoff	Quan:	21.000	Engr	Quan:		21.000
518.01	INSTALL OWNER FURNISHED, TECH PYLON WI	Quan:	21.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00 21.00 EA	4,750.000					99,750		99,750

BID ITEM = 519	CLIENT# = 519	Land Item	SCHEDULE: 1	100						
Description =	INSTALL OWNER FURNISHED, BENCH	Unit =	EA	Takeoff	Quan:	25.000	Engr	Quan:		25.000
519.01	INSTALL OWNER FURNISHED, BENCH	Quan:	25.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
<u>ZZZZ</u>	SITE FURNISHINGS CREW	20.00 CH	Prod:	20.0000 CH	Lab Pcs:	2.00	Eqp Pcs:	0.00		
LAG	General Laborer	2.00 40.00 MH	52.910	2,790				2,790		
\$2,790.41	1.6000 MH/EA	40.00 MH	[93.122]	2,790				2,790		
====>	Item Totals: 519 - INSTALL OWNER FURNISHED, BENCH									
\$2,790.41	1.6000 MH/EA	40.00 MH	[93.122]	2,790				2,790		
111.616	25 EA			111.62				111.62		

BID ITEM = 520	CLIENT# = 520	Land Item	SCHEDULE: 1	100						
Description =	INSTALL OWNER FURNISHED, BLADE	Unit =	EA	Takeoff	Quan:	41.000	Engr	Quan:		41.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 520	CLIENT# = 520		Land Item	SCHEDULE: 1	100					
Description =	INSTALL OWNER FURNISHED, BLADE		Unit =	EA	Takeoff Quan:		41.000	Engr Quan:		41.000
520.01	INSTALL OWNER FURNISHED, BLADE		Quan:	41.00 EA	Hrs/Shift:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZZZ</u>	SHELTER CREW		41.00 CH	Prod:	41.0000 CH	Lab Pcs:	3.00	Eqp Pcs:	2.00	
8TRBOOM	BOOM TRUCK	1.00	41.00 HR	45.000				1,845		1,845
8TRML	MANLIFT	1.00	41.00 HR	25.000				1,025		1,025
LAG	General Laborer	3.00	123.00 MH	52.910	8,581					8,581
\$11,450.51	3.0000 MH/EA		123.00 MH	[174.603]	8,581			2,870		11,451
====>	Item Totals: 520 - INSTALL OWNER FURNISHED, BLADE									
\$11,450.51	3.0000 MH/EA		123.00 MH	[174.603]	8,581			2,870		11,451
279.281	41 EA				209.28			70.00		279.28
BID ITEM = 521	CLIENT# = 521		Land Item	SCHEDULE: 1	100					
Description =	FURNISH AND INSTALL RAPIDRIDE SHELTER, R		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
521.01	FURNISH AND INSTALL RAPIDRIDE SHELTER,		Quan:	1.00 EA	Hrs/Shift:	10.00	Cal: 510	WC: WAAVG		
<u>ZZZZZ</u>	(Mod) SHELTER CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	3.00	Eqp Pcs:	0.00	
2SHEL125	SHELTER TYPE 1@110.2	1.00	1.00 EA	19,880.000		21,918				21,918
3BOOM	BOOM TRUCK	1.00	8.00 HR	250.000		2,000				2,000
4GLAS	GLASS INSTALLER	1.00	1.00 EA	5,409.000				5,409		5,409
LAG	General Laborer	3.00	24.00 MH	52.910	1,674					1,674
\$31,000.94	24.0000 MH/EA		24.00 MH	[1396.82]	1,674	21,918	2,000	5,409		31,001
====>	Item Totals: 521 - FURNISH AND INSTALL RAPIDRIDE SHELTER, R									
\$31,000.94	24.0000 MH/EA		24.00 MH	[1396.82]	1,674	21,918	2,000	5,409		31,001
31,000.940	1 EA				1,674.24	21,917.70	2,000.00	5,409.00		31,000.94
BID ITEM = 522	CLIENT# = 522		Land Item	SCHEDULE: 1	100					
Description =	KCM POWER PEDESTAL		Unit =	EA	Takeoff Quan:		15.000	Engr Quan:		15.000
522.01	KCM POWER PEDESTAL		Quan:	15.00 EA	Hrs/Shift:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	15.00 EA	5,750.000				86,250		86,250
BID ITEM = 523	CLIENT# = 523		Land Item	SCHEDULE: 1	100					
Description =	KCM POWER PEDESTAL WITH STEP-DOWN TRANSF		Unit =	EA	Takeoff Quan:		3.000	Engr Quan:		3.000
523.01	KCM POWER PEDESTAL WITH STEP-DOWN TR		Quan:	3.00 EA	Hrs/Shift:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	3.00 EA	5,630.000				16,890		16,890
BID ITEM = 524	CLIENT# = 524		Land Item	SCHEDULE: 1	100					
Description =	FOUNDATION, KCM POWER PEDESTAL		Unit =	EA	Takeoff Quan:		15.000	Engr Quan:		15.000
524.01	FOUNDATION, KCM POWER PEDESTAL		Quan:	15.00 EA	Hrs/Shift:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	15.00 EA	4,110.000				61,650		61,650

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 525	CLIENT# = 525	Land Item	SCHEDULE: 1	100						
Description =	FOUNDATION, KCM POWER PEDESTAL WITH STEP	Unit =	EA	Takeoff Quan:		3.000		Engr Quan:		3.000
525.01	FOUNDATION, KCM POWER PEDESTAL WITH S	Quan:	3.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	3.00 EA	4,110.000				12,330		12,330
BID ITEM = 526	CLIENT# = 526	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, SPRING ST & 3RD AVE	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
526.01	KCM STATION WIRING, SPRING ST & 3RD AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	3,800.000				3,800		3,800
BID ITEM = 527	CLIENT# = 527	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, SPRING ST & 4TH AVE	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
527.01	KCM STATION WIRING, SPRING ST & 4TH AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,900.000				1,900		1,900
BID ITEM = 528	CLIENT# = 528	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, SPRING ST & 8TH AVE	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
528.01	KCM STATION WIRING, SPRING ST & 8TH AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,300.000				1,300		1,300
BID ITEM = 529	CLIENT# = 529	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON ST & 3RD AVE	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
529.01	KCM STATION WIRING, MADISON ST & 3RD AV	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,800.000				1,800		1,800
BID ITEM = 530	CLIENT# = 530	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & 5TH AVE	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
530.01	KCM STATION WIRING, MADISON & 5TH AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,400.000				1,400		1,400
BID ITEM = 531	CLIENT# = 531	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & 8TH AVE	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 531	CLIENT# = 531	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & 8TH AVE	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
531.01	KCM STATION WIRING, MADISON & 8TH AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,300.000				1,300		1,300
BID ITEM = 532	CLIENT# = 532	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & TERRY AVE	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
532.01	KCM STATION WIRING, MADISON & TERRY AV	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	3,400.000				3,400		3,400
BID ITEM = 533	CLIENT# = 533	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & BOYLSTON A	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
533.01	KCM STATION WIRING, MADISON & BOYLSTO	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	6,900.000				6,900		6,900
BID ITEM = 534	CLIENT# = 534	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & E UNION ST	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
534.01	KCM STATION WIRING, MADISON & E UNION S	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	7,100.000				7,100		7,100
BID ITEM = 535	CLIENT# = 535	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & 17TH AVE W	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
535.01	KCM STATION WIRING, MADISON & 17TH AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	4,900.000				4,900		4,900
BID ITEM = 536	CLIENT# = 536	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & 17TH AVE E	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000
536.01	KCM STATION WIRING, MADISON & 17TH AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4ELEC	Electrical sub	1.00	1.00 LS	1,600.000				1,600		1,600
BID ITEM = 537	CLIENT# = 537	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & E DENNY WA	Unit =	LS	Takeoff Quan:		1.000		Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 537	CLIENT# = 537	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & E DENNY WA	Unit =	LS	Takeoff Quan:			1.000	Engr Quan:		1.000
537.01	KCM STATION WIRING, MADISON & E DENNY	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	2,200.000				2,200		2,200
BID ITEM = 538	CLIENT# = 538	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & E DENNY WA	Unit =	LS	Takeoff Quan:			1.000	Engr Quan:		1.000
538.01	KCM STATION WIRING, MADISON & E DENNY	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	3,100.000				3,100		3,100
BID ITEM = 539	CLIENT# = 539	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & 23RD AVE W	Unit =	LS	Takeoff Quan:			1.000	Engr Quan:		1.000
539.01	KCM STATION WIRING, MADISON & 23RD AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	1,600.000				1,600		1,600
BID ITEM = 540	CLIENT# = 540	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & 24TH AVE E	Unit =	LS	Takeoff Quan:			1.000	Engr Quan:		1.000
540.01	KCM STATION WIRING, MADISON & 24TH AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	2,600.000				2,600		2,600
BID ITEM = 541	CLIENT# = 541	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & MLK BLVD W	Unit =	LS	Takeoff Quan:			1.000	Engr Quan:		1.000
541.01	KCM STATION WIRING, MADISON & MLK BLVD	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	1,900.000				1,900		1,900
BID ITEM = 542	CLIENT# = 542	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, MADISON & 27TH AVE E	Unit =	LS	Takeoff Quan:			1.000	Engr Quan:		1.000
542.01	KCM STATION WIRING, MADISON & 27TH AVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	3,100.000				3,100		3,100
BID ITEM = 543	CLIENT# = 543	Land Item	SCHEDULE: 1	100						
Description =	KCM STATION WIRING, 1ST AVE NB	Unit =	LS	Takeoff Quan:			1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 543	CLIENT# = 543		Land Item	SCHEDULE: 1	100					
Description =	KCM STATION WIRING, 1ST AVE NB		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
543.01	KCM STATION WIRING, 1ST AVE NB	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4ELEC	Electrical sub	1.00	1.00 LS	1,800.000				1,800		1,800
BID ITEM = 544	CLIENT# = 544		Land Item	SCHEDULE: 1	100					
Description =	YELLOW DETECTABLE GUIDANCE STRIP		Unit =	LF	Takeoff Quan:		134.000	Engr Quan:		134.000
544.01	YELLOW DETECTABLE GUIDANCE STRIP	Quan:	134.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4STRI	Striping sub	1.00	134.00 LF	25.000				3,350		3,350
BID ITEM = 545	CLIENT# = 545		Land Item	SCHEDULE: 1	100					
Description =	ADJUST EXISTING SCL VAULT ACCESS		Unit =	EA	Takeoff Quan:		15.000	Engr Quan:		15.000
545.01	ADJUST EXISTING SCL VAULT ACCESS	Quan:	15.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>EAS</u>	Earthwork 4 Man Crew		15.00 CH	Prod:	15.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	15.00 HR	51.051			766		766	
8EX100	100 Excavator	1.00	15.00 HR	52.300			784		784	
FOCI	Civil Forman	1.00	15.00 MH	77.060	1,510				1,510	
LAG	General Laborer	2.00	30.00 MH	52.910	2,093				2,093	
OPE	Operator - Excavator	1.00	15.00 MH	74.560	1,462				1,462	
\$6,614.52	4.0000 MH/EA		60.00 MH	[283.184]	5,064		1,550		6,615	
====>	Item Totals: 545 - ADJUST EXISTING SCL VAULT ACCESS									
\$6,614.52	4.0000 MH/EA		60.00 MH	[283.184]	5,064		1,550		6,615	
440.968	15 EA				337.62		103.35		440.97	
BID ITEM = 546	CLIENT# = 546		Land Item	SCHEDULE: 1	100					
Description =	ARTWORK FOUNDATION		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
546.01	ARTWORK FOUNDATION	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>COM</u>	Concrete 6 Man Crew		24.00 CH	Prod:	24.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR040	4000LB READY M@110.2	1.00	8.00 CY	121.150		1,069			1,069	
2REBARART	ART FOUNDATION@110	1.00	1.00 LS	2,500.000		2,756			2,756	
CEJ	Cement Mason	5.00	120.00 MH	64.980	10,224				10,224	
FOCO	Concrete Forman	1.00	24.00 MH	68.980	2,168				2,168	
\$16,216.01	144.0000 MH/LS		144.00 MH	[10398.43]	12,391	3,825			16,216	
====>	Item Totals: 546 - ARTWORK FOUNDATION									
\$16,216.01	144.0000 MH/LS		144.00 MH	[10398.43]	12,391	3,825			16,216	
16,216.010	1 LS				12,391.22	3,824.79			16,216.01	
BID ITEM = 547	CLIENT# = 547		Land Item	SCHEDULE: 1	100					
Description =	PONY BAR RAMP		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 547	CLIENT# = 547		Land Item	SCHEDULE: 1 100						
Description =	PONY BAR RAMP		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
547.01	PONY BAR RAMP		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>COM</u>	Concrete 6 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2PONYRAMP	PONY BAR RAMP@110.2	1.00	1.00 LS	5,000.000		5,513				5,513
CEJ	Cement Mason	5.00	80.00 MH	64.980	6,816					6,816
FOCO	Concrete Forman	1.00	16.00 MH	68.980	1,445					1,445
\$13,773.32	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	5,513				13,773
====>	Item Totals: 547 - PONY BAR RAMP									
\$13,773.32	96.0000 MH/LS		96.00 MH	[6932.29]	8,261	5,513				13,773
13,773.320	1 LS				8,260.82	5,512.50				13,773.32
BID ITEM = 548	CLIENT# = 548		Land Item	SCHEDULE: 1 100						
Description =	MOBILIZATION-SCHEDULE 2		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
548.01	MOBILIZATION-SCHEDULE 2		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
There are no cost resources for this activity.										
====>	Item Totals: 548 - MOBILIZATION-SCHEDULE 2									
\$0.00					[]					
0.000	1 LS									
BID ITEM = 549	CLIENT# = 549		Land Item	SCHEDULE: 1 100						
Description =	SAFETY SYSTEMS IN TRENCH EXCAVATION, MIN		Unit =	SF	Takeoff Quan:	50,405.000		Engr Quan:	50,405.000	
549.01	SAFETY SYSTEMS IN TRENCH EXCAVATION, M		Quan:	50,405.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3SHORING	shoring water line	1.00	1.00 LS	100,000.000		100,000				100,000
====>	Item Totals: 549 - SAFETY SYSTEMS IN TRENCH EXCAVATION, MIN									
\$100,000.00				[]		100,000				100,000
1.984	50405 SF					1.98				1.98
BID ITEM = 550	CLIENT# = 550		Land Item	SCHEDULE: 1 100						
Description =	MINERAL AGGREGATE, TYPE 17		Unit =	TN	Takeoff Quan:	4,520.000		Engr Quan:	4,520.000	
550.01	MINERAL AGGREGATE, TYPE 17		Quan:	4,520.00 TN	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
2AGS17	SEATTLE TYPE 17	1.00	4,520.00 TON	25.750		116,390				116,390
3DEDU02D	Dirt Trucking and Dump	1.00	3,616.00 TCY	24.500			88,592			88,592
\$204,982.00				[]		116,390	88,592			204,982
====>	Item Totals: 550 - MINERAL AGGREGATE, TYPE 17									
\$204,982.00				[]		116,390	88,592			204,982
45.350	4520 TN					25.75	19.60			45.35

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
-------------------	------	-----	---------------	-----------	-------	---------------	-----------------	------------	--------------	-------

BID ITEM = 551 CLIENT# = 551 Land Item SCHEDULE: 1 100
Description = MAINTENANCE HOLE, TYPE 204A Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

551.01 MAINTENANCE HOLE, TYPE 204A Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		5.30 CH	Prod:	5.3000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CPSMH204A	TYPE 204A MAINTENAN	1.00	1.00 EA	1,796.000		1,796			1,796
2CPSZ230	TYPE 230 CASTING SEW	1.00	1.00 EA	785.000		785			785
3DEDU02C	Concrete Trucking and Du	1.00	5.00 TCY	29.000			145		145
8EX135A	135 Excavator W/Attach	1.00	5.30 HR	68.251				362	362
8EX200	200 Excavator	1.00	5.30 HR	78.000				413	413
8LO950	950 Loader	1.00	5.30 HR	81.500				432	432
FOCI	Civil Forman	1.00	5.30 MH	77.060	533				533
LAP	Labor Underground Water	2.00	10.60 MH	53.880	753				753
OPE	Operator - Excavator	1.00	5.30 MH	74.560	516				516
OPL	Operator - Loader	1.00	5.30 MH	74.560	516				516
\$6,252.04	26.5000 MH/EA		26.50 MH	[1946.86]	2,319	2,581	145	1,207	6,252

551.02 CHANAL MH Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew		3.00 CH	Prod:	3.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	3.00 CY	121.500		402			402
CEJ	Cement Mason	5.00	15.00 MH	64.980	1,278				1,278
FOCO	Concrete Forman	1.00	3.00 MH	68.980	271				271
\$1,950.76	18.0000 MH/EA		18.00 MH	[1299.8]	1,549	402			1,951

====> **Item Totals: 551 - MAINTENANCE HOLE, TYPE 204A**
 \$8,202.80 44.5000 MH/EA 44.50 MH [3246.66] 3,868 2,983 145 1,207 **8,203**
 8,202.800 1 EA 3,867.89 2,982.86 145.00 1,207.05 8,202.80

BID ITEM = 552 CLIENT# = 552 Land Item SCHEDULE: 1 100
Description = EXTRA DEPTH, TYPE 204A MAINTENANCE HOLE Unit = VF Takeoff Quan: 3.000 Engr Quan: 3.000

552.01 EXTRA DEPTH, TYPE 204A MAINTENANCE HOL Quan: 3.00 VF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		3.00 CH	Prod:	3.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CPSED204	EXTRA DEPTH MH 204	1.00	3.00 LF	1.000		3			3
8EX135A	135 Excavator W/Attach	1.00	3.00 HR	68.251			205		205
8EX200	200 Excavator	1.00	3.00 HR	78.000			234		234
8LO950	950 Loader	1.00	3.00 HR	81.500			244		244
FOCI	Civil Forman	1.00	3.00 MH	77.060	302				302
LAP	Labor Underground Water	2.00	6.00 MH	53.880	426				426
OPE	Operator - Excavator	1.00	3.00 MH	74.560	292				292
OPL	Operator - Loader	1.00	3.00 MH	74.560	292				292
\$1,998.88	5.0000 MH/VF		15.00 MH	[367.337]	1,313	3		683	1,999

====> **Item Totals: 552 - EXTRA DEPTH, TYPE 204A MAINTENANCE HOLE**
 \$1,998.88 5.0000 MH/VF 15.00 MH [367.337] 1,313 3 683 **1,999**
 666.293 3 VF 437.55 1.00 227.74 666.29

BID ITEM = 553 CLIENT# = 553 Land Item SCHEDULE: 1 100
Description = TEMPORARY WATER MAINS AND SERVICES Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

553.01 STAGE 2 TEMP WATER MAIN Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 553	CLIENT# = 553		Land Item	SCHEDULE: 1 100						
Description =	TEMPORARY WATER MAINS AND SERVICES		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
UNS	Underground Utilities 4 Man		74.00 CH	Prod:	74.0000 CH	Lab Pcs:		4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	74.00 HR	51.051				3,778		3,778
8EX100	100 Excavator	1.00	74.00 HR	52.300				3,870		3,870
FOCI	Civil Forman	1.00	74.00 MH	77.060	7,448					7,448
LAP	Labor Underground Water	1.00	74.00 MH	53.880	5,254					5,254
OPB	Operator - Backhoe	1.00	74.00 MH	74.560	7,211					7,211
OPE	Operator - Excavator	1.00	74.00 MH	74.560	7,211					7,211
\$34,772.54	296.0000 MH/LS		296.00 MH	[22796.87]	27,125			7,648		34,773
553.02	STAGE 3 TEMP WATER MAIN		Quan:	1.00 LS	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
UNS	Underground Utilities 4 Man		60.00 CH	Prod:	60.0000 CH	Lab Pcs:		4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	60.00 HR	51.051				3,063		3,063
8EX100	100 Excavator	1.00	60.00 HR	52.300				3,138		3,138
FOCI	Civil Forman	1.00	60.00 MH	77.060	6,039					6,039
LAP	Labor Underground Water	1.00	60.00 MH	53.880	4,260					4,260
OPB	Operator - Backhoe	1.00	60.00 MH	74.560	5,847					5,847
OPE	Operator - Excavator	1.00	60.00 MH	74.560	5,847					5,847
\$28,193.96	240.0000 MH/LS		240.00 MH	[18483.96]	21,993			6,201		28,194
553.03	STAGE 4 TEMP WATER MAIN		Quan:	1.00 LS	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
UNS	Underground Utilities 4 Man		32.00 CH	Prod:	32.0000 CH	Lab Pcs:		4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	32.00 HR	51.051				1,634		1,634
8EX100	100 Excavator	1.00	32.00 HR	52.300				1,674		1,674
FOCI	Civil Forman	1.00	32.00 MH	77.060	3,221					3,221
LAP	Labor Underground Water	1.00	32.00 MH	53.880	2,272					2,272
OPB	Operator - Backhoe	1.00	32.00 MH	74.560	3,118					3,118
OPE	Operator - Excavator	1.00	32.00 MH	74.560	3,118					3,118
\$15,036.77	128.0000 MH/LS		128.00 MH	[9858.11]	11,730			3,307		15,037
553.04	STAGE 5 TEMP WATER MAIN		Quan:	1.00 LS	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
UNS	Underground Utilities 4 Man		60.00 CH	Prod:	60.0000 CH	Lab Pcs:		4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	60.00 HR	51.051				3,063		3,063
8EX100	100 Excavator	1.00	60.00 HR	52.300				3,138		3,138
FOCI	Civil Forman	1.00	60.00 MH	77.060	6,039					6,039
LAP	Labor Underground Water	1.00	60.00 MH	53.880	4,260					4,260
OPB	Operator - Backhoe	1.00	60.00 MH	74.560	5,847					5,847
OPE	Operator - Excavator	1.00	60.00 MH	74.560	5,847					5,847
\$28,193.96	240.0000 MH/LS		240.00 MH	[18483.96]	21,993			6,201		28,194
553.05	STAGE 6 TEMP WATER MAIN		Quan:	1.00 LS	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
UNS	Underground Utilities 4 Man		40.00 CH	Prod:	40.0000 CH	Lab Pcs:		4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	40.00 HR	51.051				2,042		2,042
8EX100	100 Excavator	1.00	40.00 HR	52.300				2,092		2,092
FOCI	Civil Forman	1.00	40.00 MH	77.060	4,026					4,026
LAP	Labor Underground Water	1.00	40.00 MH	53.880	2,840					2,840
OPB	Operator - Backhoe	1.00	40.00 MH	74.560	3,898					3,898
OPE	Operator - Excavator	1.00	40.00 MH	74.560	3,898					3,898
\$18,795.98	160.0000 MH/LS		160.00 MH	[12322.64]	14,662			4,134		18,796
553.06	STAGE 9 TEMP WATER MAIN		Quan:	1.00 LS	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
UNS	Underground Utilities 4 Man		56.00 CH	Prod:	56.0000 CH	Lab Pcs:		4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	56.00 HR	51.051				2,859		2,859
8EX100	100 Excavator	1.00	56.00 HR	52.300				2,929		2,929
FOCI	Civil Forman	1.00	56.00 MH	77.060	5,636					5,636

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----	------------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 553 CLIENT# = 553 Land Item SCHEDULE: 1 100
Description = TEMPORARY WATER MAINS AND SERVICES Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

LAP	Labor Underground Water	1.00	56.00 MH	53.880	3,976					3,976
OPB	Operator - Backhoe	1.00	56.00 MH	74.560	5,457					5,457
OPE	Operator - Excavator	1.00	56.00 MH	74.560	5,457					5,457
\$26,314.35	224.0000 MH/LS		224.00 MH	[17251.71]	20,527			5,788		26,314

553.07 TEMPORARY WATERMAIN MATERIALS Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

2BI553PIPE	BID ITEM 553 PIPE	1.00	1.00 LS	45,000.000		45,000				45,000
3FUSIONMACHI	FUSHION MACHINE	1.00	1.00 LS	5,000.000			5,000			5,000
3TEMPWATMIS	MISS TEMP WATER PAR	1.00	1.00 LS	10,000.000			10,000			10,000
\$60,000.00				[]		45,000	15,000			60,000

=====> **Item Totals: 553 - TEMPORARY WATER MAINS AND SERVICES**

\$211,307.56	1,288.0000 MH/LS		1,288.00 MH	[99197.25]	118,029	45,000	15,000	33,279		211,308
211,307.560	1 LS				118,028.57	45,000.00	15,000.00	33,278.99		211,307.56

BID ITEM = 554 CLIENT# = 554 Land Item SCHEDULE: 1 100
Description = PIPE, WM, D.I., CL 52, 12 IN, RJ, INCL. Unit = LF Takeoff Quan: 3,964.000 Engr Quan: 3,964.000

554.01 PIPE, WM, D.I., CL 52, 12 IN, RJ, INCL. Quan: 3,964.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		481.00 CH	Prod: 481.0000 CH		Lab Pcs: 5.00		Eqp Pcs: 3.00		
2BI554PIPE	BID ITEM 554 PIPE	1.00	1.00 LS	328,379.280	328,379					328,379
2JB12IN	JOINT BONDING 12 IN PI	1.00	1.00 LS	29,930.000	29,930					29,930
8EX135A	135 Excavator W/Attach	1.00	481.00 HR	68.251			32,829			32,829
8EX200	200 Excavator	1.00	481.00 HR	78.000			37,518			37,518
8LO950	950 Loader	1.00	481.00 HR	81.500			39,201			39,201
FOCI	Civil Forman	1.00	481.00 MH	77.060	48,411					48,411
LAP	Labor Underground Water	2.00	962.00 MH	53.880	68,303					68,303
OPE	Operator - Excavator	1.00	481.00 MH	74.560	46,873					46,873
OPL	Operator - Loader	1.00	481.00 MH	74.560	46,873					46,873
\$678,318.70	0.6067 MH/ LF		2,405.00 MH	[44.573]	210,461	358,309		109,548		678,319

554.02 FLUSHING AND TESTING Quan: 9.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		144.00 CH	Prod: 144.0000 CH		Lab Pcs: 5.00		Eqp Pcs: 3.00		
3TESTMAT	TESTING MATERIAL	1.00	1.00 LS	5,000.000	5,000					5,000
8EX135A	135 Excavator W/Attach	1.00	144.00 HR	68.251			9,828			9,828
8EX200	200 Excavator	1.00	144.00 HR	78.000			11,232			11,232
8LO950	950 Loader	1.00	144.00 HR	81.500			11,736			11,736
FOCI	Civil Forman	1.00	144.00 MH	77.060	14,493					14,493
LAP	Labor Underground Water	2.00	288.00 MH	53.880	20,448					20,448
OPE	Operator - Excavator	1.00	144.00 MH	74.560	14,033					14,033
OPL	Operator - Loader	1.00	144.00 MH	74.560	14,033					14,033
\$100,803.23	80.0000 MH/EA		720.00 MH	[5877.342]	63,007		5,000	32,796		100,803

=====> **Item Totals: 554 - PIPE, WM, D.I., CL 52, 12 IN, RJ, INCL.**

\$779,121.93	0.7883 MH/ LF		3,125.00 MH	[57.917]	273,468	358,309	5,000	142,344		779,122
196.549	3964 LF				68.99	90.39	1.26	35.91		196.55

BID ITEM = 555 CLIENT# = 555 Land Item SCHEDULE: 1 100
Description = PIPE, WM, D.I., CL 52, 16 IN, RJ, INCL. Unit = LF Takeoff Quan: 1,000.000 Engr Quan: 1,000.000

Activity	Desc	Quantity	Unit	Unit Cost	Labor	Perm	Constr	Equip	Sub-	Total
Resource	Pcs			Cost		Material	Matl/Exp	Ment	Contract	
BID ITEM	= 555	CLIENT# = 555	Land Item	SCHEDULE:	1	100				
Description =	PIPE, WM, D.I., CL 52, 16 IN, RJ, INCL.		Unit =	LF	Takeoff	Quan:	1,000.000	Engr	Quan:	1,000.000
555.01	PIPE, WM, D.I., CL 52, 16 IN, RJ, INCL.		Quan:	1,000.00	LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
UNM	Underground Utilities 6 Man		140.00	CH	Prod:	140.0000	CH	Lab Pcs:	5.00	Eqp Pcs: 3.00
2BI555PIPE	BID ITEM 555 PIPE	1.00	1.00	LS	123,334.650		123,335			123,335
2JB16IN	JOINT BONDING 16 INC	1.00	1.00	LS	10,000.000		10,000			10,000
8EX135A	135 Excavator W/Attach	1.00	140.00	HR	68.251			9,555		9,555
8EX200	200 Excavator	1.00	140.00	HR	78.000			10,920		10,920
8LO950	950 Loader	1.00	140.00	HR	81.500			11,410		11,410
FOCI	Civil Forman	1.00	140.00	MH	77.060	14,091				14,091
LAP	Labor Underground Water	2.00	280.00	MH	53.880	19,880				19,880
OPE	Operator - Excavator	1.00	140.00	MH	74.560	13,643				13,643
OPL	Operator - Loader	1.00	140.00	MH	74.560	13,643				13,643
\$226,476.68	0.7000 MH/ LF		700.00	MH	[51.427]	61,257	133,335		31,885	226,477
555.02	FLUSHING AND TESTING		Quan:	1.00	EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
UNM	Underground Utilities 6 Man		16.00	CH	Prod:	16.0000	CH	Lab Pcs:	5.00	Eqp Pcs: 3.00
8EX135A	135 Excavator W/Attach	1.00	16.00	HR	68.251			1,092		1,092
8EX200	200 Excavator	1.00	16.00	HR	78.000			1,248		1,248
8LO950	950 Loader	1.00	16.00	HR	81.500			1,304		1,304
FOCI	Civil Forman	1.00	16.00	MH	77.060	1,610				1,610
LAP	Labor Underground Water	2.00	32.00	MH	53.880	2,272				2,272
OPE	Operator - Excavator	1.00	16.00	MH	74.560	1,559				1,559
OPL	Operator - Loader	1.00	16.00	MH	74.560	1,559				1,559
\$10,644.79	80.0000 MH/EA		80.00	MH	[5877.36]	7,001		3,644		10,645
====>	Item Totals:	555	- PIPE, WM, D.I., CL 52, 16 IN, RJ, INCL.							
\$237,121.47	0.7800 MH/ LF		780.00	MH	[57.304]	68,258	133,335		35,529	237,121
237.121	1000 LF					68.26	133.33		35.53	237.12

BID ITEM	=	556	CLIENT# = 556	Land Item	SCHEDULE:	1	100	
Description =		PIPE, WM, D.I., CL 52, 20 IN, RJ, INCL.		Unit =	LF	Takeoff Quan:	319.000	Engr Quan: 319.000

556.01	PIPE, WM, D.I., CL 52, 20 IN, RJ, INCL.	Quan:	319.00	LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
--------	---	-------	--------	----	-----------	-------	------	-----	-----	-------

<u>UNM</u>	Unerground Utilities 6 Man			48.00	CH	Prod:	48.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI556PIPE	BID ITEM 556 PIPE	1.00	1.00	LS		77,793.580		77,794				77,794
2JB20IN	JOINT BONDING 20 IN PI	1.00	1.00	LS		1,216.000		1,216				1,216
8EX135A	135 Excavator W/Attach	1.00	48.00	HR		68.251				3,276		3,276
8EX200	200 Excavator	1.00	48.00	HR		78.000				3,744		3,744
8LO950	950 Loader	1.00	48.00	HR		81.500				3,912		3,912
FOCI	Civil Forman	1.00	48.00	MH		77.060	4,831					4,831
LAP	Labor Underground Water	2.00	96.00	MH		53.880	6,816					6,816
OPE	Operator - Excavator	1.00	48.00	MH		74.560	4,678					4,678
OPL	Operator - Loader	1.00	48.00	MH		74.560	4,678					4,678
\$110,943.99	0.7523 MH/ LF		240.00	MH		[55.273]	21,002	79,010		10,932		110,944

556.02	FLUSHING AND TESTING 20 IN	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
--------	----------------------------	-------	---------	-----------	-------	------	-----	-----	-------

<u>UNM</u>	Unerground Utilities 6 Man		16.00	CH	Prod:	16.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
8EX135A	135 Excavator W/Attach	1.00	16.00	HR	68.251				1,092		1,092
8EX200	200 Excavator	1.00	16.00	HR	78.000				1,248		1,248
8LO950	950 Loader	1.00	16.00	HR	81.500				1,304		1,304
FOCI	Civil Forman	1.00	16.00	MH	77.060	1,610					1,610
LAP	Labor Undergound Water	2.00	32.00	MH	53.880	2,272					2,272

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 556	CLIENT# = 556		Land Item	SCHEDULE: 1 100						
Description =	PIPE, WM, D.I., CL 52, 20 IN, RJ, INCL.		Unit =	LF	Takeoff Quan:		319.000	Engr Quan:		319.000
OPE	Operator - Excavator	1.00	16.00 MH	74.560	1,559					1,559
OPL	Operator - Loader	1.00	16.00 MH	74.560	1,559					1,559
\$10,644.79	80.0000 MH/EA		80.00 MH	[5877.36]	7,001			3,644		10,645
====> Item Totals: 556 - PIPE, WM, D.I., CL 52, 20 IN, RJ, INCL.										
\$121,588.78	1.0031 MH/ LF		320.00 MH	[73.697]	28,003	79,010		14,576		121,589
381.156	319 LF				87.78	247.68		45.69		381.16
BID ITEM = 557	CLIENT# = 557		Land Item	SCHEDULE: 1 100						
Description =	BEDDING, WATER MAIN, CL B, 8 IN PIPE		Unit =	LF	Takeoff Quan:		318.000	Engr Quan:		318.000
557.01	BEDDING, WATER MAIN, CL B, 8 IN PIPE		Quan:	318.00 LF	Hrs/Shift: 10.00	Cal: 510	WC: WAAVG			
2AGS07	SEATTLE TYPE 7	1.00	233.00 TON	29.750		6,932				6,932
3DEDU02D	Dirt Trucking and Dump	1.00	170.00 TCY	24.500			4,165			4,165
\$11,096.75				[]		6,932	4,165			11,097
====> Item Totals: 557 - BEDDING, WATER MAIN, CL B, 8 IN PIPE										
\$11,096.75				[]		6,932	4,165			11,097
34.895	318 LF					21.80	13.10			34.90
BID ITEM = 558	CLIENT# = 558		Land Item	SCHEDULE: 1 100						
Description =	BEDDING, WATER MAIN, CL B, 12 IN PIPE		Unit =	LF	Takeoff Quan:		5,128.000	Engr Quan:		5,128.000
558.01	BEDDING, WATER MAIN, CL B, 12 IN PIPE		Quan:	5,128.00 LF	Hrs/Shift: 10.00	Cal: 510	WC: WAAVG			
2AGS07	SEATTLE TYPE 7	1.00	3,621.00 TON	29.750		107,725				107,725
3DEDU02D	Dirt Trucking and Dump	1.00	2,735.00 TCY	24.500			67,008			67,008
\$174,732.25				[]		107,725	67,008			174,732
====> Item Totals: 558 - BEDDING, WATER MAIN, CL B, 12 IN PIPE										
\$174,732.25				[]		107,725	67,008			174,732
34.074	5128 LF					21.01	13.07			34.07
BID ITEM = 559	CLIENT# = 559		Land Item	SCHEDULE: 1 100						
Description =	BEDDING, WATERMAIN, CL B, 16 IN PIPE		Unit =	LF	Takeoff Quan:		1,000.000	Engr Quan:		1,000.000
559.01	BEDDING, WATERMAIN, CL B, 16 IN PIPE		Quan:	1,000.00 LF	Hrs/Shift: 10.00	Cal: 510	WC: WAAVG			
2AGS07	SEATTLE TYPE 7	1.00	668.00 TON	29.750		19,873				19,873
3DEDU02D	Dirt Trucking and Dump	1.00	532.00 TCY	24.500			13,034			13,034
\$32,907.00				[]		19,873	13,034			32,907
====> Item Totals: 559 - BEDDING, WATERMAIN, CL B, 16 IN PIPE										
\$32,907.00				[]		19,873	13,034			32,907
32.907	1000 LF					19.87	13.03			32.91

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	--------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 560 CLIENT# = 560 Land Item SCHEDULE: 1 100
Description = BEDDING, WATERMAIN, CL B, 20 IN PIPE Unit = LF Takeoff Quan: 319.000 Engr Quan: 319.000

560.01 BEDDING, WATERMAIN, CL B, 20 IN PIPE Quan: 319.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

2AGS07	SEATTLE TYPE 7	1.00	324.00 TON	29.750		9,639				9,639
3DEDU02D	Dirt Trucking and Dump	1.00	259.00 TCY	24.500			6,346			6,346
\$15,984.50				[]		9,639	6,346			15,985

====> **Item Totals: 560 - BEDDING, WATERMAIN, CL B, 20 IN PIPE**
\$15,984.50 [] 9,639 6,346 **15,985**
50.108 319 LF 30.22 19.89 50.11

BID ITEM = 561 CLIENT# = 561 Land Item SCHEDULE: 1 100
Description = BLOCKING, CEMENT CONCRETE Unit = CY Takeoff Quan: 63.000 Engr Quan: 63.000

561.01 BLOCKING, CEMENT CONCRETE Quan: 63.00 CY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

UNM	Underground Utilities 6 Man	50.00	CH	Prod: 50.0000 CH	Lab Pcs: 5.00	Eqp Pcs: 3.00
2CR040	4000LB READY MIX	1.25	78.75 CY	121.150	9,541	9,541
2TBBOLT	THRUST BLOCK BOLTS	1.00	4.00 EA	800.000	3,200	3,200
8EX135A	135 Excavator W/Attach	1.00	50.00 HR	68.251		3,413
8EX200	200 Excavator	1.00	50.00 HR	78.000		3,900
8LO950	950 Loader	1.00	50.00 HR	81.500		4,075
FOCI	Civil Forman	1.00	50.00 MH	77.060	5,032	5,032
LAP	Labor Underground Water	2.00	100.00 MH	53.880	7,100	7,100
OPE	Operator - Excavator	1.00	50.00 MH	74.560	4,873	4,873
OPL	Operator - Loader	1.00	50.00 MH	74.560	4,873	4,873
\$46,005.57	3.9682 MH/CY	250.00	MH	[291.535]	21,877 12,741	11,388 46,006

====> **Item Totals: 561 - BLOCKING, CEMENT CONCRETE**
\$46,005.57 3.9682 MH/CY 250.00 MH [291.535] 21,877 12,741 11,388 **46,006**
730.247 63 CY 347.26 202.23 180.75 730.25

BID ITEM = 562 CLIENT# = 562 Land Item SCHEDULE: 1 100
Description = STATION, ELECTROLYSIS TEST Unit = EA Takeoff Quan: 31.000 Engr Quan: 31.000

562.01 STATION, ELECTROLYSIS TEST Quan: 31.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

UNM	Underground Utilities 6 Man	62.00	CH	Prod: 62.0000 CH	Lab Pcs: 5.00	Eqp Pcs: 3.00
2STELTEST	STATION ELECTROLOSI	1.00	31.00 EA	1,483.620	45,992	45,992
3CERTTEST	CERTIFIED TESTER	1.00	31.00 EA	2,414.000	74,834	74,834
8EX135A	135 Excavator W/Attach	1.00	62.00 HR	68.251		4,232
8EX200	200 Excavator	1.00	62.00 HR	78.000		4,836
8LO950	950 Loader	1.00	62.00 HR	81.500		5,053
FOCI	Civil Forman	1.00	62.00 MH	77.060	6,240	6,240
LAP	Labor Underground Water	2.00	124.00 MH	53.880	8,804	8,804
OPE	Operator - Excavator	1.00	62.00 MH	74.560	6,042	6,042
OPL	Operator - Loader	1.00	62.00 MH	74.560	6,042	6,042
\$162,074.82	10.0000 MH/EA	310.00	MH	[734.668]	27,128 45,992 74,834	14,121 162,075

====> **Item Totals: 562 - STATION, ELECTROLYSIS TEST**
\$162,074.82 10.0000 MH/EA 310.00 MH [734.668] 27,128 45,992 74,834 14,121 **162,075**
5,228.220 31 EA 875.10 1,483.62 2,414.00 455.50 5,228.22

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
Resource	Pcs									
BID ITEM = 563	CLIENT# = 563		Land Item	SCHEDULE: 1	100					
Description =	SACRIFICIAL ANODE BONDED TO PIPE		Unit =	EA	Takeoff Quan:		244.000	Engr Quan:		244.000
563.01	SACRIFICIAL ANODE BONDED TO PIPE		Quan:	244.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
UNM	Underground Utilities 6 Man		30.00 CH	Prod:	30.0000 CH	Lab Pcs:	5.00	Eqp Pcs:		3.00
2ANOD	ANODES	1.00	244.00 EA	253.000	61,732					61,732
8EX135A	135 Excavator W/Attach	1.00	30.00 HR	68.251				2,048		2,048
8EX200	200 Excavator	1.00	30.00 HR	78.000				2,340		2,340
8LO950	950 Loader	1.00	30.00 HR	81.500				2,445		2,445
FOCI	Civil Forman	1.00	30.00 MH	77.060	3,019					3,019
LAP	Labor Underground Water	2.00	60.00 MH	53.880	4,260					4,260
OPE	Operator - Excavator	1.00	30.00 MH	74.560	2,924					2,924
OPL	Operator - Loader	1.00	30.00 MH	74.560	2,924					2,924
\$81,691.00	0.6147 MH/EA		150.00 MH	[45.164]	13,126	61,732		6,833		81,691
====>	Item Totals:	563	- SACRIFICIAL ANODE BONDED TO PIPE							
\$81,691.00	0.6147 MH/EA		150.00 MH	[45.164]	13,126	61,732		6,833		81,691
334.799	244 EA				53.80	253.00		28.00		334.80

BID ITEM = **564** CLIENT# = 564 Land Item SCHEDULE: 1 100
Description = SUPPORT SPU WITH JOINT CLAMP EXISTING PI Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

264.01	JOINT CLAMP 1ST AND MADISON			Quan:	1.00 LS	Hrs/Shft:	8.00	Cal:	S08	WC: WAAVG
<u>EAS</u>	Earthwork 4 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
2AGS07	SEATTLE TYPE 7	1.00	10.00 TON	29.750	298				298	
2AGS17	SEATTLE TYPE 17	1.00	20.00 TON	25.750	515				515	
3VAC	VACTOR TRUCKS	1.00	1.00 LS	4,000.000		4,000			4,000	
4SAWC	Sawcutting	1.00	832.00 INFT	0.580				483	483	
8BA310A	418 Backhoe W/Attachme	1.00	8.00 HR	51.051				408	408	
8EX100	100 Excavator	1.00	8.00 HR	52.300				418	418	
FOCI	Civil Forman	1.00	8.00 MH	77.060	1,092				1,092	
LAG	General Laborer	2.00	16.00 MH	52.910	1,510				1,510	
OPE	Operator - Excavator	1.00	8.00 MH	74.560	1,057				1,057	
\$9,780.64	32.0000 MH/LS		32.00 MH	[3089.28]	3,659	813	4,000	827	483	9,781
264.02	JOINT CLAMP SPRING AND 8TH			Quan:	1.00 LS	Hrs/Shft:	8.00	Cal:	S08	WC: WAAVG
<u>EAS</u>	Earthwork 4 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
2AGS07	SEATTLE TYPE 7	1.00	10.00 TON	29.750	298				298	
2AGS17	SEATTLE TYPE 17	1.00	10.00 TON	25.750	258				258	
3VAC	VACTOR TRUCKS	1.00	1.00 LS	4,000.000		4,000			4,000	
8BA310A	418 Backhoe W/Attachme	1.00	8.00 HR	51.051				408	408	
8EX100	100 Excavator	1.00	8.00 HR	52.300				418	418	
FOCI	Civil Forman	1.00	8.00 MH	77.060	1,092				1,092	
LAG	General Laborer	2.00	16.00 MH	52.910	1,510				1,510	
OPE	Operator - Excavator	1.00	8.00 MH	74.560	1,057				1,057	
\$9,040.58	32.0000 MH/LS		32.00 MH	[3089.28]	3,659	555	4,000	827		9,041
264.03	JOINT CLAMP MADISON AND 5TH			Quan:	1.00 LS	Hrs/Shft:	8.00	Cal:	S08	WC: WAAVG
<u>EAS</u>	Earthwork 4 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
2AGS07	SEATTLE TYPE 7	1.00	10.00 TON	29.750	298				298	
2AGS17	SEATTLE TYPE 17	1.00	10.00 TON	25.750	258				258	
3VAC	VACTOR TRUCKS	1.00	1.00 LS	4,000.000		4,000			4,000	
8BA310A	418 Backhoe W/Attachme	1.00	8.00 HR	51.051				408	408	
8EX100	100 Excavator	1.00	8.00 HR	52.300				418	418	

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 564	CLIENT# = 564		Land Item	SCHEDULE: 1 100						
Description =	SUPPORT SPU WITH JOINT CLAMP EXISTING PI		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
FOCI	Civil Forman	1.00	8.00 MH	77.060	1,092					1,092
LAG	General Laborer	2.00	16.00 MH	52.910	1,510					1,510
OPE	Operator - Excavator	1.00	8.00 MH	74.560	1,057					1,057
\$9,040.58	32.0000 MH/LS		32.00 MH	[3089.28]	3,659	555	4,000	827		9,041
====> Item Totals: 564 - SUPPORT SPU WITH JOINT CLAMP EXISTING PI										
\$27,861.80	96.0000 MH/LS		96.00 MH	[9267.84]	10,976	1,923	12,000	2,480	483	27,862
27,861.800	1 LS				10,976.34	1,922.50	12,000.00	2,480.40	482.56	27,861.80

BID ITEM = 565	CLIENT# = 565		Land Item	SCHEDULE: 1 100						
Description =	SUPPORT SPU WITH CUT, CAP, AND CONNECT		Unit =	EA	Takeoff Quan:		44.000	Engr Quan:		44.000
565.01	SUPPORT SPU WITH CUT, CAP, AND CONNECT		Quan:	44.00 EA	Hrs/Shft:	12.00	Cal: 512	WC: WAAVG		
UNS	Underground Utilities 4 Man		352.00 CH	Prod: 352.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00		
2AGS07	SEATTLE TYPE 7	1.00	195.00 TON	29.750	5,801			5,801		
2AGS17	SEATTLE TYPE 17	1.00	443.00 TON	25.750	11,407			11,407		
2BI565PIPE	BID ITEM 565 P@110.25	1.00	1.00 LS	25,000.000	27,563			27,563		
3DEDU02D	Dirt Trucking and Dump	1.00	450.00 TCY	24.500		11,025		11,025		
8BA310A	418 Backhoe W/Attachme	1.00	352.00 HR	51.051			17,970	17,970		
8EX100	100 Excavator	1.00	352.00 HR	52.300			18,410	18,410		
FOCI	Civil Forman	1.00	352.00 MH	77.060	40,159			40,159		
LAP	Labor Underground Water	1.00	352.00 MH	53.880	28,300			28,300		
OPB	Operator - Backhoe	1.00	352.00 MH	74.560	38,880			38,880		
OPE	Operator - Excavator	1.00	352.00 MH	74.560	38,880			38,880		
\$238,393.59	32.0000 MH/EA		1,408.00 MH	[2800.6]	146,218	44,771	11,025	36,380		238,394
====> Item Totals: 565 - SUPPORT SPU WITH CUT, CAP, AND CONNECT										
\$238,393.59	32.0000 MH/EA		1,408.00 MH	[2800.6]	146,218	44,771	11,025	36,380		238,394
5,418.036	44 EA				3,323.14	1,017.52	250.57	826.81		5,418.04

BID ITEM = 566	CLIENT# = 566		Land Item	SCHEDULE: 1 100						
Description =	PIPE, WM, D.I. CL 53 MIN, 8 IN, RJ, POLY		Unit =	LF	Takeoff Quan:		318.000	Engr Quan:		318.000
566.01	PIPE, WM, D.I. CL 53 MIN, 8 IN, RJ, POLY		Quan:	318.00 LF	Hrs/Shft:	10.00	Cal: 610	WC: WAAVG		
UNM	Unerground Utilities 6 Man		32.00 CH	Prod: 32.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00		
2BI566PIPE	BID ITEM 566 PIPE	1.00	1.00 LS	19,022.220	19,022			19,022		
8EX135A	135 Excavator W/Attach	1.00	32.00 HR	68.251			2,184	2,184		
8EX200	200 Excavator	1.00	32.00 HR	78.000			2,496	2,496		
8LO950	950 Loader	1.00	32.00 HR	81.500			2,608	2,608		
FOCI	Civil Forman	1.00	32.00 MH	77.060	3,412			3,412		
LAP	Labor Underground Water	2.00	64.00 MH	53.880	4,811			4,811		
OPE	Operator - Excavator	1.00	32.00 MH	74.560	3,303			3,303		
OPL	Operator - Loader	1.00	32.00 MH	74.560	3,303			3,303		
\$41,140.54	0.5031 MH/LF		160.00 MH	[39.206]	14,830	19,022		7,288		41,141
====> Item Totals: 566 - PIPE, WM, D.I. CL 53 MIN, 8 IN, RJ, POLY										
\$41,140.54	0.5031 MH/LF		160.00 MH	[39.206]	14,830	19,022		7,288		41,141
129.373	318 LF				46.64	59.82		22.92		129.37

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract

BID ITEM = 567 CLIENT# = 567 Land Item SCHEDULE: 1 100
Description = PIPE, WM, D.I. CL 53 MIN, 12 IN, RJ, POL Unit = LF Takeoff Quan: 1,164.000 Engr Quan: 1,164.000

567.01 PIPE, WM, D.I. CL 53 MIN, 12 IN, RJ, POL Quan: 1,164.00 LF Hrs/Shift: 10.00 Cal: 610 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		127.00	CH	Prod:	127.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI567PIPE	BID ITEM 567 PIPE	1.00	1.00	LS	94,606.000		94,606				94,606
8EX135A	135 Excavator W/Attach	1.00	127.00	HR	68.251			8,668			8,668
8EX200	200 Excavator	1.00	127.00	HR	78.000			9,906			9,906
8LO950	950 Loader	1.00	127.00	HR	81.500			10,350			10,350
FOCI	Civil Forman	1.00	127.00	MH	77.060	13,541					13,541
LAP	Labor Underground Water	2.00	254.00	MH	53.880	19,096					19,096
OPE	Operator - Excavator	1.00	127.00	MH	74.560	13,111					13,111
OPL	Operator - Loader	1.00	127.00	MH	74.560	13,111					13,111
\$182,388.13	0.5455 MH/LF		635.00	MH	[42.509]	58,858	94,606		28,924		182,388

=====> **Item Totals: 567 - PIPE, WM, D.I. CL 53 MIN, 12 IN, RJ, POL**
\$182,388.13 0.5455 MH/LF 635.00 MH [42.509] 58,858 94,606 28,924 **182,388**
156.691 1164 LF 50.57 81.28 24.85 156.69

BID ITEM = 568 CLIENT# = 568 Land Item SCHEDULE: 1 100
Description = DAILY BLOCK, CEMENT CONCRETE, PRECAST Unit = EA Takeoff Quan: 7.000 Engr Quan: 7.000

568.01 DAILY BLOCK, CEMENT CONCRETE, PRECAST Quan: 7.00 EA Hrs/Shift: 10.00 Cal: 610 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		16.00	CH	Prod:	16.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2AGS02	SEATTLE TYPE 2	1.00	70.00	TON	29.750		2,083				2,083
2CPSDAILY	DAILY BLOCK	1.00	7.00	EA	750.000		5,250				5,250
8EX135A	135 Excavator W/Attach	1.00	16.00	HR	68.251			1,092			1,092
8EX200	200 Excavator	1.00	16.00	HR	78.000			1,248			1,248
8LO950	950 Loader	1.00	16.00	HR	81.500			1,304			1,304
FOCI	Civil Forman	1.00	16.00	MH	77.060	1,706					1,706
LAP	Labor Underground Water	2.00	32.00	MH	53.880	2,406					2,406
OPE	Operator - Excavator	1.00	16.00	MH	74.560	1,652					1,652
OPL	Operator - Loader	1.00	16.00	MH	74.560	1,652					1,652
\$18,391.65	11.4285 MH/EA		80.00	MH	[890.533]	7,415	7,333		3,644		18,392

=====> **Item Totals: 568 - DAILY BLOCK, CEMENT CONCRETE, PRECAST**
\$18,391.65 11.4285 MH/EA 80.00 MH [890.533] 7,415 7,333 3,644 **18,392**
2,627.379 7 EA 1,059.31 1,047.50 520.57 2,627.38

BID ITEM = 569 CLIENT# = 569 Land Item SCHEDULE: 1 100
Description = VALVE, GATE, 4 IN Unit = EA Takeoff Quan: 8.000 Engr Quan: 8.000

569.01 VALVE, GATE, 4 IN Quan: 8.00 EA Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		8.00	CH	Prod:	8.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI569PIPE	BID ITEM 569 PIPE	1.00	1.00	LS	9,165.040		9,165				9,165
8EX135A	135 Excavator W/Attach	1.00	8.00	HR	68.251			546			546
8EX200	200 Excavator	1.00	8.00	HR	78.000			624			624
8LO950	950 Loader	1.00	8.00	HR	81.500			652			652
FOCI	Civil Forman	1.00	8.00	MH	77.060	805					805
LAP	Labor Underground Water	2.00	16.00	MH	53.880	1,136					1,136
OPE	Operator - Excavator	1.00	8.00	MH	74.560	780					780
OPL	Operator - Loader	1.00	8.00	MH	74.560	780					780

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 569	CLIENT# = 569									
Description =	VALVE, GATE, 4 IN			Land Item Unit =	SCHEDULE: 1 100					
					EA Takeoff Quan:		8.000	Engr Quan:		8.000
\$14,487.44	5.0000 MH/EA	40.00 MH		[367.335]	3,500	9,165		1,822		14,487
====> Item Totals: 569 - VALVE, GATE, 4 IN										
\$14,487.44	5.0000 MH/EA	40.00 MH		[367.335]	3,500	9,165		1,822		14,487
1,810.930	8 EA				437.55	1,145.63		227.75		1,810.93

BID ITEM = 570	CLIENT# = 570									
Description =	VALVE, GATE, 6 IN			Land Item Unit =	SCHEDULE: 1 100					
					EA Takeoff Quan:		31.000	Engr Quan:		31.000
570.01	VALVE, GATE, 6 IN			Quan:	31.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG		
UNM	Underground Utilities 6 Man		31.00 CH	Prod:	31.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI570PIPE	BID ITEM 570 PIPE	1.00	1.00 LS	45,642.230	45,642					45,642
8EX135A	135 Excavator W/Attach	1.00	31.00 HR	68.251			2,116			2,116
8EX200	200 Excavator	1.00	31.00 HR	78.000			2,418			2,418
8LO950	950 Loader	1.00	31.00 HR	81.500			2,526			2,526
FOCI	Civil Forman	1.00	31.00 MH	77.060	3,120					3,120
LAP	Labor Underground Water	2.00	62.00 MH	53.880	4,402					4,402
OPE	Operator - Excavator	1.00	31.00 MH	74.560	3,021					3,021
OPL	Operator - Loader	1.00	31.00 MH	74.560	3,021					3,021
\$66,266.52	5.0000 MH/EA	155.00 MH		[367.335]	13,564	45,642		7,060		66,267
====> Item Totals: 570 - VALVE, GATE, 6 IN										
\$66,266.52	5.0000 MH/EA	155.00 MH		[367.335]	13,564	45,642		7,060		66,267
2,137.630	31 EA				437.55	1,472.33		227.75		2,137.63

BID ITEM = 571	CLIENT# = 571									
Description =	VALVE, GATE, 8 IN			Land Item Unit =	SCHEDULE: 1 100					
					EA Takeoff Quan:		5.000	Engr Quan:		5.000
571.01	VALVE, GATE, 8 IN			Quan:	5.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG		
UNM	Underground Utilities 6 Man		5.00 CH	Prod:	5.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI571PIPE	BID ITEM 571 PIPE	1.00	1.00 LS	14,639.780	14,640					14,640
8EX135A	135 Excavator W/Attach	1.00	5.00 HR	68.251			341			341
8EX200	200 Excavator	1.00	5.00 HR	78.000			390			390
8LO950	950 Loader	1.00	5.00 HR	81.500			407			407
FOCI	Civil Forman	1.00	5.00 MH	77.060	503					503
LAP	Labor Underground Water	2.00	10.00 MH	53.880	710					710
OPE	Operator - Excavator	1.00	5.00 MH	74.560	487					487
OPL	Operator - Loader	1.00	5.00 MH	74.560	487					487
\$17,966.27	5.0000 MH/EA	25.00 MH		[367.334]	2,188	14,640		1,139		17,966
====> Item Totals: 571 - VALVE, GATE, 8 IN										
\$17,966.27	5.0000 MH/EA	25.00 MH		[367.334]	2,188	14,640		1,139		17,966
3,593.254	5 EA				437.55	2,927.96		227.75		3,593.25

BID ITEM = 572	CLIENT# = 572									
Description =	VALVE, GATE, 12 IN			Land Item Unit =	SCHEDULE: 1 100					
					EA Takeoff Quan:		26.000	Engr Quan:		26.000
572.01	VALVE, GATE, 12 IN			Quan:	26.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG		

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 572 CLIENT# = 572									
Description =	VALVE, GATE, 12 IN		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	26.000	Engr Quan:	26.000
UNM	Underground Utilities 6 Man	26.00	CH	Prod: 26.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI572PIPE	BID ITEM 572 PIPE	1.00	1.00 LS	127,497.880	127,498				127,498
8EX135A	135 Excavator W/Attach	1.00	26.00 HR	68.251		1,775			1,775
8EX200	200 Excavator	1.00	26.00 HR	78.000		2,028			2,028
8LO950	950 Loader	1.00	26.00 HR	81.500		2,119			2,119
FOCI	Civil Forman	1.00	26.00 MH	77.060	2,617				2,617
LAP	Labor Underground Water	2.00	52.00 MH	53.880	3,692				3,692
OPE	Operator - Excavator	1.00	26.00 MH	74.560	2,534				2,534
OPL	Operator - Loader	1.00	26.00 MH	74.560	2,534				2,534
\$144,795.68	5.0000 MH/EA	130.00	MH	[367.335]	11,376	127,498	5,922		144,796
=====> Item Totals: 572 - VALVE, GATE, 12 IN									
\$144,795.68	5.0000 MH/EA	130.00	MH	[367.335]	11,376	127,498	5,922		144,796
5,569.065	26 EA				437.55	4,903.76	227.75		5,569.06

BID ITEM = 573 CLIENT# = 573									
Description =	VALVE, BUTTERFLY, 16 IN		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	3.000	Engr Quan:	3.000
573.01	VALVE, BUTTERFLY, 16 IN		Quan:	3.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
UNM	Underground Utilities 6 Man	6.00	CH	Prod: 6.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI573PIPE	BID ITEM 573 PIPE	1.00	3.00 EA	16,257.300	48,772				48,772
8EX135A	135 Excavator W/Attach	1.00	6.00 HR	68.251		409			409
8EX200	200 Excavator	1.00	6.00 HR	78.000		468			468
8LO950	950 Loader	1.00	6.00 HR	81.500		489			489
FOCI	Civil Forman	1.00	6.00 MH	77.060	604				604
LAP	Labor Underground Water	2.00	12.00 MH	53.880	852				852
OPE	Operator - Excavator	1.00	6.00 MH	74.560	585				585
OPL	Operator - Loader	1.00	6.00 MH	74.560	585				585
\$52,763.69	10.0000 MH/EA	30.00	MH	[734.673]	2,625	48,772	1,366		52,764
=====> Item Totals: 573 - VALVE, BUTTERFLY, 16 IN									
\$52,763.69	10.0000 MH/EA	30.00	MH	[734.673]	2,625	48,772	1,366		52,764
17,587.897	3 EA				875.10	16,257.30	455.50		17,587.90

BID ITEM = 574 CLIENT# = 574									
Description =	VALVE, BUTTERFLY, 20 IN		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	2.000	Engr Quan:	2.000
574.01	VALVE, BUTTERFLY, 20 IN		Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
UNM	Underground Utilities 6 Man	4.00	CH	Prod: 4.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI574PIPE	BID ITEM 574 PIPE	1.00	1.00 LS	17,642.840	17,643				17,643
8EX135A	135 Excavator W/Attach	1.00	4.00 HR	68.251		273			273
8EX200	200 Excavator	1.00	4.00 HR	78.000		312			312
8LO950	950 Loader	1.00	4.00 HR	81.500		326			326
FOCI	Civil Forman	1.00	4.00 MH	77.060	403				403
LAP	Labor Underground Water	2.00	8.00 MH	53.880	568				568
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390				390
OPL	Operator - Loader	1.00	4.00 MH	74.560	390				390
\$20,304.03	10.0000 MH/EA	20.00	MH	[734.66]	1,750	17,643	911		20,304
=====> Item Totals: 574 - VALVE, BUTTERFLY, 20 IN									
\$20,304.03	10.0000 MH/EA	20.00	MH	[734.66]	1,750	17,643	911		20,304

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM	= 574	CLIENT# = 574	Land Item	SCHEDULE: 1 100						
Description =	VALVE, BUTTERFLY, 20 IN		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
10,152.015	2 EA				875.10	8,821.42		455.50		10,152.02

BID ITEM	= 575	CLIENT# = 575	Land Item	SCHEDULE: 1 100						
Description =	VALVE BOX, CAST IRON		Unit =	EA	Takeoff Quan:		70.000	Engr Quan:		70.000

575.01 VALVE BOX, CAST IRON Quan: 70.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

2BI575PIPE	BID ITEM 575 PIPE	1.00	1.00 LS	20,813.000		20,813				20,813
------------	-------------------	------	---------	------------	--	--------	--	--	--	--------

====> Item Totals:	575	- VALVE BOX, CAST IRON								
\$20,813.00				[]		20,813				20,813
297.329	70 EA					297.33				297.33

BID ITEM	= 576	CLIENT# = 576	Land Item	SCHEDULE: 1 100						
Description =	VALVE CHAMBER, PRECAST, 8'X10'		Unit =	EA	Takeoff Quan:		5.000	Engr Quan:		5.000

576.01 VALVE CHAMBER, PRECAST, 8'X10' Quan: 5.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	(Mod) Underground Utilities 6 Man	100.00	CH	Prod:	100.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	4.00	
2BI576PIPE	BID ITEM 576 P@110.25	1.00	1.00 LS	193,007.000		212,790				212,790
2VCHAMBER	VALVE CHAMBER	1.00	5.00 EA	15,908.000		79,540				79,540
8EX135A	135 Excavator W/Attach	1.00	100.00 HR	68.251			6,825			6,825
8EX200	200 Excavator	1.00	100.00 HR	78.000			7,800			7,800
8EX400	400 Excavator	1.00	100.00 HR	175.700			17,570			17,570
8LO950	950 Loader	1.00	100.00 HR	81.500			8,150			8,150
FOCI	Civil Forman	1.00	100.00 MH	77.060	10,065					10,065
LAP	Labor Underground Water	2.00	200.00 MH	53.880	14,200					14,200
OPE	Operator - Excavator	2.00	200.00 MH	74.560	19,490					19,490
OPL	Operator - Loader	1.00	100.00 MH	74.560	9,745					9,745
\$386,175.24	120.0000 MH/EA	600.00	MH	[8987]	53,500	292,330		40,345		386,175

====> Item Totals:	576	- VALVE CHAMBER, PRECAST, 8'X10'								
\$386,175.24	120.0000 MH/EA	600.00	MH	[8987]	53,500	292,330		40,345		386,175
77,235.048	5 EA				10,699.98	58,466.04		8,069.02		77,235.05

BID ITEM	= 577	CLIENT# = 577	Land Item	SCHEDULE: 1 100						
Description =	HYDRANT, 6 IN CONN, TYPE 310		Unit =	EA	Takeoff Quan:		15.000	Engr Quan:		15.000

577.01 HYDRANT, 6 IN CONN, TYPE 310 Quan: 15.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man	60.00	CH	Prod:	60.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI577PIPE	BID ITEM 577 PIPE	1.00	1.00 LS	55,896.600		55,897				55,897
8EX135A	135 Excavator W/Attach	1.00	60.00 HR	68.251			4,095			4,095
8EX200	200 Excavator	1.00	60.00 HR	78.000			4,680			4,680
8LO950	950 Loader	1.00	60.00 HR	81.500			4,890			4,890
FOCI	Civil Forman	1.00	60.00 MH	77.060	6,039					6,039
LAP	Labor Underground Water	2.00	120.00 MH	53.880	8,520					8,520
OPE	Operator - Excavator	1.00	60.00 MH	74.560	5,847					5,847
OPL	Operator - Loader	1.00	60.00 MH	74.560	5,847					5,847
\$95,814.62	20.0000 MH/EA	300.00	MH	[1469.336]	26,253	55,897		13,665		95,815

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 577	CLIENT# = 577		Land Item	SCHEDULE: 1	100				
Description =	HYDRANT, 6 IN CONN, TYPE 310		Unit =	EA	Takeoff Quan:	15.000	Engr Quan:		15.000
====> Item Totals: 577 - HYDRANT, 6 IN CONN, TYPE 310									
\$95,814.62	20.0000 MH/EA	300.00	MH	[1469.336]	26,253	55,897	13,665		95,815
6,387.641	15 EA				1,750.20	3,726.44	911.00		6,387.64

BID ITEM = 578	CLIENT# = 578		Land Item	SCHEDULE: 1	100				
Description =	HYDRANT, 6 IN CONN, TYPE 311		Unit =	EA	Takeoff Quan:	1.000	Engr Quan:		1.000
578.01 HYDRANT, 6 IN CONN, TYPE 311									
		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>UNM</u>	Underground Utilities 6 Man	4.00	CH	Prod:	4.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI578PIPE	BID ITEM 578 PIPE	1.00	LS	3,999.300	3,999				3,999
8EX135A	135 Excavator W/Attach	1.00	4.00 HR	68.251			273		273
8EX200	200 Excavator	1.00	4.00 HR	78.000			312		312
8LO950	950 Loader	1.00	4.00 HR	81.500			326		326
FOCI	Civil Forman	1.00	4.00 MH	77.060	403				403
LAP	Labor Underground Water	2.00	8.00 MH	53.880	568				568
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390				390
OPL	Operator - Loader	1.00	4.00 MH	74.560	390				390
\$6,660.49	20.0000 MH/EA	20.00	MH	[1469.32]	1,750	3,999	911		6,660
====> Item Totals: 578 - HYDRANT, 6 IN CONN, TYPE 311									
\$6,660.49	20.0000 MH/EA	20.00	MH	[1469.32]	1,750	3,999	911		6,660
6,660.490	1 EA				1,750.19	3,999.30	911.00		6,660.49

BID ITEM = 579	CLIENT# = 579		Land Item	SCHEDULE: 1	100				
Description =	SUPPORT SPU WITH SERVICE TRANSFER OR REN		Unit =	EA	Takeoff Quan:	43.000	Engr Quan:		43.000
579..02 BACKFILL 3/4 TO 2 INCH SERVICE									
		Quan:	43.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>UNS</u>	Underground Utilities 4 Man	57.00	CH	Prod:	57.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	57.00 HR	51.051			2,910		2,910
8EX100	100 Excavator	1.00	57.00 HR	52.300			2,981		2,981
FOCI	Civil Forman	1.00	57.00 MH	77.060	5,737				5,737
LAP	Labor Underground Water	1.00	57.00 MH	53.880	4,047				4,047
OPB	Operator - Backhoe	1.00	57.00 MH	74.560	5,555				5,555
OPE	Operator - Excavator	1.00	57.00 MH	74.560	5,555				5,555
\$26,784.25	5.3023 MH/EA	228.00	MH	[408.367]	20,893		5,891		26,784
579.01 TRENCH 3/4 TO 2 INCH SERVICE									
		Quan:	43.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>UNS</u>	Underground Utilities 4 Man	57.00	CH	Prod:	57.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	57.00 HR	51.051			2,910		2,910
8EX100	100 Excavator	1.00	57.00 HR	52.300			2,981		2,981
FOCI	Civil Forman	1.00	57.00 MH	77.060	5,737				5,737
LAP	Labor Underground Water	1.00	57.00 MH	53.880	4,047				4,047
OPB	Operator - Backhoe	1.00	57.00 MH	74.560	5,555				5,555
OPE	Operator - Excavator	1.00	57.00 MH	74.560	5,555				5,555
\$26,784.25	5.3023 MH/EA	228.00	MH	[408.367]	20,893		5,891		26,784
====> Item Totals: 579 - SUPPORT SPU WITH SERVICE TRANSFER OR REN									
\$53,568.50	10.6046 MH/EA	456.00	MH	[816.733]	41,787		11,782		53,569
1,245.779	43 EA				971.78		274.00		1,245.78

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 580 CLIENT# = 580 Land Item SCHEDULE: 1 100
Description = SUPPORT SPU WITH SERVICE TRANSFER OR REN Unit = EA Takeoff Quan: 18.000 Engr Quan: 18.000

580.01 TRENCH SERVICE 4 TO 8 INCH Quan: 18.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	40.00	CH	Prod:	40.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2BI580PIPE	BID ITEM 580 P@110.25	1.00	1.00 LS	20,548.940	22,655				22,655
8BA310A	418 Backhoe W/Attachme	1.00	40.00 HR	51.051			2,042		2,042
8EX100	100 Excavator	1.00	40.00 HR	52.300			2,092		2,092
FOCI	Civil Forman	1.00	40.00 MH	77.060	4,026				4,026
LAP	Labor Underground Water	1.00	40.00 MH	53.880	2,840				2,840
OPB	Operator - Backhoe	1.00	40.00 MH	74.560	3,898				3,898
OPE	Operator - Excavator	1.00	40.00 MH	74.560	3,898				3,898
\$41,451.19	8.8888 MH/EA	160.00	MH	[684.591]	14,662	22,655		4,134	41,451

580.02 BACKFILL SERVICE 4 TO 8 IN Quan: 18.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	30.00	CH	Prod:	30.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	30.00 HR	51.051			1,532		1,532
8EX100	100 Excavator	1.00	30.00 HR	52.300			1,569		1,569
FOCI	Civil Forman	1.00	30.00 MH	77.060	3,019				3,019
LAP	Labor Underground Water	1.00	30.00 MH	53.880	2,130				2,130
OPB	Operator - Backhoe	1.00	30.00 MH	74.560	2,924				2,924
OPE	Operator - Excavator	1.00	30.00 MH	74.560	2,924				2,924
\$14,096.98	6.6666 MH/EA	120.00	MH	[513.443]	10,996			3,101	14,097

====> **Item Totals: 580 - SUPPORT SPU WITH SERVICE TRANSFER OR REN**
\$55,548.17 15.5555 MH/EA 280.00 MH [1198.034] 25,658 22,655 7,235 **55,548**
3,086.009 18 EA 1,425.47 1,258.62 401.92 3,086.01

BID ITEM = 581 CLIENT# = 581 Land Item SCHEDULE: 1 100
Description = SUPPORT SPU WITH NEW WATER SERVICE, 4 IN Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

581.01 SUPPORT SPU WITH NEW WATER SERVICE, 4 I Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	2.00	CH	Prod:	2.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2BI581PIPE	BID ITEM 581 P@110.25	1.00	1.00 EA	5,487.800	6,050				6,050
8BA310A	418 Backhoe W/Attachme	1.00	2.00 HR	51.051			102		102
8EX100	100 Excavator	1.00	2.00 HR	52.300			105		105
FOCI	Civil Forman	1.00	2.00 MH	77.060	201				201
LAP	Labor Underground Water	1.00	2.00 MH	53.880	142				142
OPB	Operator - Backhoe	1.00	2.00 MH	74.560	195				195
OPE	Operator - Excavator	1.00	2.00 MH	74.560	195				195
\$6,990.09	8.0000 MH/EA	8.00	MH	[616.13]	733	6,050		207	6,990

====> **Item Totals: 581 - SUPPORT SPU WITH NEW WATER SERVICE, 4 IN**
\$6,990.09 8.0000 MH/EA 8.00 MH [616.13] 733 6,050 207 **6,990**
6,990.090 1 EA 733.10 6,050.30 206.69 6,990.09

BID ITEM = 582 CLIENT# = 582 Land Item SCHEDULE: 1 100
Description = SUPPORT SPU WITH WATER SERVICE RETIREMEN Unit = EA Takeoff Quan: 2.000 Engr Quan: 2.000

582.01 SUPPORT SPU WITH WATER SERVICE RETIRE Quan: 2.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	4.00	CH	Prod:	4.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
------------	-----------------------------	------	----	--------------	------------------	----------	------	----------	------

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 582	CLIENT# = 582		Land Item	SCHEDULE: 1 100						
Description =	SUPPORT SPU WITH WATER SERVICE RETIREMEN	Unit =	EA	Takeoff	Quan:		2.000	Engr Quan:		2.000
8BA310A	418 Backhoe W/Attachme	1.00	4.00 HR	51.051				204		204
8EX100	100 Excavator	1.00	4.00 HR	52.300				209		209
FOCI	Civil Forman	1.00	4.00 MH	77.060	403					403
LAP	Labor Underground Water	1.00	4.00 MH	53.880	284					284
OPB	Operator - Backhoe	1.00	4.00 MH	74.560	390					390
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390					390
\$1,879.59	8.0000 MH/EA		16.00 MH	[616.125]	1,466			413		1,880
====>	Item Totals: 582 - SUPPORT SPU WITH WATER SERVICE RETIREMEN									
\$1,879.59	8.0000 MH/EA		16.00 MH	[616.125]	1,466			413		1,880
939.795	2 EA				733.10			206.70		939.80
BID ITEM = 583	CLIENT# = 583		Land Item	SCHEDULE: 1 100						
Description =	BEDDING, CL B, 4 IN PIPE	Unit =	LF	Takeoff	Quan:		26.000	Engr Quan:		26.000
583.01	BEDDING, CL B, 4 IN PIPE		Quan:	26.00 LF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
2AGS07	SEATTLE TYPE 7	1.00	13.00 TON	29.750		387				387
3DEDU02D	Dirt Trucking and Dump	1.00	10.00 TCY	24.500			245			245
\$631.75				[]		387	245			632
====>	Item Totals: 583 - BEDDING, CL B, 4 IN PIPE									
\$631.75				[]		387	245			632
24.298	26 LF					14.88	9.42			24.30
BID ITEM = 584	CLIENT# = 584		Land Item	SCHEDULE: 1 100						
Description =	BEDDING, CL B, 6 IN PIPE	Unit =	LF	Takeoff	Quan:		55.000	Engr Quan:		55.000
584.01	BEDDING, CL B, 6 IN PIPE		Quan:	55.00 LF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
2AGS07	SEATTLE TYPE 7	1.00	27.00 TON	29.750		803				803
3DEDU02D	Dirt Trucking and Dump	1.00	19.00 TCY	24.500			466			466
\$1,268.75				[]		803	466			1,269
====>	Item Totals: 584 - BEDDING, CL B, 6 IN PIPE									
\$1,268.75				[]		803	466			1,269
23.068	55 LF					14.60	8.46			23.07
BID ITEM = 585	CLIENT# = 585		Land Item	SCHEDULE: 1 100						
Description =	BEDDING, CL B, 8 IN PIPE	Unit =	LF	Takeoff	Quan:		12.000	Engr Quan:		12.000
585.01	BEDDING, CL B, 8 IN PIPE		Quan:	12.00 LF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG			
2AGS07	SEATTLE TYPE 7	1.00	9.00 TON	29.750		268				268
3DEDU02D	Dirt Trucking and Dump	1.00	6.00 TCY	24.500			147			147
\$414.75				[]		268	147			415
====>	Item Totals: 585 - BEDDING, CL B, 8 IN PIPE									
\$414.75				[]		268	147			415
34.563	12 LF					22.31	12.25			34.56

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
-------------------	------	-----	---------------	-----------	-------	---------------	-----------------	------------	--------------	-------

BID ITEM = 586 CLIENT# = 586 Land Item SCHEDULE: 1 100
Description = PIPE, SS or SSS, PVC D3034 SDR 35, 4 IN Unit = LF Takeoff Quan: 26.000 Engr Quan: 26.000

586.01 PIPE, SS or SSS, PVC D3034 SDR 35, 4 IN Quan: 26.00 LF Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		16.00	CH	Prod:	16.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI586PIPE	BID ITEM 586 PIPE	1.00	1.00	LS	122.000		122				122
8EX135A	135 Excavator W/Attach	1.00	16.00	HR	68.251				1,092		1,092
8EX200	200 Excavator	1.00	16.00	HR	78.000				1,248		1,248
8LO950	950 Loader	1.00	16.00	HR	81.500				1,304		1,304
FOCI	Civil Forman	1.00	16.00	MH	77.060	1,610					1,610
LAP	Labor Underground Water	2.00	32.00	MH	53.880	2,272					2,272
OPE	Operator - Excavator	1.00	16.00	MH	74.560	1,559					1,559
OPL	Operator - Loader	1.00	16.00	MH	74.560	1,559					1,559
\$10,766.79	3.0769 MH/LF		80.00	MH	[226.052]	7,001	122		3,644		10,767

=====> **Item Totals: 586 - PIPE, SS or SSS, PVC D3034 SDR 35, 4 IN**
\$10,766.79 3.0769 MH/LF 80.00 MH [226.052] 7,001 122 3,644 **10,767**
414.107 26 LF 269.26 4.69 140.15 414.11

BID ITEM = 587 CLIENT# = 587 Land Item SCHEDULE: 1 100
Description = PIPE, SS or SSS, PVC D3034 SDR 35, 6 IN Unit = LF Takeoff Quan: 55.000 Engr Quan: 55.000

587.01 PIPE, SS or SSS, PVC D3034 SDR 35, 6 IN Quan: 55.00 LF Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		16.00	CH	Prod:	16.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI587PIPE	BID ITEM 587 PIPE	1.00	1.00	LS	362.000		362				362
8EX135A	135 Excavator W/Attach	1.00	16.00	HR	68.251				1,092		1,092
8EX200	200 Excavator	1.00	16.00	HR	78.000				1,248		1,248
8LO950	950 Loader	1.00	16.00	HR	81.500				1,304		1,304
FOCI	Civil Forman	1.00	16.00	MH	77.060	1,610					1,610
LAP	Labor Underground Water	2.00	32.00	MH	53.880	2,272					2,272
OPE	Operator - Excavator	1.00	16.00	MH	74.560	1,559					1,559
OPL	Operator - Loader	1.00	16.00	MH	74.560	1,559					1,559
\$11,006.79	1.4545 MH/LF		80.00	MH	[106.861]	7,001	362		3,644		11,007

=====> **Item Totals: 587 - PIPE, SS or SSS, PVC D3034 SDR 35, 6 IN**
\$11,006.79 1.4545 MH/LF 80.00 MH [106.861] 7,001 362 3,644 **11,007**
200.123 55 LF 127.29 6.58 66.25 200.12

BID ITEM = 588 CLIENT# = 588 Land Item SCHEDULE: 1 100
Description = PIPE, SD, D.I., CL 50, 8 IN Unit = LF Takeoff Quan: 12.000 Engr Quan: 12.000

588.01 PIPE, SD, D.I., CL 50, 8 IN Quan: 12.00 LF Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		6.00	CH	Prod:	6.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI588PIPE	BID ITEM 588 PIPE	1.00	1.00	LS	285.480		285				285
8EX135A	135 Excavator W/Attach	1.00	6.00	HR	68.251				409		409
8EX200	200 Excavator	1.00	6.00	HR	78.000				468		468
8LO950	950 Loader	1.00	6.00	HR	81.500				489		489
FOCI	Civil Forman	1.00	6.00	MH	77.060	604					604
LAP	Labor Underground Water	2.00	12.00	MH	53.880	852					852
OPE	Operator - Excavator	1.00	6.00	MH	74.560	585					585
OPL	Operator - Loader	1.00	6.00	MH	74.560	585					585
\$4,277.27	2.5000 MH/LF		30.00	MH	[183.668]	2,625	285		1,366		4,277

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 588	CLIENT# = 588		Land Item	SCHEDULE: 1 100						
Description =	PIPE, SD, D.I., CL 50, 8 IN		Unit =	LF	Takeoff Quan:		12.000	Engr Quan:		12.000
=====> Item Totals:	588 - PIPE, SD, D.I., CL 50, 8 IN									
\$4,277.27	2.5000 MH/LF	30.00 MH		[183.668]	2,625	285		1,366		4,277
356.439	12 LF				218.78	23.79		113.87		356.44

BID ITEM = 589	CLIENT# = 589		Land Item	SCHEDULE: 1 100						
Description =	SEWER CLEANOUT, 4 IN		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
589.01	SEWER CLEANOUT, 4 IN		Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>UNM</u>	Underground Utilities 6 Man	2.00	CH	Prod:	2.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI589PIPE	BID ITEM 589 PIPE	1.00	LS	136.340		136				136
8EX135A	135 Excavator W/Attach	1.00	HR	68.251				136		136
8EX200	200 Excavator	1.00	HR	78.000				156		156
8LO950	950 Loader	1.00	HR	81.500				163		163
FOCI	Civil Forman	1.00	MH	77.060	201					201
LAP	Labor Underground Water	2.00	MH	53.880	284					284
OPE	Operator - Excavator	1.00	MH	74.560	195					195
OPL	Operator - Loader	1.00	MH	74.560	195					195
\$1,466.92	5.0000 MH/EA	10.00 MH		[367.33]	875	136		455		1,467
=====> Item Totals:	589 - SEWER CLEANOUT, 4 IN									
\$1,466.92	5.0000 MH/EA	10.00 MH		[367.33]	875	136		455		1,467
733.460	2 EA				437.55	68.17		227.75		733.46

BID ITEM = 590	CLIENT# = 590		Land Item	SCHEDULE: 1 100						
Description =	SEWER CLEANOUT, 8 IN		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
590.01	SEWER CLEANOUT, 8 IN		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>UNM</u>	Underground Utilities 6 Man	1.00	CH	Prod:	1.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI590PIPE	BID ITEM 590 PIPE	1.00	LS	686.450		686				686
8EX135A	135 Excavator W/Attach	1.00	HR	68.251				68		68
8EX200	200 Excavator	1.00	HR	78.000				78		78
8LO950	950 Loader	1.00	HR	81.500				81		81
FOCI	Civil Forman	1.00	MH	77.060	101					101
LAP	Labor Underground Water	2.00	MH	53.880	142					142
OPE	Operator - Excavator	1.00	MH	74.560	97					97
OPL	Operator - Loader	1.00	MH	74.560	97					97
\$1,351.74	5.0000 MH/EA	5.00 MH		[367.35]	438	686		228		1,352
=====> Item Totals:	590 - SEWER CLEANOUT, 8 IN									
\$1,351.74	5.0000 MH/EA	5.00 MH		[367.35]	438	686		228		1,352
1,351.740	1 EA				437.56	686.45		227.73		1,351.74

BID ITEM = 591	CLIENT# = 591		Land Item	SCHEDULE: 1 100						
Description =	CONDUIT RISER, 4 IN		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
591.01	CONDUIT RISER, 4 IN		Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4ELEC	Electrical sub	1.00	EA	2,800.000				5,600		5,600

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = **592** CLIENT# = 592 Land Item SCHEDULE: 1 100
Description = HANDHOLE, TYPE 5 Unit = EA Takeoff Quan: 1.000 Engr Quan: 1.000

592.01 HANDHOLE, TYPE 5 Quan: 1.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4ELEC	Electrical sub	1.00	1.00 EA	3,200.000					3,200	3,200
-------	----------------	------	---------	-----------	--	--	--	--	-------	-------

BID ITEM = **593** CLIENT# = 593 Land Item SCHEDULE: 1 100
Description = METRO COMFORT STATION-BREAK ROOM Unit = LS Takeoff Quan: 1.000 Engr Quan: 1.000

593.01 METRO COMFORT STATION-BREAK ROOM Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4COMSUB	COMFORT STATION SU	1.00	1.00 LS	200,000.000				200,000	200,000
4ELEC	Electrical sub	1.00	1.00 LS	69,700.000				69,700	69,700
4GLAS	GLASS INSTALLER	1.00	1.00 LS	19,500.000				19,500	19,500
4HVAC	HAVAC SUB	1.00	1.00 LS	10,000.000				10,000	10,000
4PLUM	PLUMING SUB	1.00	1.00 LS	10,000.000				10,000	10,000
\$309,200.00				[]				309,200	309,200

593.02 EXCAVATATE FOUNDATION Quan: 20.00 CY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	16.00 HR	51.051			817		817
8EX100	100 Excavator	1.00	16.00 HR	52.300			837		837
FOCI	Civil Forman	1.00	16.00 MH	77.060	1,610				1,610
LAG	General Laborer	2.00	32.00 MH	52.910	2,232				2,232
OPE	Operator - Excavator	1.00	16.00 MH	74.560	1,559				1,559
\$7,055.49	3.2000 MH/CY		64.00 MH	[226.548]	5,402		1,654		7,055

593.03 FOUNDATION Quan: 15.00 CY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COM</u>	Concrete 6 Man Crew		40.00 CH	Prod:	40.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00
2CR040	4000LB READY M@110.2	1.00	15.00 CY	121.500	2,009				2,009
2RBCOM	REBAR COMFOR S@110.	1.00	1.00 LS	2,500.000	2,756				2,756
2SLABIN	SLAB INSALATIO@110.2	1.00	200.00 SF	10.000	2,205				2,205
CEJ	Cement Mason	5.00	200.00 MH	64.980	17,039				17,039
FOCO	Concrete Forman	1.00	40.00 MH	68.980	3,613				3,613
\$27,622.58	16.0000 MH/CY		240.00 MH	[1155.381]	20,652	6,971			27,623

====> **Item Totals: 593 - METRO COMFORT STATION-BREAK ROOM**

\$343,878.07	304.0000 MH/LS	304.00 MH	[21861.67]	26,054	6,971		1,654	309,200	343,878
343,878.070	1 LS			26,053.91	6,970.56		1,653.60	309,200.00	343,878.07

BID ITEM = **594** CLIENT# = 594 Land Item SCHEDULE: 1 100
Description = CONCRETE ENCASED DUCT BANK (9-5" RGS) Unit = LF Takeoff Quan: 46.000 Engr Quan: 46.000

594.01 EXCAVATE CONCRETE ENCASED DUCT BANK Quan: 46.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>DBC</u>	DUCTBANK CREW		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
3DEDU02V	VACTOR TRUCK DISPO	1.00	3.00 EA	500.000		1,500			1,500
3VAC	VACTOR TRUCKS	1.00	16.00 HR	275.000		4,400			4,400
8EX100	100 Excavator	1.00	16.00 HR	52.300			837		837
8EX135A	135 Excavator W/Attach	1.00	16.00 HR	68.251			1,092		1,092
8LO950	950 Loader	1.00	16.00 HR	81.500			1,304		1,304
FOCI	Civil Forman	1.00	16.00 MH	77.060	1,610				1,610

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 594	CLIENT# = 594			Land Item	SCHEDULE: 1 100					
Description =	CONCRETE ENCASED DUCT BANK (9-5" RGS)		Unit =	LF	Takeoff Quan:		46.000	Engr Quan:		46.000
LAG	General Laborer	2.00	32.00 MH	52.910	2,232					2,232
OPE	Operator - Excavator	1.00	16.00 MH	74.560	1,559					1,559
OPL	Operator - Loader	1.00	16.00 MH	74.560	1,559					1,559
\$16,093.89	1.7391 MH/LF		80.00 MH	[127.026]	6,961		5,900	3,233		16,094
594.02	CONCRETE ENCASED DUCT BANK (9-5" RGS)		Quan:	46.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>DBC</u>	DUCTBANK CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
4ELEC	Electrical sub	1.00	46.00 LF	1,770.000				81,420	81,420	
8EX100	100 Excavator	1.00	8.00 HR	52.300				418	418	
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546	546	
8LO950	950 Loader	1.00	8.00 HR	81.500				652	652	
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805	
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116	
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780	
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780	
\$86,516.95	0.8695 MH/LF		40.00 MH	[63.513]	3,481			1,616	81,420	86,517
594.03	BACFILL CON ENCASED DUCT BANK		Quan:	46.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>DBC</u>	DUCTBANK CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2CRLSFTB	LOW STRENGHT FTB	1.00	28.00 CY	107.150		3,000			3,000	
8EX100	100 Excavator	1.00	8.00 HR	52.300				418	418	
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546	546	
8LO950	950 Loader	1.00	8.00 HR	81.500				652	652	
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805	
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116	
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780	
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780	
\$8,097.15	0.8695 MH/LF		40.00 MH	[63.513]	3,481	3,000		1,616		8,097
====> Item Totals:	594		- CONCRETE ENCASED DUCT BANK (9-5" RGS)							
\$110,707.99	3.4782 MH/LF		160.00 MH	[254.053]	13,922	3,000	5,900	6,466	81,420	110,708
2,406.695	46 LF				302.66	65.22	128.26	140.56	1,770.00	2,406.70

BID ITEM = 595 CLIENT# = 595 Land Item SCHEDULE: 1 100
Description = HSFTB ENCASED DUCT BANK (4-5" FIBERGLASS Unit = LF Takeoff Quan: 48.000 Engr Quan: 48.000

595.01	EXCAVATE DUCT BANK		Quan:	48.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>DBC</u>	DUCTBANK CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
3DEDU02D	Dirt Trucking and Dump	1.00	133.00 TCY	24.500		3,259			3,259	
8EX100	100 Excavator	1.00	8.00 HR	52.300				418	418	
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546	546	
8LO950	950 Loader	1.00	8.00 HR	81.500				652	652	
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805	
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116	
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780	
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780	
\$8,355.45	0.8333 MH/LF		40.00 MH	[60.867]	3,481		3,259	1,616		8,355
595.02	HSFTB ENCASED DUCT BANK (4-5" FIBERGLAS		Quan:	48.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>DBC</u>	DUCTBANK CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
4ELEC	Electrical sub	1.00	48.00 LF	610.000					29,280	29,280
8EX100	100 Excavator	1.00	8.00 HR	52.300				418		418

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
-------------------	------	--------------	------	-----------	-------	---------------	-----------------	------------	--------------	-------

BID ITEM = 595	CLIENT# = 595	Land Item	SCHEDULE: 1 100							
Description =	HSFTB ENCASED DUCT BANK (4-5" FIBERGLASS	Unit =	LF	Takeoff	Quan:		48.000	Engr	Quan:	48.000
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546		546
8LO950	950 Loader	1.00	8.00 HR	81.500				652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805					805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780					780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780					780
\$34,376.95	0.8333 MH/LF	40.00	MH	[60.867]	3,481			1,616	29,280	34,377

595.03 BACFILL DUCT BANK **Quan: 48.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>DBC</u>	DUCTBANK CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CRLSFTB	LOW STRENGHT FTB	1.00	88.00 CY	107.150	9,429				9,429
8EX100	100 Excavator	1.00	8.00 HR	52.300				418	418
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546	546
8LO950	950 Loader	1.00	8.00 HR	81.500				652	652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780
\$14,526.15	0.8333 MH/LF	40.00	MH	[60.867]	3,481	9,429		1,616	14,526

====> **Item Totals: 595 - HSFTB ENCASED DUCT BANK (4-5" FIBERGLASS**

\$57,258.55	2.5000 MH/LF	120.00	MH	[182.601]	10,442	9,429	3,259	4,849	29,280	57,259
1,192.886	48 LF				217.53	196.44	67.89	101.03	610.00	1,192.89

BID ITEM = 596	CLIENT# = 596	Land Item	SCHEDULE: 1 100							
Description =	HSFTB ENCASED DUCT BANK (4-5" FIBERGLASS	Unit =	LF	Takeoff	Quan:		74.000	Engr	Quan:	74.000

596.01 EXCAVATE DUCT BANK **Quan: 74.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>DBC</u>	DUCTBANK CREW		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
3DEDU02D	Dirt Trucking and Dump	1.00	189.00 TCY	24.500		4,631			4,631
3VAC	VACTOR TRUCKS	1.00	8.00 HR	275.000		2,200			2,200
8EX100	100 Excavator	1.00	16.00 HR	52.300				837	837
8EX135A	135 Excavator W/Attach	1.00	16.00 HR	68.251				1,092	1,092
8LO950	950 Loader	1.00	16.00 HR	81.500				1,304	1,304
FOCI	Civil Forman	1.00	16.00 MH	77.060	1,610				1,610
LAG	General Laborer	2.00	32.00 MH	52.910	2,232				2,232
OPE	Operator - Excavator	1.00	16.00 MH	74.560	1,559				1,559
OPL	Operator - Loader	1.00	16.00 MH	74.560	1,559				1,559
\$17,024.39	1.0810 MH/LF	80.00	MH	[78.962]	6,961	6,831		3,233	17,024

596.02 HSFTB ENCASED DUCT BANK (4-5" FIBERGLAS **Quan: 74.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>EAS</u>	Earthwork 4 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
4ELEC	Electrical sub	1.00	74.00 LF	520.000				38,480	38,480
8BA310A	418 Backhoe W/Attachme	1.00	8.00 HR	51.051				408	408
8EX100	100 Excavator	1.00	8.00 HR	52.300				418	418
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
\$42,007.75	0.4324 MH/LF	32.00	MH	[30.615]	2,701			827	38,480

596.03 BACKFILL DUCT BANK **Quan: 74.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>EAS</u>	Earthwork 4 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
------------	----------------------	--	---------	--------------	------------------	----------	------	----------	------

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 596	CLIENT# = 596		Land Item	SCHEDULE: 1 100						
Description =	HSFTB ENCASED DUCT BANK (4-5" FIBERGLASS)		Unit =	LF	Takeoff Quan:		74.000	Engr Quan:		74.000
2CRLSFTB	LOW STRENGHT FTB	1.00	138.00 CY	107.150		14,787				14,787
8BA310A	418 Backhoe W/Attachme	1.00	8.00 HR	51.051				408		408
8EX100	100 Excavator	1.00	8.00 HR	52.300				418		418
FOCI	Civil Forman	1.00	8.00 MH	77.060	805					805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780					780
\$18,314.45	0.4324 MH/LF		32.00 MH	[30.615]	2,701	14,787		827		18,314
=====> Item Totals: 596 - HSFTB ENCASED DUCT BANK (4-5" FIBERGLASS)										
\$77,346.59	1.9459 MH/LF		144.00 MH	[140.191]	12,363	14,787	6,831	4,886	38,480	77,347
1,045.224	74 LF				167.07	199.82	92.30	66.03	520.00	1,045.22

BID ITEM = 597	CLIENT# = 597		Land Item	SCHEDULE: 1 100						
Description =	HSFTB ENCASED DUCT BANK (2-4" PVC)		Unit =	LF	Takeoff Quan:		72.000	Engr Quan:		72.000

597.01 HSFTB ENCASED DUCT BANK (2-4" PVC) Quan: 72.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>DBC</u>	DUCTBANK CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
3DEDU02D	Dirt Trucking and Dump	1.00	64.00 TCY	24.500		1,568				1,568
8EX100	100 Excavator	1.00	8.00 HR	52.300				418		418
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251				546		546
8LO950	950 Loader	1.00	8.00 HR	81.500				652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805					805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780					780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780					780
\$6,664.95	0.5555 MH/LF		40.00 MH	[40.578]	3,481	1,568		1,616		6,665

597.02 HSFTB ENCASED DUCT BANK (2-4" PVC) Quan: 72.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

4ELEC	Electrical sub	1.00	72.00 LF	140.000					10,080	10,080
-------	----------------	------	----------	---------	--	--	--	--	--------	--------

597.03 BACFILL DUCT BANK Quan: 72.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>DBC</u>	DUCTBANK CREW		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2CRLSFTB	LOW STRENGHT FTB	1.00	33.00 CY	107.150		3,536				3,536
8EX100	100 Excavator	1.00	4.00 HR	52.300				209		209
8EX135A	135 Excavator W/Attach	1.00	4.00 HR	68.251				273		273
8LO950	950 Loader	1.00	4.00 HR	81.500				326		326
FOCI	Civil Forman	1.00	4.00 MH	77.060	403					403
LAG	General Laborer	2.00	8.00 MH	52.910	558					558
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390					390
OPL	Operator - Loader	1.00	4.00 MH	74.560	390					390
\$6,084.42	0.2777 MH/LF		20.00 MH	[20.289]	1,740	3,536		808		6,084

=====> Item Totals: 597 - HSFTB ENCASED DUCT BANK (2-4" PVC)										
\$22,829.37	0.8333 MH/LF		60.00 MH	[60.867]	5,221	3,536	1,568	2,425	10,080	22,829
317.075	72 LF				72.51	49.11	21.78	33.68	140.00	317.07

BID ITEM = 598	CLIENT# = 598		Land Item	SCHEDULE: 1 100						
Description =	HSFTB ENCASED DUCT BANK (4-4" PVC)		Unit =	LF	Takeoff Quan:		10.000	Engr Quan:		10.000

598.01 HSFTB ENCASED DUCT BANK (4-4" PVC) Quan: 10.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 598	CLIENT# = 598		Land Item	SCHEDULE: 1 100					
Description =	HSFTB ENCASED DUCT BANK (4-4" PVC)		Unit =	LF	Takeoff Quan:	10.000	Engr Quan:		10.000
<u>DBC</u>	DUCTBANK CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CRLSFTB	LOW STRENGHT FTB	1.00	8.00 CY	107.150		857			857
3DEDU02D	Dirt Trucking and Dump	1.00	12.00 TCY	24.500		294			294
4ELEC	Electrical sub	1.00	10.00 LF	1,220.000				12,200	12,200
8EX100	100 Excavator	1.00	8.00 HR	52.300			418		418
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546		546
8LO950	950 Loader	1.00	8.00 HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780
\$18,448.15	4.0000 MH/LF	40.00 MH	[292.161]	3,481	857	294	1,616	12,200	18,448
=====> Item Totals: 598	- HSFTB ENCASED DUCT BANK (4-4" PVC)								
\$18,448.15	4.0000 MH/LF	40.00 MH	[292.161]	3,481	857	294	1,616	12,200	18,448
1,844.815	10 LF			348.06	85.72	29.40	161.64	1,220.00	1,844.82

BID ITEM = 599	CLIENT# = 599		Land Item	SCHEDULE: 1 100					
Description =	HSFTB ENCASED DUCT BANK (4-5" FIBERGLASS		Unit =	LF	Takeoff Quan:	12.000	Engr Quan:		12.000
599.01	HSFTB ENCASED DUCT BANK (4-5" FIBERGLAS	Quan:	12.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>DBC</u>	DUCTBANK CREW		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CRLSFTB	LOW STRENGHT FTB	1.00	10.00 CY	107.150		1,072			1,072
3DEDU02D	Dirt Trucking and Dump	1.00	14.00 TCY	24.500		343			343
4ELEC	Electrical sub	1.00	12.00 LF	1,730.000				20,760	20,760
8EX100	100 Excavator	1.00	8.00 HR	52.300			418		418
8EX135A	135 Excavator W/Attach	1.00	8.00 HR	68.251			546		546
8LO950	950 Loader	1.00	8.00 HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00 MH	74.560	780				780
\$27,271.45	3.3333 MH/LF	40.00 MH	[243.468]	3,481	1,072	343	1,616	20,760	27,271
=====> Item Totals: 599	- HSFTB ENCASED DUCT BANK (4-5" FIBERGLASS								
\$27,271.45	3.3333 MH/LF	40.00 MH	[243.468]	3,481	1,072	343	1,616	20,760	27,271
2,272.621	12 LF			290.05	89.29	28.58	134.70	1,730.00	2,272.62

BID ITEM = 600	CLIENT# = 600		Land Item	SCHEDULE: 1 100					
Description =	CONDUIT 2-4" PVC DIRECT BURY		Unit =	LF	Takeoff Quan:	38.000	Engr Quan:		38.000
600.01	CONDUIT 2-4" PVC DIRECT BURY	Quan:	38.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
4ELEC	Electrical sub	1.00	38.00 LF	60.000				2,280	2,280
8BA310A	418 Backhoe W/Attachme	1.00	8.00 HR	51.051			408		408
8EX100	100 Excavator	1.00	8.00 HR	52.300			418		418
FOCI	Civil Forman	1.00	8.00 MH	77.060	805				805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116				1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780				780
\$5,807.75	0.8421 MH/LF	32.00 MH	[59.618]	2,701			827	2,280	5,808

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 600	CLIENT# = 600		Land Item	SCHEDULE: 1 100						
Description =	CONDUIT 2-4" PVC DIRECT BURY		Unit =	LF	Takeoff Quan:		38.000	Engr Quan:		38.000
=====> Item Totals: 600 - CONDUIT 2-4" PVC DIRECT BURY										
\$5,807.75	0.8421 MH/LF		32.00 MH	[59.618]	2,701			827	2,280	5,808
152.836	38 LF				71.08			21.76	60.00	152.84

BID ITEM = 601	CLIENT# = 601		Land Item	SCHEDULE: 1 100						
Description =	ENLARGED VAULT ROOF OPENING		Unit =	EA	Takeoff Quan:		7.000	Engr Quan:		7.000
601.01 ENLARGED VAULT ROOF OPENING										
			Quan:	7.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		56.00 CH	Prod:	56.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
2CPSC42	42 INCH SCL VAULT CA	1.00	7.00 EA	1,400.000		9,800				9,800
2CPVSLAB	PRECAST VAULT LID SL	1.00	7.00 EA	1,000.000		7,000				7,000
2CR040	4000LB READY MIX	1.00	14.00 CY	121.150		1,696				1,696
4SAWC	Sawcutting	1.00	7.00 EA	0.680					5	5
8BA310A	418 Backhoe W/Attachme	1.00	56.00 HR	51.051				2,859		2,859
8EX100	100 Excavator	1.00	56.00 HR	52.300				2,929		2,929
FOCI	Civil Forman	1.00	56.00 MH	77.060	5,636					5,636
LAG	General Laborer	2.00	112.00 MH	52.910	7,813					7,813
OPE	Operator - Excavator	1.00	56.00 MH	74.560	5,457					5,457
\$43,195.11	32.0000 MH/EA		224.00 MH	[2265.473]	18,907	18,496		5,788	5	43,195
=====> Item Totals: 601 - ENLARGED VAULT ROOF OPENING										
\$43,195.11	32.0000 MH/EA		224.00 MH	[2265.473]	18,907	18,496		5,788	5	43,195
6,170.730	7 EA				2,700.94	2,642.30		826.81	0.68	6,170.73

BID ITEM = 602	CLIENT# = 602		Land Item	SCHEDULE: 1 100						
Description =	VAULT 133M013 ACCESS MODIFICATION		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
602.01 VAULT 133M013 ACCESS MODIFICATION										
			Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		16.00 CH	Prod:	16.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
2CPSC42	42 INCH SCL VAULT CA	1.00	1.00 EA	1,400.000		1,400				1,400
2CPVSLAB	PRECAST VAULT LID SL	1.00	1.00 EA	1,000.000		1,000				1,000
8BA310A	418 Backhoe W/Attachme	1.00	16.00 HR	51.051				817		817
8EX100	100 Excavator	1.00	16.00 HR	52.300				837		837
FOCI	Civil Forman	1.00	16.00 MH	77.060	1,610					1,610
LAG	General Laborer	2.00	32.00 MH	52.910	2,232					2,232
OPE	Operator - Excavator	1.00	16.00 MH	74.560	1,559					1,559
\$9,455.49	64.0000 MH/EA		64.00 MH	[4530.95]	5,402	2,400		1,654		9,455
=====> Item Totals: 602 - VAULT 133M013 ACCESS MODIFICATION										
\$9,455.49	64.0000 MH/EA		64.00 MH	[4530.95]	5,402	2,400		1,654		9,455
9,455.490	1 EA				5,401.89	2,400.00		1,653.60		9,455.49

BID ITEM = 603	CLIENT# = 603		Land Item	SCHEDULE: 1 100						
Description =	REPLACE ACCESS FRAME AND COVER		Unit =	EA	Takeoff Quan:		17.000	Engr Quan:		17.000
603.01 REPLACE ACCESS FRAME AND COVER										
			Quan:	17.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		17.00 CH	Prod:	17.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
2CPSC42	42 INCH SCL VAULT CA	1.00	17.00 EA	1,400.000		23,800				23,800

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 603	CLIENT# = 603									
Description =	REPLACE ACCESS FRAME AND COVER		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	17.000	Engr Quan:		17.000
8BA310A	418 Backhoe W/Attachme	1.00	17.00 HR	51.051				868		868
8EX100	100 Excavator	1.00	17.00 HR	52.300				889		889
FOCI	Civil Forman	1.00	17.00 MH	77.060	1,711					1,711
LAG	General Laborer	2.00	34.00 MH	52.910	2,372					2,372
OPE	Operator - Excavator	1.00	17.00 MH	74.560	1,657					1,657
\$31,296.45	4.0000 MH/EA		68.00 MH	[283.184]	5,740	23,800		1,757		31,296
====> Item Totals:	603	- REPLACE ACCESS FRAME AND COVER								
\$31,296.45	4.0000 MH/EA		68.00 MH	[283.184]	5,740	23,800		1,757		31,296
1,840.968	17 EA				337.62	1,400.00		103.35		1,840.97

BID ITEM = 604	CLIENT# = 604									
Description =	SCL VAULT, 444-LA		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	1.000	Engr Quan:		1.000
604.01	SCL VAULT, 444-LA		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>EAS</u>	Earthwork 4 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
2CRCDF	CDF	1.00	10.00 CY	106.150	1,062					1,062
3DEDU02D	Dirt Trucking and Dump	1.00	12.00 TCY	24.500		294				294
4ELEC	Electrical sub	1.00	1.00 EA	15,000.000				15,000		15,000
8BA310A	418 Backhoe W/Attachme	1.00	8.00 HR	51.051				408		408
8EX100	100 Excavator	1.00	8.00 HR	52.300				418		418
FOCI	Civil Forman	1.00	8.00 MH	77.060	805					805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780					780
\$19,883.25	32.0000 MH/EA		32.00 MH	[2265.48]	2,701	1,062	294	827	15,000	19,883
====> Item Totals:	604	- SCL VAULT, 444-LA								
\$19,883.25	32.0000 MH/EA		32.00 MH	[2265.48]	2,701	1,062	294	827	15,000	19,883
19,883.250	1 EA				2,700.95	1,061.50	294.00	826.80	15,000.00	19,883.25

BID ITEM = 605	CLIENT# = 605									
Description =	SCL VAULT, 712-LA		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	1.000	Engr Quan:		1.000
605.01	SCL VAULT, 712-LA		Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG
<u>EAS</u>	Earthwork 4 Man Crew		12.00 CH	Prod:	12.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
2CRCDF	CDF	1.00	71.00 CY	106.150	7,537					7,537
3DEDU02D	Dirt Trucking and Dump	1.00	133.00 TCY	24.500		3,259				3,259
4ELEC	Electrical sub	1.00	1.00 EA	25,000.000				25,000		25,000
8BA310A	418 Backhoe W/Attachme	1.00	12.00 HR	51.051				613		613
8EX100	100 Excavator	1.00	12.00 HR	52.300				628		628
FOCI	Civil Forman	1.00	12.00 MH	77.060	1,208					1,208
LAG	General Laborer	2.00	24.00 MH	52.910	1,674					1,674
OPE	Operator - Excavator	1.00	12.00 MH	74.560	1,169					1,169
\$41,086.76	48.0000 MH/EA		48.00 MH	[3398.2]	4,051	7,537	3,259	1,240	25,000	41,087
====> Item Totals:	605	- SCL VAULT, 712-LA								
\$41,086.76	48.0000 MH/EA		48.00 MH	[3398.2]	4,051	7,537	3,259	1,240	25,000	41,087
41,086.760	1 EA				4,051.41	7,536.65	3,258.50	1,240.20	25,000.00	41,086.76

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 606	CLIENT# = 606									
Description =	CONSTRUCTION SURVEYING-ADDITIVE		Land Item Unit =	SCHEDULE: 1 100						
				LS	Takeoff Quan:	1.000		Engr Quan:		1.000
606.01	CONSTRUCTION SURVEYING-ADDITIVE	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
4SURV	Surveying sub	1.00	1.00 LS	4,850.000				4,850		4,850
BID ITEM = 607	CLIENT# = 607									
Description =	CRITICAL PATH SCHEDULE UPDATE, MIN. BID		Land Item Unit =	SCHEDULE: 1 100						
				EA	Takeoff Quan:	1.000		Engr Quan:		1.000
607.01	CRITICAL PATH SCHEDULE UPDATE, MIN. BID	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
3CPM	CPM SCHEDULE UPDAT	1.00	1.00 EA	2,500.000			2,500			2,500
====>	Item Totals:	607	- CRITICAL PATH SCHEDULE UPDATE, MIN. BID							
\$2,500.00				[]			2,500			2,500
2,500.000		1 EA					2,500.00			2,500.00
BID ITEM = 608	CLIENT# = 608									
Description =	MOBILIZATION-SCHEDULE 3		Land Item Unit =	SCHEDULE: 1 100						
				LS	Takeoff Quan:	1.000		Engr Quan:		1.000
608.01	MOBILIZATION-SCHEDULE 3	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
3ADOHML	ADDITIVE MANAGMEN	1.00	1.00 LS	26,530.000			26,530			26,530
3ADOHPA	ADDITIVE PROJECT AD	1.00	1.00 LS	79,000.000			79,000			79,000
3ADOHPM	ADDITIVE PROJECT MA	1.00	1.00 LS	131,279.000			131,279			131,279
3ADOHVC	ADDITIVE VEHICLE COS	1.00	1.00 LS	95,000.000			95,000			95,000
3ADOHVF	ADDITIVE VEHICLE FUE	1.00	1.00 LS	32,000.000			32,000			32,000
3ADPHTR	ADDITIVE PROJECT TR	1.00	1.00 LS	24,144.000			24,144			24,144
\$387,953.00				[]			387,953			387,953
608.02	ADDITIVE CIVIL SUPERINTENDENTS	Quan:	120.00 SHIF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
ZSUP	==> Superintendent	1.00	640.00 MH	72.000	59,100					59,100
\$59,100.42	5.3333 MH/SHIF		640.00 MH	[384]	59,100					59,100
608.03	ADDITIVE CONCRETE SUPERINTENDENTS	Quan:	80.00 SHIF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
ZSUP	==> Superintendent	1.00	640.00 MH	72.000	59,100					59,100
\$59,100.42	8.0000 MH/SHIF		640.00 MH	[576]	59,100					59,100
608.04	ADDITIVE FIELD ENGINEERING	Quan:	80.00 SHIF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
ZENF	==> Field Engineer	1.00	640.00 MH	57.820	44,363					44,363
\$44,363.08	8.0000 MH/SHIF		640.00 MH	[462.56]	44,363					44,363
608.05	ADDITIVE MINI EX	Quan:	40.00 SHIF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
8EX035	==> 35 Excavator	1.00	320.00 HR	28.830				9,226		9,226
608.06	WATER TRUCK	Quan:	20.00 SHIF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
8TRW	==> Water Truck	1.00	160.00 HR	70.000				11,200		11,200
608.07	SUB MOB	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 608	CLIENT# = 608		Land Item	SCHEDULE: 1	100					
Description =	MOBILIZATION-SCHEDULE 3		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
4LAND	Landscape sub	1.00	1.00 LS	0.001						
=====> Item Totals: 608 - MOBILIZATION-SCHEDULE 3										
\$570,942.52	1,920.0000 MH/LS		1,920.00 MH	[129164.8]	162,564		387,953	20,426		570,943
570,942.520	1 LS				162,563.92		387,953.00	20,425.60		570,942.52

BID ITEM = 609	CLIENT# = 609		Land Item	SCHEDULE: 1	100					
Description =	MAINTENANCE AND PROTECTION OF TRAFFIC CO		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000
609.01	ADDITIVE TCS		Quan:	48.00 SHIF	Hrs/Shft:	10.00	Cal: 710	WC: WAAVG		
LAFT	==> Traffic Control Supervi	1.00	640.00 MH	52.810	51,862					51,862
\$51,862.26	13.3333 MH/SHIF		640.00 MH	[905.304]	51,862					51,862
609.02	ADDITIVE FLAGGERS		Quan:	48.00 SHIF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
LAF	==> Flager	1.00	480.00 MH	44.840	28,531					28,531
\$28,530.73	10.0000 MH/SHIF		480.00 MH	[493.24]	28,531					28,531
=====> Item Totals: 609 - MAINTENANCE AND PROTECTION OF TRAFFIC CO										
\$80,392.99	1,120.0000 MH/LS		1,120.00 MH	[67130.12]	80,393					80,393
80,392.990	1 LS				80,392.99					80,392.99

BID ITEM = 610	CLIENT# = 610		Land Item	SCHEDULE: 1	100					
Description =	CLEARING & GRUBBING		Unit =	SF	Takeoff Quan:		800.000	Engr Quan:		800.000
610.01	CLEARING & GRUBBING		Quan:	89.00 SY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		1.40 CH	Prod:	1.4000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
3DEDU02S	SOD DISPOSAL	1.00	17.00 TCY	28.000		476				476
8BA310A	418 Backhoe W/Attachme	1.00	1.40 HR	51.051			71			71
8EX100	100 Excavator	1.00	1.40 HR	52.300			73			73
FOCI	Civil Forman	1.00	1.40 MH	77.060	141					141
LAG	General Laborer	2.00	2.80 MH	52.910	195					195
OPE	Operator - Excavator	1.00	1.40 MH	74.560	136					136
\$1,093.33	0.0629 MH/SY		5.60 MH	[4.454]	473	476	145			1,093
=====> Item Totals: 610 - CLEARING & GRUBBING										
\$1,093.33	0.0070 MH/SF		5.60 MH	[0.496]	473	476	145			1,093
1.367	800 SF				0.59	0.60	0.18			1.37

BID ITEM = 611	CLIENT# = 611		Land Item	SCHEDULE: 1	100					
Description =	REMOVE CEMENT CONCRETE SIDEWALK		Unit =	SY	Takeoff Quan:		500.000	Engr Quan:		500.000
611.01	REMOVE CEMENT CONCRETE SIDEWALK		Quan:	500.00 SY	Hrs/Shft:	10.00	Cal: 610	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		21.00 CH	Prod:	21.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
3DEDU02C	Concrete Trucking and Du	1.00	106.00 TCY	29.000		3,074				3,074
8BA310A	418 Backhoe W/Attachme	1.00	21.00 HR	51.051			1,072			1,072
8EX100	100 Excavator	1.00	21.00 HR	52.300			1,098			1,098
FOCI	Civil Forman	1.00	21.00 MH	77.060	2,239					2,239

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM	= 611	CLIENT# = 611		Land Item	SCHEDULE: 1	100				
Description =	REMOVE CEMENT CONCRETE SIDEWALK		Unit =	SY	Takeoff	Quan:	500.000	Engr	Quan:	500.000
LAG	General Laborer	2.00	42.00 MH	52.910	3,102					3,102
OPE	Operator - Excavator	1.00	21.00 MH	74.560	2,168					2,168
\$12,753.59	0.1680 MH/SY		84.00 MH	[12.615]	7,509		3,074	2,170		12,754
611.02	GRADING SIDEWALKS			Quan:	500.00 SY	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>EAS</u>	Earthwork 4 Man Crew		8.00 CH	Prod:	8.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	8.00 HR	51.051				408		408
8EX100	100 Excavator	1.00	8.00 HR	52.300				418		418
FOCI	Civil Forman	1.00	8.00 MH	77.060	805					805
LAG	General Laborer	2.00	16.00 MH	52.910	1,116					1,116
OPE	Operator - Excavator	1.00	8.00 MH	74.560	780					780
\$3,527.75	0.0640 MH/SY		32.00 MH	[4.531]	2,701			827		3,528
====>	Item Totals:	611	- REMOVE CEMENT CONCRETE SIDEWALK							
\$16,281.34	0.2320 MH/SY		116.00 MH	[17.146]	10,210		3,074	2,997		16,281
32.563	500 SY				20.42		6.15	5.99		32.56
BID ITEM	= 612	CLIENT# = 612		Land Item	SCHEDULE: 1	100				
Description =	REMOVE PAVEMENT		Unit =	SY	Takeoff	Quan:	3,108.000	Engr	Quan:	3,108.000
612.01	REMOVE PAVEMENT			Quan:	3,108.00 SY	Hrs/Shft:	10.00	Cal:	610	WC: WAAVG
<u>DEM</u>	Demo 5 Man Crew		95.77 CH	Prod:	95.7734 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
3DEDU02C	Concrete Trucking and Du	1.00	2,010.00 TCY	29.000		58,290				58,290
8EX135A	135 Excavator W/Attach	1.00	95.77 HR	68.251				6,536		6,536
8EX200	200 Excavator	1.00	95.77 HR	78.000				7,470		7,470
8LO950	950 Loader	1.00	95.77 HR	81.500				7,805		7,805
FOCI	Civil Forman	1.00	95.77 MH	77.060	10,211					10,211
LAG	General Laborer	2.00	191.55 MH	52.910	14,149					14,149
OPE	Operator - Excavator	2.00	191.55 MH	74.560	19,774					19,774
\$124,235.73	0.1540 MH/SY		478.87 MH	[11.936]	44,134	58,290		21,812		124,236
====>	Item Totals:	612	- REMOVE PAVEMENT							
\$124,235.73	0.1540 MH/SY		478.87 MH	[11.936]	44,134	58,290		21,812		124,236
39.973	3108 SY				14.20	18.75		7.02		39.97
BID ITEM	= 613	CLIENT# = 613		Land Item	SCHEDULE: 1	100				
Description =	REMOVE PAVEMENT, OVER 14 INCH DEPTH, INC		Unit =	SY	Takeoff	Quan:	1,242.000	Engr	Quan:	1,242.000
613.01	REMOVE PAVEMENT, OVER 14 INCH DEPTH, IN			Quan:	1,242.00 SY	Hrs/Shft:	10.00	Cal:	610	WC: WAAVG
<u>DEM</u>	Demo 5 Man Crew		74.42 CH	Prod:	74.4270 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
3DEDU02C	Concrete Trucking and Du	1.00	1,238.00 TCY	29.000		35,902				35,902
3RAILDIS	DISPOSAL OF RAIL	1.00	2,211.88 LF	2.000		4,424				4,424
3TIEDIS	DISPOSAL RAIL TIE	1.00	552.78 LF	2.000		1,106				1,106
8EX135A	135 Excavator W/Attach	1.00	74.43 HR	68.251				5,080		5,080
8EX200	200 Excavator	1.00	74.43 HR	78.000				5,806		5,806
8LO950	950 Loader	1.00	74.43 HR	81.500				6,066		6,066
FOCI	Civil Forman	1.00	74.43 MH	77.060	7,936					7,936
LAG	General Laborer	2.00	148.85 MH	52.910	10,995					10,995
OPE	Operator - Excavator	2.00	148.85 MH	74.560	15,366					15,366
\$92,679.51	0.2996 MH/SY		372.13 MH	[23.211]	34,297	41,431		16,951		92,680

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 613	CLIENT# = 613		Land Item	SCHEDULE: 1	100				
Description =	REMOVE PAVEMENT, OVER 14 INCH DEPTH, INC		Unit =	SY	Takeoff Quan:	1,242.000	Engr Quan:		1,242.000
====>	Item Totals: 613 - REMOVE PAVEMENT, OVER 14 INCH DEPTH, INC								
\$92,679.51	0.2996 MH/SY	372.13	MH	[23.211]	34,297	41,431	16,951		92,680
74.621	1242 SY				27.61	33.36	13.65		74.62

BID ITEM = 614	CLIENT# = 614		Land Item	SCHEDULE: 1	100				
Description =	REMOVE PIPE		Unit =	LF	Takeoff Quan:	325.000	Engr Quan:		325.000
614.01 REMOVE PIPE			Quan:	325.00 LF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG		
<u>UNS</u>	Underground Utilities 4 Man		22.00	CH	Prod: 22.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
3PIPEDIS	PIPE DISPOSAL	1.00	325.00	LF	2.000	650			650
8BA310A	418 Backhoe W/Attachme	1.00	22.00	HR	51.051		1,123		1,123
8EX100	100 Excavator	1.00	22.00	HR	52.300		1,151		1,151
FOCI	Civil Forman	1.00	22.00	MH	77.060	2,214			2,214
LAP	Labor Underground Water	1.00	22.00	MH	53.880	1,562			1,562
OPB	Operator - Backhoe	1.00	22.00	MH	74.560	2,144			2,144
OPE	Operator - Excavator	1.00	22.00	MH	74.560	2,144			2,144
\$10,987.77	0.2707 MH/LF	88.00	MH	[20.854]	8,064	650	2,274		10,988
====>	Item Totals: 614 - REMOVE PIPE								
\$10,987.77	0.2707 MH/LF	88.00	MH	[20.854]	8,064	650	2,274		10,988
33.809	325 LF				24.81	2.00	7.00		33.81

BID ITEM = 615	CLIENT# = 615		Land Item	SCHEDULE: 1	100				
Description =	REMOVE GATE VALVE		Unit =	EA	Takeoff Quan:	3.000	Engr Quan:		3.000
615.01 REMOVE GATE VALVE			Quan:	3.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG		
<u>UNM</u>	Unerground Utilities 6 Man		3.00	CH	Prod: 3.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
8EX135A	135 Excavator W/Attach	1.00	3.00	HR	68.251		205		205
8EX200	200 Excavator	1.00	3.00	HR	78.000		234		234
8LO950	950 Loader	1.00	3.00	HR	81.500		244		244
FOCI	Civil Forman	1.00	3.00	MH	77.060	302			302
LAP	Labor Underground Water	2.00	6.00	MH	53.880	426			426
OPE	Operator - Excavator	1.00	3.00	MH	74.560	292			292
OPL	Operator - Loader	1.00	3.00	MH	74.560	292			292
\$1,995.88	5.0000 MH/EA	15.00	MH	[367.337]	1,313		683		1,996
====>	Item Totals: 615 - REMOVE GATE VALVE								
\$1,995.88	5.0000 MH/EA	15.00	MH	[367.337]	1,313		683		1,996
665.293	3 EA				437.55		227.74		665.29

BID ITEM = 616	CLIENT# = 616		Land Item	SCHEDULE: 1	100				
Description =	REMOVE HYDRANT		Unit =	EA	Takeoff Quan:	1.000	Engr Quan:		1.000
616.01 REMOVE HYDRANT			Quan:	1.00 EA	Hrs/Shft: 10.00	Cal: 610	WC: WAAVG		
<u>UNS</u>	Underground Utilities 4 Man		3.00	CH	Prod: 3.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	3.00	HR	51.051		153		153
8EX100	100 Excavator	1.00	3.00	HR	52.300		157		157
FOCI	Civil Forman	1.00	3.00	MH	77.060	320			320

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 616	CLIENT# = 616									
Description =	REMOVE HYDRANT			Land Item Unit =	SCHEDULE: 1 100					
				EA	Takeoff Quan:		1.000	Engr Quan:		1.000
LAP	Labor Underground Water	1.00	3.00 MH	53.880	226					226
OPB	Operator - Backhoe	1.00	3.00 MH	74.560	310					310
OPE	Operator - Excavator	1.00	3.00 MH	74.560	310					310
\$1,474.84	12.0000 MH/EA		12.00 MH	[980.25]	1,165			310		1,475
=====>	Item Totals: 616 - REMOVE HYDRANT									
\$1,474.84	12.0000 MH/EA		12.00 MH	[980.25]	1,165			310		1,475
1,474.840	1 EA				1,164.81			310.03		1,474.84

BID ITEM = 617	CLIENT# = 617									
Description =	REMOVE PAVEMENT RAIL AND CAR SYSTEM			Land Item Unit =	SCHEDULE: 1 100					
				SY	Takeoff Quan:		360.000	Engr Quan:		360.000
617.01	REMOVE PAVEMENT RAIL AND CAR SYSTEM			Quan:	360.00 SY	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
DEM	Demo 5 Man Crew		33.50 CH	Prod:	33.5000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
3DEDU02C	Concrete Trucking and Du	1.00	344.00 TCY	29.000		9,976			9,976	
3RAILDIS	DISPOSAL OF RAIL	1.00	720.00 LF	2.000		1,440			1,440	
3TIEDIS	DISPOSAL RAIL TIE	1.00	360.00 LF	2.000		720			720	
8EX135A	135 Excavator W/Attach	1.00	33.50 HR	68.251			2,286		2,286	
8EX200	200 Excavator	1.00	33.50 HR	78.000			2,613		2,613	
8LO950	950 Loader	1.00	33.50 HR	81.500			2,730		2,730	
FOCI	Civil Forman	1.00	33.50 MH	77.060	3,372				3,372	
LAG	General Laborer	2.00	67.00 MH	52.910	4,674				4,674	
OPE	Operator - Excavator	2.00	67.00 MH	74.560	6,529				6,529	
\$34,340.41	0.4652 MH/SY		167.50 MH	[33.984]	14,575		12,136	7,630		34,340
=====>	Item Totals: 617 - REMOVE PAVEMENT RAIL AND CAR SYSTEM									
\$34,340.41	0.4652 MH/SY		167.50 MH	[33.984]	14,575		12,136	7,630		34,340
95.390	360 SY				40.49		33.71	21.19		95.39

BID ITEM = 618	CLIENT# = 618									
Description =	REMOVE TREE			Land Item Unit =	SCHEDULE: 1 100					
				EA	Takeoff Quan:		3.000	Engr Quan:		3.000
618.01	REMOVE TREE			Quan:	3.00 EA	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
3TREEREM	TREE REMOVAL	1.00	3.00 EA	2,350.000			7,050			7,050
=====>	Item Totals: 618 - REMOVE TREE									
\$7,050.00				[]			7,050			7,050
2,350.000	3 EA						2,350.00			2,350.00

BID ITEM = 619	CLIENT# = 619									
Description =	REMOVE VALVE CHAMBER			Land Item Unit =	SCHEDULE: 1 100					
				EA	Takeoff Quan:		2.000	Engr Quan:		2.000
619.01	REMOVE VALVE CHAMBER			Quan:	2.00 EA	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
UNM	Unerground Utilities 6 Man		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
8EX135A	135 Excavator W/Attach	1.00	4.00 HR	68.251			273		273	
8EX200	200 Excavator	1.00	4.00 HR	78.000			312		312	
8LO950	950 Loader	1.00	4.00 HR	81.500			326		326	
FOCI	Civil Forman	1.00	4.00 MH	77.060	403				403	

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 619	CLIENT# = 619			Land Item	SCHEDULE: 1	100				
Description =	REMOVE VALVE CHAMBER		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
LAP	Labor Underground Water	2.00	8.00 MH	53.880	568					568
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390					390
OPL	Operator - Loader	1.00	4.00 MH	74.560	390					390
\$2,661.19	10.0000 MH/EA		20.00 MH	[734.66]	1,750			911		2,661
=====>	Item Totals: 619 - REMOVE VALVE CHAMBER									
\$2,661.19	10.0000 MH/EA		20.00 MH	[734.66]	1,750			911		2,661
1,330.595	2 EA				875.10			455.50		1,330.60

BID ITEM = 620	CLIENT# = 620			Land Item	SCHEDULE: 1	100				
Description =	SAWCUT RIGID PAVEMENT, FULL DEPTH		Unit =	LF	Takeoff Quan:		234.000	Engr Quan:		234.000
620	SAWCUT RIGID PAVEMENT, FULL DEPTH		Quan:	3,954.34	INFT	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
4SAWC	Sawcutting	1.00	3,954.34 INFT	0.680				2,689		2,689

BID ITEM = 621	CLIENT# = 621			Land Item	SCHEDULE: 1	100				
Description =	ABANDON VALVE CHAMBER		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
621.01	ABANDON VALVE CHAMBER		Quan:	1.00	EA	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>UNM</u>	Underground Utilities 6 Man		1.00 CH	Prod:	1.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2AGS17	SEATTLE TYPE 1@110.2	1.00	2.00 TON	25.750		57				57
8EX135A	135 Excavator W/Attach	1.00	1.00 HR	68.251				68		68
8EX200	200 Excavator	1.00	1.00 HR	78.000				78		78
8LO950	950 Loader	1.00	1.00 HR	81.500				81		81
FOCI	Civil Forman	1.00	1.00 MH	77.060	101					101
LAP	Labor Underground Water	2.00	2.00 MH	53.880	142					142
OPE	Operator - Excavator	1.00	1.00 MH	74.560	97					97
OPL	Operator - Loader	1.00	1.00 MH	74.560	97					97
\$722.07	5.0000 MH/EA		5.00 MH	[367.35]	438	57		228		722
=====>	Item Totals: 621 - ABANDON VALVE CHAMBER									
\$722.07	5.0000 MH/EA		5.00 MH	[367.35]	438	57		228		722
722.070	1 EA				437.56	56.78		227.73		722.07

BID ITEM = 623	CLIENT# = 623			Land Item	SCHEDULE: 1	100				
Description =	REMOVE, STORE AND REINSTALL MOSAIC TILE		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
623.01	REMOVE, STORE AND REINSTALL MOSAIC TIL		Quan:	1.00	EA	Hrs/Shft:	10.00	Cal:	510	WC: WAAVG
<u>EAS</u>	Earthwork 4 Man Crew		1.50 CH	Prod:	1.5000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	1.50 HR	51.051				77		77
8EX100	100 Excavator	1.00	1.50 HR	52.300				78		78
FOCI	Civil Forman	1.00	1.50 MH	77.060	151					151
LAG	General Laborer	2.00	3.00 MH	52.910	209					209
OPE	Operator - Excavator	1.00	1.50 MH	74.560	146					146
\$661.45	6.0000 MH/EA		6.00 MH	[424.77]	506			155		661
=====>	Item Totals: 623 - REMOVE, STORE AND REINSTALL MOSAIC TILE									
\$661.45	6.0000 MH/EA		6.00 MH	[424.77]	506			155		661

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 623	CLIENT# = 623		Land Item	SCHEDULE: 1	100					
Description =	REMOVE, STORE AND REINSTALL MOSAIC TILE		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
661.450	1 EA				506.44			155.01		661.45

BID ITEM = 624	CLIENT# = 624		Land Item	SCHEDULE: 1	100					
Description =	REMOVE CURB, GRANITE W/ SALVAGE		Unit =	LF	Takeoff Quan:		730.000	Engr Quan:		730.000

624.01 REMOVE CURB, GRANITE W/ SALVAGE Quan: 730.00 LF Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		37.00	CH	Prod:	37.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	37.00	HR	51.051			1,889		1,889
8EX100	100 Excavator	1.00	37.00	HR	52.300			1,935		1,935
FOCI	Civil Forman	1.00	37.00	MH	77.060	3,724				3,724
LAG	General Laborer	2.00	74.00	MH	52.910	5,162				5,162
OPE	Operator - Excavator	1.00	37.00	MH	74.560	3,606				3,606
\$16,315.83	0.2027 MH/LF		148.00	MH	[14.353]	12,492		3,824		16,316

====> Item Totals: 624 - REMOVE CURB, GRANITE W/ SALVAGE										
\$16,315.83	0.2027 MH/LF		148.00	MH	[14.353]	12,492		3,824		16,316
22.350	730 LF					17.11		5.24		22.35

BID ITEM = 625	CLIENT# = 625		Land Item	SCHEDULE: 1	100					
Description =	COMMON EXCAVATION		Unit =	CY	Takeoff Quan:		794.000	Engr Quan:		794.000

625.01 COMMON EXCAVATION Quan: 794.00 CY Hrs/Shift: 10.00 Cal: 610 WC: WAAVG

<u>GRM</u>	Grading 5 Man Crew		34.00	CH	Prod:	34.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	4.00
3DEDU02D	Dirt Trucking and Dump	1.00	952.19	TCY	24.500		23,329			23,329
8DO0450	JD 450 Dozer	1.00	34.00	HR	49.500			1,683		1,683
8EX135A	135 Excavator W/Attach	1.00	34.00	HR	68.251			2,321		2,321
8EX200	200 Excavator	1.00	34.00	HR	78.000			2,652		2,652
8RO84	84 Inch Roller	1.00	34.00	HR	55.700			1,894		1,894
FOCI	Civil Forman	1.00	34.00	MH	77.060	3,625				3,625
LAG	General Laborer	2.00	68.00	MH	52.910	5,023				5,023
OPE	Operator - Excavator	2.00	68.00	MH	74.560	7,020				7,020
\$47,545.71	0.2141 MH/CY		170.00	MH	[16.587]	15,668	23,329	8,549		47,546

====> Item Totals: 625 - COMMON EXCAVATION										
\$47,545.71	0.2141 MH/CY		170.00	MH	[16.587]	15,668	23,329	8,549		47,546
59.881	794 CY					19.73	29.38	10.77		59.88

BID ITEM = 626	CLIENT# = 626		Land Item	SCHEDULE: 1	100					
Description =	SAFETY SYSTEMS IN TRENCH EXCAVATION, MIN		Unit =	SF	Takeoff Quan:		364.000	Engr Quan:		364.000

626.01 SAFETY SYSTEMS IN TRENCH EXCAVATION, M Quan: 364.00 SF Hrs/Shift: 10.00 Cal: 510 WC: WAAVG

3SHOR	SHORING ADDITIVE	1.00	1.00	LS	5,000.000		5,000			5,000
-------	------------------	------	------	----	-----------	--	-------	--	--	-------

====> Item Totals: 626 - SAFETY SYSTEMS IN TRENCH EXCAVATION, MIN										
\$5,000.00					[]		5,000			5,000
13.736	364 SF						13.74			13.74

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----------------	------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = **627** CLIENT# = 627 Land Item SCHEDULE: 1 100
Description = MINERAL AGGREGATE, TYPE 2 Unit = TN Takeoff Quan: 1,456.000 Engr Quan: 1,456.000

627.01 MINERAL AGGREGATE, TYPE 2 Quan: 1,456.00 TN Hrs/Shft: 10.00 Cal: 610 WC: WAAVG

<u>GRM</u>	Grading 5 Man Crew		48.00	CH	Prod:	48.0000	CH	Lab Pcs:	5.00	Eqp Pcs:	4.00
2AGS02	SEATTLE TYPE 2@110.2	1.00	1,456.00	TON	29.750		47,756				47,756
8DO0450	JD 450 Dozer	1.00	48.00	HR	49.500			2,376			2,376
8EX135A	135 Excavator W/Attach	1.00	48.00	HR	68.251			3,276			3,276
8EX200	200 Excavator	1.00	48.00	HR	78.000			3,744			3,744
8RO84	84 Inch Roller	1.00	48.00	HR	55.700			2,674			2,674
FOCI	Civil Forman	1.00	48.00	MH	77.060	5,118					5,118
LAG	General Laborer	2.00	96.00	MH	52.910	7,091					7,091
OPE	Operator - Excavator	2.00	96.00	MH	74.560	9,910					9,910
\$81,944.66	0.1648 MH/TN		240.00	MH	[12.77]	22,119	47,756		12,070		81,945

====> **Item Totals: 627 - MINERAL AGGREGATE, TYPE 2**
\$81,944.66 0.1648 MH/TN 240.00 MH [12.77] 22,119 47,756 12,070 **81,945**
56.281 1456 TN 15.19 32.80 8.29 56.28

BID ITEM = **628** CLIENT# = 628 Land Item SCHEDULE: 1 100
Description = MINERAL AGGREGATE, TYPE 17 Unit = TN Takeoff Quan: 107.000 Engr Quan: 107.000

628.01 MINERAL AGGREGATE, TYPE 17 Quan: 107.00 TN Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

2AGS17	SEATTLE TYPE 1@110.2	1.00	107.00	TON	25.750		3,038				3,038
3DEDU02D	Dirt Trucking and Dump	1.00	75.19	TCY	24.500			1,842			1,842
\$4,879.82					[]		3,038	1,842			4,880

====> **Item Totals: 628 - MINERAL AGGREGATE, TYPE 17**
\$4,879.82 [] 3,038 1,842 **4,880**
45.606 107 TN 28.39 17.22 45.61

BID ITEM = **629** CLIENT# = 629 Land Item SCHEDULE: 1 100
Description = MINERAL AGGREGATE, TYPE 9 Unit = CY Takeoff Quan: 3.000 Engr Quan: 3.000

629.01 MINERAL AGGREGATE, TYPE 9 Quan: 3.00 CY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		0.50	CH	Prod:	0.5000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	0.50	HR	51.051			26			26
8EX100	100 Excavator	1.00	0.50	HR	52.300			26			26
FOCI	Civil Forman	1.00	0.50	MH	77.060	50					50
LAG	General Laborer	2.00	1.00	MH	52.910	70					70
OPE	Operator - Excavator	1.00	0.50	MH	74.560	49					49
\$220.47	0.6666 MH/CY		2.00	MH	[47.197]	169			52		220

====> **Item Totals: 629 - MINERAL AGGREGATE, TYPE 9**
\$220.47 0.6666 MH/CY 2.00 MH [47.197] 169 52 **220**
73.490 3 CY 56.27 17.22 73.49

BID ITEM = **630** CLIENT# = 630 Land Item SCHEDULE: 1 100
Description = PAVEMENT PATCH, TEMPORARY Unit = TN Takeoff Quan: 30.000 Engr Quan: 30.000

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
----------------------	------	-----	------------------	--------------	-------	------------------	--------------------	---------------	------------------	-------

BID ITEM = 630 CLIENT# = 630 Land Item SCHEDULE: 1 100
Description = PAVEMENT PATCH, TEMPORARY Unit = TN Takeoff Quan: 30.000 Engr Quan: 30.000

630.01 PAVEMENT PATCH, TEMPORARY Quan: 30.00 TN Hrs/Shft: 10.00 Cal: X10 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew		5.00	CH	Prod:	5.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
3COLDMIX	COLD MIX	1.00	30.00	TN	110.000			3,300			3,300
3DEDU02A	Asphalt trucking and Dump	1.00	30.00	TCY	29.000			870			870
8BA310A	418 Backhoe W/Attachme	1.00	5.00	HR	51.051				255		255
8EX100	100 Excavator	1.00	5.00	HR	52.300				261		261
FOCI	Civil Forman	1.00	5.00	MH	77.060	906					906
LAG	General Laborer	2.00	10.00	MH	52.910	1,251					1,251
OPE	Operator - Excavator	1.00	5.00	MH	74.560	877					877
\$7,721.80	0.6666 MH/TN		20.00	MH	[85.813]	3,035		4,170	517		7,722

====> **Item Totals: 630 - PAVEMENT PATCH, TEMPORARY**
 \$7,721.80 0.6666 MH/TN 20.00 MH [85.813] 3,035 4,170 517 **7,722**
 257.393 30 TN 101.17 139.00 17.22 257.39

BID ITEM = 631 CLIENT# = 631 Land Item SCHEDULE: 1 100
Description = ROADWAY CEM CONC, VARIABLE MIXES, 12 IN Unit = SY Takeoff Quan: 2,939.000 Engr Quan: 2,939.000

631.01 ROADWAY CEM CONC, VARIABLE MIXES, 12 IN Quan: 2,939.00 SY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COL</u>	Concrete 9 Man Crew		156.00	CH	Prod:	156.0000	CH	Lab Pcs:	9.00	Eqp Pcs:	0.00
2CRP3D	3 DAY PAVING M@110.2	1.02	999.26	CY	125.150	137,876					137,876
2DOWEL	DOWELS@110.25%	1.00	2,957.00	LF	15.750	51,346					51,346
2JOINT	JOINT MATERIAL@110.2	1.00	1,332.00	LF	2.750	4,038					4,038
2TIEBAR	TIE BARS@110.25%	1.00	444.00	EA	2.940	1,439					1,439
3SAWSEAL	SAWING AND SEALING	1.00	2,957.00	LF	3.680		10,882				10,882
CEJ	Cement Mason	8.00	1,248.00	MH	64.980	106,326					106,326
FOCO	Concrete Forman	1.00	156.00	MH	68.980	14,089					14,089
\$325,996.93	0.4777 MH/SY		1,404.00	MH	[34.38]	120,415	194,700	10,882			325,997

====> **Item Totals: 631 - ROADWAY CEM CONC, VARIABLE MIXES, 12 IN**
 \$325,996.93 0.4777 MH/SY 1,404.00 MH [34.38] 120,415 194,700 10,882 **325,997**
 110.921 2939 SY 40.97 66.25 3.70 110.92

BID ITEM = 632 CLIENT# = 632 Land Item SCHEDULE: 1 100
Description = ROADWAY CEM CONC, HES (24 HR), 12 IN Unit = SY Takeoff Quan: 1,686.000 Engr Quan: 1,686.000

632.01 ROADWAY CEM CONC, HES (24 HR), 12 IN Quan: 1,686.00 SY Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>COL</u>	Concrete 9 Man Crew		89.92	CH	Prod:	89.9200	CH	Lab Pcs:	9.00	Eqp Pcs:	0.00
2CRP1D	1 DAY PAVING M@110.2	1.02	562.82	CY	187.150	116,128					116,128
2DOWEL	DOWELS@110.25%	1.00	1,696.00	LF	15.750	29,450					29,450
2JOINT	JOINT MATERIAL@110.2	1.00	762.00	SY	2.750	2,310					2,310
2TIEBAR	TIE BARS@110.25%	1.00	254.00	EA	2.940	823					823
3SAWSEAL	SAWING AND SEALING	1.00	1,696.00	LF	3.680		6,241				6,241
CEJ	Cement Mason	8.00	719.36	MH	64.980	83,027					83,027
FOCO	Concrete Forman	1.00	89.92	MH	68.980	11,006					11,006
\$248,986.19	0.4800 MH/SY		809.28	MH	[47.106]	94,033	148,712	6,241			248,986

====> **Item Totals: 632 - ROADWAY CEM CONC, HES (24 HR), 12 IN**
 \$248,986.19 0.4800 MH/SY 809.28 MH [47.106] 94,033 148,712 6,241 **248,986**
 147.679 1686 SY 55.77 88.20 3.70 147.68

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment Contract	

BID ITEM = 633 CLIENT# = 633 Land Item SCHEDULE: 1 100
Description = PCCP PANEL REINFORCING Unit = EA Takeoff Quan: 32.000 Engr Quan: 32.000

633.01 PCCP PANEL REINFORCING Quan: 32.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>COL</u>	Concrete 9 Man Crew	5.12	CH	Prod:	5.1200 CH	Lab Pcs:	9.00	Eqp Pcs:	0.00
2RB05	#5 Rebar@110.25%	1.00	7,872.00 LF	1.000	8,679				8,679
CEJ	Cement Mason	8.00	40.96 MH	64.980	3,490				3,490
FOCO	Concrete Forman	1.00	5.12 MH	68.980	462				462
\$12,630.98	1.4400 MH/EA	46.08	MH	[103.633]	3,952	8,679			12,631

====> **Item Totals: 633 - PCCP PANEL REINFORCING**
\$12,630.98 1.4400 MH/EA 46.08 MH [103.633] 3,952 8,679 **12,631**
394.718 32 EA 123.50 271.22 394.72

BID ITEM = 634 CLIENT# = 634 Land Item SCHEDULE: 1 100
Description = INLET, TYPE 250B Unit = EA Takeoff Quan: 7.000 Engr Quan: 7.000

634.01 INLET, TYPE 250B Quan: 7.00 EA Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	28.00	CH	Prod:	28.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2CPSIN250	TYPE 250 INLET@110.25	1.00	7.00 EA	355.000	2,740				2,740
2CPSZ263	TYPE 263 INLET@110.25	1.00	7.00 EA	700.000	5,402				5,402
8BA310A	418 Backhoe W/Attachme	1.00	28.00 HR	51.051		1,429			1,429
8EX100	100 Excavator	1.00	28.00 HR	52.300		1,464			1,464
FOCI	Civil Forman	1.00	28.00 MH	77.060	3,822				3,822
LAP	Labor Underground Water	1.00	28.00 MH	53.880	2,690				2,690
OPB	Operator - Backhoe	1.00	28.00 MH	74.560	3,700				3,700
OPE	Operator - Excavator	1.00	28.00 MH	74.560	3,700				3,700
\$24,946.14	16.0000 MH/EA	112.00	MH	[1680.36]	13,910	8,142	2,894		24,946

====> **Item Totals: 634 - INLET, TYPE 250B**
\$24,946.14 16.0000 MH/EA 112.00 MH [1680.36] 13,910 8,142 **24,946**
3,563.734 7 EA 1,987.19 1,163.14 413.40 3,563.73

BID ITEM = 635 CLIENT# = 635 Land Item SCHEDULE: 1 100
Description = PIPE, CB CONN, D.I., CL 50, 8 IN Unit = LF Takeoff Quan: 64.000 Engr Quan: 64.000

635.01 PIPE, CB CONN, D.I., CL 50, 8 IN Quan: 64.00 LF Hrs/Shft: 10.00 Cal: S10 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	16.00	CH	Prod:	16.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2BI635PIPE	BID ITEM 635 P@110.25	1.00	1.00 LS	2,670.980	2,945				2,945
8BA310A	418 Backhoe W/Attachme	1.00	16.00 HR	51.051		817			817
8EX100	100 Excavator	1.00	16.00 HR	52.300		837			837
FOCI	Civil Forman	1.00	16.00 MH	77.060	2,184				2,184
LAP	Labor Underground Water	1.00	16.00 MH	53.880	1,537				1,537
OPB	Operator - Backhoe	1.00	16.00 MH	74.560	2,114				2,114
OPE	Operator - Excavator	1.00	16.00 MH	74.560	2,114				2,114
\$12,547.13	1.0000 MH/LF	64.00	MH	[105.023]	7,949	2,945	1,654		12,547

====> **Item Totals: 635 - PIPE, CB CONN, D.I., CL 50, 8 IN**
\$12,547.13 1.0000 MH/LF 64.00 MH [105.023] 7,949 2,945 **12,547**
196.049 64 LF 124.20 46.01 25.84 196.05

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
-------------------	------	--------------	------	-----------	-------	---------------	-----------------	------------	--------------	-------

BID ITEM = 636 CLIENT# = 636 Land Item SCHEDULE: 1 100
Description = PIPE, INLET CONN, D.I., CL 50, 8 IN Unit = LF Takeoff Quan: 116.000 Engr Quan: 116.000

636.01 PIPE, INLET CONN, D.I., CL 50, 8 IN Quan: 116.00 LF Hrs/Shft: 10.00 Cal: Z10 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man	28.00	CH	Prod: 28.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2BI636PIPE	BID ITEM 636 P@110.25	1.00	1.00 LS	3,624.280		3,996			3,996
8BA310A	418 Backhoe W/Attachme	1.00	28.00 HR	51.051			1,429		1,429
8EX100	100 Excavator	1.00	28.00 HR	52.300			1,464		1,464
FOCI	Civil Forman	1.00	28.00 MH	77.060	4,449				4,449
LAP	Labor Underground Water	1.00	28.00 MH	53.880	3,128				3,128
OPB	Operator - Backhoe	1.00	28.00 MH	74.560	4,306				4,306
OPE	Operator - Excavator	1.00	28.00 MH	74.560	4,306				4,306
\$23,079.33	0.9655 MH/LF	112.00	MH	[118.301]	16,190	3,996		2,894	23,079

====> **Item Totals: 636 - PIPE, INLET CONN, D.I., CL 50, 8 IN**
 \$23,079.33 0.9655 MH/LF 112.00 MH [118.301] 16,190 3,996 2,894 **23,079**
 198.960 116 LF 139.57 34.45 24.95 198.96

BID ITEM = 637 CLIENT# = 637 Land Item SCHEDULE: 1 100
Description = 4 INCH DRAIN PIPE, GIP, SCH 40 Unit = EA Takeoff Quan: 2.000 Engr Quan: 2.000

637.01 4 INCH DRAIN PIPE, GIP, SCH 40 Quan: 2.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>EAS</u>	Earthwork 4 Man Crew	4.00	CH	Prod: 4.0000	CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
2BI637PIPE	BID ITEM 637 P@110.25	1.00	1.00 LS	162.000		179			179
8BA310A	418 Backhoe W/Attachme	1.00	4.00 HR	51.051			204		204
8EX100	100 Excavator	1.00	4.00 HR	52.300			209		209
FOCI	Civil Forman	1.00	4.00 MH	77.060	403				403
LAG	General Laborer	2.00	8.00 MH	52.910	558				558
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390				390
\$1,942.48	8.0000 MH/EA	16.00	MH	[566.365]	1,350	179		413	1,942

====> **Item Totals: 637 - 4 INCH DRAIN PIPE, GIP, SCH 40**
 \$1,942.48 8.0000 MH/EA 16.00 MH [566.365] 1,350 179 413 **1,942**
 971.240 2 EA 675.24 89.31 206.70 971.24

BID ITEM = 638 CLIENT# = 638 Land Item SCHEDULE: 1 100
Description = BEDDING, CL B, 8 IN PIPE Unit = LF Takeoff Quan: 180.000 Engr Quan: 180.000

638.01 BEDDING, CL B, 8 IN PIPE Quan: 180.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

2AGS09	SEATTLE TYPE 9@110.2	1.00	136.00 TON	29.750		4,461			4,461
3DEDU02D	Dirt Trucking and Dump	1.00	96.00 TCY	24.500			2,352		2,352
\$6,812.72				[]		4,461	2,352		6,813

====> **Item Totals: 638 - BEDDING, CL B, 8 IN PIPE**
 \$6,812.72 [] 4,461 2,352 **6,813**
 37.848 180 LF 24.78 13.07 37.85

BID ITEM = 639 CLIENT# = 639 Land Item SCHEDULE: 1 100
Description = TELEVISION INSPECTION Unit = LF Takeoff Quan: 64.000 Engr Quan: 64.000

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 639	CLIENT# = 639									
Description =	TELEVISION INSPECTION			Land Item Unit =	SCHEDULE: 1 100 LF Takeoff Quan:		64.000	Engr Quan:		64.000
639.01	TELEVISION INSPECTION			Quan:	64.00 LF	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG		
3CCTV	TV INSPECTION	1.00	1.00 LS	2,500.000			2,500			2,500
====>	Item Totals: 639 - TELEVISION INSPECTION									
\$2,500.00				[]			2,500			2,500
39.063	64 LF						39.06			39.06

BID ITEM = 640	CLIENT# = 640									
Description =	TEE, 8 IN, CUT-IN EXISTING CONC PIPE			Land Item Unit =	SCHEDULE: 1 100 EA Takeoff Quan:		2.000	Engr Quan:		2.000
640.01	TEE, 8 IN, CUT-IN EXISTING CONC PIPE			Quan:	2.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG		
<u>UNS</u>	Underground Utilities 4 Man		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
3SPUCORE	SPU CORE TAP	1.00	2.00 EA	150.000		300			300	
8BA310A	418 Backhoe W/Attachme	1.00	4.00 HR	51.051				204	204	
8EX100	100 Excavator	1.00	4.00 HR	52.300				209	209	
FOCI	Civil Forman	1.00	4.00 MH	77.060	403				403	
LAP	Labor Underground Water	1.00	4.00 MH	53.880	284				284	
OPB	Operator - Backhoe	1.00	4.00 MH	74.560	390				390	
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390				390	
\$2,179.59	8.0000 MH/EA		16.00 MH	[616.125]	1,466		300	413		2,180
====>	Item Totals: 640 - TEE, 8 IN, CUT-IN EXISTING CONC PIPE									
\$2,179.59	8.0000 MH/EA		16.00 MH	[616.125]	1,466		300	413		2,180
1,089.795	2 EA				733.10		150.00	206.70		1,089.80

BID ITEM = 641	CLIENT# = 641									
Description =	ADJUST EXISTING MH, CB, OR VC			Land Item Unit =	SCHEDULE: 1 100 EA Takeoff Quan:		10.000	Engr Quan:		10.000
641.01	ADJUST EXISTING MH, CB, OR VC			Quan:	10.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		9.00 CH	Prod:	9.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
8BA310A	418 Backhoe W/Attachme	1.00	9.00 HR	51.051				459	459	
8EX100	100 Excavator	1.00	9.00 HR	52.300				471	471	
FOCI	Civil Forman	1.00	9.00 MH	77.060	906				906	
LAG	General Laborer	2.00	18.00 MH	52.910	1,256				1,256	
OPE	Operator - Excavator	1.00	9.00 MH	74.560	877				877	
\$3,968.70	3.6000 MH/EA		36.00 MH	[254.865]	3,039			930		3,969
====>	Item Totals: 641 - ADJUST EXISTING MH, CB, OR VC									
\$3,968.70	3.6000 MH/EA		36.00 MH	[254.865]	3,039			930		3,969
396.870	10 EA				303.86			93.01		396.87

BID ITEM = 642	CLIENT# = 642									
Description =	ADJUST EXISTING HANDHOLE			Land Item Unit =	SCHEDULE: 1 100 EA Takeoff Quan:		1.000	Engr Quan:		1.000
642.01	ADJUST EXISTING HANDHOLE			Quan:	1.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG		
<u>EAS</u>	Earthwork 4 Man Crew		0.50 CH	Prod:	0.5000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 642	CLIENT# = 642									
Description =	ADJUST EXISTING HANDHOLE		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	1.000	Engr Quan:		1.000
8BA310A	418 Backhoe W/Attachme	1.00	0.50 HR	51.051				26		26
8EX100	100 Excavator	1.00	0.50 HR	52.300				26		26
FOCI	Civil Forman	1.00	0.50 MH	77.060	50					50
LAG	General Laborer	2.00	1.00 MH	52.910	70					70
OPE	Operator - Excavator	1.00	0.50 MH	74.560	49					49
\$220.47	2.0000 MH/EA		2.00 MH	[141.59]	169			52		220
====>	Item Totals: 642 - ADJUST EXISTING HANDHOLE									
\$220.47	2.0000 MH/EA		2.00 MH	[141.59]	169			52		220
220.470	1 EA				168.82			51.65		220.47

BID ITEM = 643	CLIENT# = 643									
Description =	UTILITY CASTING, TYPE 230		Land Item Unit =	SCHEDULE: 1 100	EA	Takeoff Quan:	7.000	Engr Quan:		7.000
643.01	UTILITY CASTING, TYPE 230		Quan:	7.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
EAS	Earthwork 4 Man Crew		3.50 CH	Prod:	3.5000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00	
2CPSZ230	TYPE 230 CASTI@110.25	1.00	7.00 EA	785.000	6,058				6,058	
8BA310A	418 Backhoe W/Attachme	1.00	3.50 HR	51.051				179		179
8EX100	100 Excavator	1.00	3.50 HR	52.300				183		183
FOCI	Civil Forman	1.00	3.50 MH	77.060	352					352
LAG	General Laborer	2.00	7.00 MH	52.910	488					488
OPE	Operator - Excavator	1.00	3.50 MH	74.560	341					341
\$7,601.63	2.0000 MH/EA		14.00 MH	[141.593]	1,182	6,058		362		7,602
====>	Item Totals: 643 - UTILITY CASTING, TYPE 230									
\$7,601.63	2.0000 MH/EA		14.00 MH	[141.593]	1,182	6,058		362		7,602
1,085.947	7 EA				168.81	865.46		51.67		1,085.95

BID ITEM = 644	CLIENT# = 644									
Description =	EROSION CONTROL		Land Item Unit =	SCHEDULE: 1 100	LS	Takeoff Quan:	1.000	Engr Quan:		1.000
644.01	EROSION CONTROL ADDITIVE		Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
3EROSIONAD	EROSION CONTROL AD	1.00	1.00 LS	5,000.000			5,000			5,000
====>	Item Totals: 644 - EROSION CONTROL									
\$5,000.00				[]			5,000			5,000
5,000.000	1 LS						5,000.00			5,000.00

BID ITEM = 645	CLIENT# = 645									
Description =	SEEDED LAWN INSTALATION		Land Item Unit =	SCHEDULE: 1 100	SF	Takeoff Quan:	551.000	Engr Quan:		551.000
645.01	SEEDED LAWN INSTALLATION		Quan:	551.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
4LAND	Landscape sub	1.00	551.00 SF	2.000				1,102		1,102

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 646	CLIENT# = 646	Land Item	SCHEDULE: 1	100						
Description =	TREE, DECIDUOUS, 1-3/4 IN TO 2 IN CAL	Unit =	EA	Takeoff Quan:		3.000	Engr Quan:		3.000	
646.01	TREE, DECIDUOUS, 1-3/4 IN TO 2 IN CAL	Quan:	3.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	3.00 EA	750.000				2,250	2,250	
BID ITEM = 647	CLIENT# = 647	Land Item	SCHEDULE: 1	100						
Description =	TOPSOIL, TYPE A	Unit =	CY	Takeoff Quan:		20.000	Engr Quan:		20.000	
647.01	TOPSOIL, TYPE A	Quan:	20.00 CY	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	20.00 CY	150.000				3,000	3,000	
BID ITEM = 648	CLIENT# = 648	Land Item	SCHEDULE: 1	100						
Description =	TREE ROOT BARRIER	Unit =	LF	Takeoff Quan:		84.000	Engr Quan:		84.000	
648.01	TREE ROOT BARRIER	Quan:	84.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	84.00 LF	20.000				1,680	1,680	
BID ITEM = 649	CLIENT# = 649	Land Item	SCHEDULE: 1	100						
Description =	FLEXIBLE POROUS SURFACE TREATMENT	Unit =	SF	Takeoff Quan:		2,335.000	Engr Quan:		2,335.000	
649.01	FLEXIBLE POROUS SURFACE TREATMENT	Quan:	2,335.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
COM	Concrete 6 Man Crew	55.00	CH	Prod:	55.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2FLEXIPAVE	FLEXI PAVE MAT@110.2	1.00	1.00 LS	15,714.550		17,325			17,325	
CEJ	Cement Mason	5.00	275.00 MH	64.980	23,429				23,429	
FOCO	Concrete Forman	1.00	55.00 MH	68.980	4,967				4,967	
\$45,721.82	0.1413 MH/SF	330.00	MH	[10.205]	28,397	17,325			45,722	
====> Item Totals:	649 - FLEXIBLE POROUS SURFACE TREATMENT									
\$45,721.82	0.1413 MH/SF	330.00	MH	[10.205]	28,397	17,325			45,722	
19.581	2335 SF				12.16	7.42			19.58	
BID ITEM = 650	CLIENT# = 650	Land Item	SCHEDULE: 1	100						
Description =	LANDSCAPE ESTABLISHMENT - BID ADDITIVE,	Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000	
650.01	LANDSCAPE ESTABLISHMENT - BID ADDITIVE,	Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
4LAND	Landscape sub	1.00	1.00 LS	2,000.000				2,000	2,000	
BID ITEM = 651	CLIENT# = 651	Land Item	SCHEDULE: 1	100						
Description =	CURB, CEM CONC W/ 25% POZZOLANS	Unit =	LF	Takeoff Quan:		1,426.000	Engr Quan:		1,426.000	
651.01	CURB, CEM CONC W/ 25% POZZOLANS	Quan:	1,426.00 LF	Hrs/Shft:	10.00	Cal: 610	WC: WAAVG			

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 651	CLIENT# = 651		Land Item	SCHEDULE: 1 100						
Description =	CURB, CEM CONC W/ 25% POZZOLANS		Unit =	LF	Takeoff Quan:		1,426.000	Engr Quan:		1,426.000
<u>COM</u>	Concrete 6 Man Crew		64.20 CH	Prod:	64.2062 CH	Lab Pcs:		6.00	Eqp Pcs:	0.00
2CR025	2500LB READY M@110.2	1.00	13.46 CY	115.350		1,712				1,712
2CRUBHOOP	CURB HOOPS@110.25%	1.00	475.33 EA	2.000		1,048				1,048
CEJ	Cement Mason	5.00	321.03 MH	64.980	28,969					28,969
FOCO	Concrete Forman	1.00	64.21 MH	68.980	6,143					6,143
\$37,871.08	0.2701 MH/LF		385.24 MH	[20.691]	35,111	2,760				37,871
=====> Item Totals: 651 - CURB, CEM CONC W/ 25% POZZOLANS										
\$37,871.08	0.2701 MH/LF		385.24 MH	[20.691]	35,111	2,760				37,871
26.558	1426 LF				24.62	1.94				26.56

BID ITEM = 652	CLIENT# = 652		Land Item	SCHEDULE: 1 100						
Description =	RESET MONUMENT AND MONUMENT FRAME AND		Unit =	EA	Takeoff Quan:		2.000	Engr Quan:		2.000
652.01	RESET MONUMENT AND MONUMENT FRAME A	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
<u>EAS</u>	Earthwork 4 Man Crew		4.00 CH	Prod:	4.0000 CH	Lab Pcs:		4.00	Eqp Pcs:	2.00
4SURV	Surveying sub	1.00	2.00 EA	1,500.000					3,000	3,000
8BA310A	418 Backhoe W/Attachme	1.00	4.00 HR	51.051				204		204
8EX100	100 Excavator	1.00	4.00 HR	52.300				209		209
FOCI	Civil Forman	1.00	4.00 MH	77.060	403					403
LAG	General Laborer	2.00	8.00 MH	52.910	558					558
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390					390
\$4,763.87	8.0000 MH/EA		16.00 MH	[566.365]	1,350			413	3,000	4,764
=====> Item Totals: 652 - RESET MONUMENT AND MONUMENT FRAME AND CO										
\$4,763.87	8.0000 MH/EA		16.00 MH	[566.365]	1,350			413	3,000	4,764
2,381.935	2 EA				675.24			206.70	1,500.00	2,381.94

BID ITEM = 653	CLIENT# = 653		Land Item	SCHEDULE: 1 100						
Description =	SIDEWALK, CEM CONC W/ 25% POZZOLANS		Unit =	SY	Takeoff Quan:		390.000	Engr Quan:		390.000
653.01	SIDEWALK, CEM CONC W/ 25% POZZOLANS	Quan:	390.00 SY	Hrs/Shft:	10.00	Cal:	610	WC:	WAAVG	
<u>COM</u>	Concrete 6 Man Crew		41.00 CH	Prod:	41.0000 CH	Lab Pcs:		6.00	Eqp Pcs:	0.00
2CR025	2500LB READY M@110.2	1.00	45.00 CY	115.350		5,723				5,723
CEJ	Cement Mason	5.00	205.00 MH	64.980	18,499					18,499
FOCO	Concrete Forman	1.00	41.00 MH	68.980	3,922					3,922
\$28,143.52	0.6307 MH/SY		246.00 MH	[48.311]	22,421	5,723				28,144
=====> Item Totals: 653 - SIDEWALK, CEM CONC W/ 25% POZZOLANS										
\$28,143.52	0.6307 MH/SY		246.00 MH	[48.311]	22,421	5,723				28,144
72.163	390 SY				57.49	14.67				72.16

BID ITEM = 654	CLIENT# = 654		Land Item	SCHEDULE: 1 100						
Description =	SIDEWALK, THICKENED EDGE W/ 25%		Unit =	LF	Takeoff Quan:		1,426.000	Engr Quan:		1,426.000
654.01	SIDEWALK, THICKENED EDGE W/ 25%	Quan:	1,426.00 LF	Hrs/Shft:	10.00	Cal:	510	WC:	WAAVG	
2CR025	2500LB READY M@110.2	1.00	98.38 CY	115.350		12,511				12,511

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 654	CLIENT# = 654		Land Item	SCHEDULE: 1	100					
Description =	SIDEWALK, THICKENED EDGE W/ 25%		Unit =	LF	Takeoff Quan:	1,426.000		Engr Quan:		1,426.000
====> Item Totals:	654	- SIDEWALK, THICKENED EDGE W/ 25%								
\$12,511.32				[]		12,511				12,511
8.774		1426 LF				8.77				8.77

BID ITEM = 655	CLIENT# = 655		Land Item	SCHEDULE: 1	100					
Description =	POZZOLANS DRIVEWAY, CEM CONC, HES (24 HR		Unit =	SY	Takeoff Quan:	41.000		Engr Quan:		41.000
655.01	POZZOLANS DRIVEWAY, CEM CONC, HES (24 H	Quan:	41.00 SY	Hrs/Shft:	10.00	Cal: S10	WC: WAAVG			
<u>COM</u>	Concrete 6 Man Crew	8.00	CH	Prod:	8.0000 CH	Lab Pcs:	6.00	Eqp Pcs:	0.00	
2CR025	2500LB READY M@110.2	1.00	8.00 CY	187.150		1,651				1,651
CEJ	Cement Mason	5.00	40.00 MH	64.980	4,617					4,617
FOCO	Concrete Forman	1.00	8.00 MH	68.980	979					979
\$7,246.55	1.1707 MH/SY	48.00	MH	[115.282]	5,596	1,651				7,247
====> Item Totals:	655	- POZZOLANS DRIVEWAY, CEM CONC, HES (24 HR								
\$7,246.55	1.1707 MH/SY	48.00	MH	[115.282]	5,596	1,651				7,247
176.745	41 SY				136.49	40.26				176.75

BID ITEM = 656		CLIENT# = 656		Land Item	SCHEDULE: 1	100				
Description =	MOBILIZATION-SCHEDULE 4			Unit =	LS	Takeoff Quan:	1.000	Engr Quan:	1.000	
656.01	MOBILIZATION-SCHEDULE 4			Quan:	1.00 LS	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG	
<i>There are no cost resources for this activity.</i>										
====>	Item Totals:	656	- MOBILIZATION-SCHEDULE 4							
\$0.00						[]				
0.000		1 LS								

BID ITEM = 657	CLIENT# = 657		Land Item	SCHEDULE: 1	100					
Description =	SAFETY SYSTEMS IN TRENCH EXCAVATION, MIN		Unit =	SF	Takeoff Quan:	6,725.000		Engr Quan:		6,725.000
657.01	SAFETY SYSTEMS IN TRENCH EXCAVATION, M	Quan:	6,725.00 SF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
3SHORING	shoring water line	1.00	1.00 LS	10,000.000		10,000				10,000
====> Item Totals:	657	- SAFETY SYSTEMS IN TRENCH EXCAVATION, MIN								
\$10,000.00				[]		10,000				10,000
1.487		6725 SF				1.49				1.49

BID ITEM = 658	CLIENT# = 658		Land Item	SCHEDULE: 1	100					
Description =	MINERAL AGGREGATE, TYPE 17		Unit =	TN	Takeoff Quan:	527.000		Engr Quan:		527.000
658.01	MINERAL AGGREGATE, TYPE 17	Quan:	527.00 TN	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
2AGS17	SEATTLE TYPE 17	1.00	527.00 TON	25.750		13,570				13,570
3DEDU02D	Dirt Trucking and Dump	1.00	327.00 TCY	24.500			8,012			8,012
\$21,581.75				[]		13,570	8,012			21,582

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 658	CLIENT# = 658		Land Item	SCHEDULE: 1	100					
Description =	MINERAL AGGREGATE, TYPE 17		Unit =	TN	Takeoff Quan:		527.000	Engr Quan:		527.000
====> Item Totals:	658	- MINERAL AGGREGATE, TYPE 17								
\$21,581.75				[]		13,570	8,012			21,582
40.952		527 TN				25.75	15.20			40.95

BID ITEM = 659	CLIENT# = 659		Land Item	SCHEDULE: 1	100					
Description =	TEMPORARY WATER MAINS AND SERVICES ADDIT		Unit =	LS	Takeoff Quan:		1.000	Engr Quan:		1.000

659.01 PHASE 11 TEMP MAIN **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>UNS</u>	Underground Utilities 4 Man		24.00	CH	Prod: 24.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	24.00	HR	51.051			1,225	1,225
8EX100	100 Excavator	1.00	24.00	HR	52.300			1,255	1,255
FOCI	Civil Forman	1.00	24.00	MH	77.060	2,416			2,416
LAP	Labor Underground Water	1.00	24.00	MH	53.880	1,704			1,704
OPB	Operator - Backhoe	1.00	24.00	MH	74.560	2,339			2,339
OPE	Operator - Excavator	1.00	24.00	MH	74.560	2,339			2,339
\$11,277.57	96.0000 MH/LS		96.00	MH	[7393.57]	8,797		2,480	11,278

659.02 PHASE 12 TEMP MAIN **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

<u>UNM</u>	Unergound Utilities 6 Man		24.00	CH	Prod: 24.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
8EX135A	135 Excavator W/Attach	1.00	24.00	HR	68.251			1,638	1,638
8EX200	200 Excavator	1.00	24.00	HR	78.000			1,872	1,872
8LO950	950 Loader	1.00	24.00	HR	81.500			1,956	1,956
FOCI	Civil Forman	1.00	24.00	MH	77.060	2,416			2,416
LAP	Labor Underground Water	2.00	48.00	MH	53.880	3,408			3,408
OPE	Operator - Excavator	1.00	24.00	MH	74.560	2,339			2,339
OPL	Operator - Loader	1.00	24.00	MH	74.560	2,339			2,339
\$15,967.19	120.0000 MH/LS		120.00	MH	[8816]	10,501		5,466	15,967

659.03 ADDITIVE TEMP WATER MAIN MATERIAL **Quan: 1.00 LS Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2TEMPWATERMADDITIVE TEMP @110.2	1.00	1.00	LS		4,000.000		4,410		4,410
---------------------------------	------	------	----	--	-----------	--	-------	--	-------

====> Item Totals:	659	- TEMPORARY WATER MAINS AND SERVICES ADDIT								
\$31,654.76	216.0000 MH/LS		216.00	MH	[16209.57]	19,298	4,410	7,946		31,655
31,654.760	1 LS					19,298.32	4,410.00	7,946.44		31,654.76

BID ITEM = 660	CLIENT# = 659		Land Item	SCHEDULE: 1	100					
Description =	BEDDING, WATER MAIN, CL B, 12 IN PIPE		Unit =	LF	Takeoff Quan:		1,133.000	Engr Quan:		1,133.000

659.01 BEDDING, WATER MAIN, CL B, 12 IN PIPE **Quan: 1,133.00 LF Hrs/Shft: 10.00 Cal: 510 WC: WAAVG**

2AGS07	SEATTLE TYPE 7	1.00	800.00	TON	29.750		23,800			23,800
3DEDU02D	Dirt Trucking and Dump	1.00	604.00	TCY	24.500			14,798		14,798
\$38,598.00					[]		23,800	14,798		38,598

====> Item Totals:	660	- BEDDING, WATER MAIN, CL B, 12 IN PIPE								
\$38,598.00					[]		23,800	14,798		38,598
34.067		1133 LF					21.01	13.06		34.07

Direct Cost Report

Activity	Desc	Quantity	Unit	Unit	Perm	Constr	Equip	Sub-	Total
Resource		Pcs		Cost	Labor	Material	Matl/Exp	Ment	Contract

BID ITEM = 661 CLIENT# = 660 Land Item SCHEDULE: 1 100
Description = BLOCKING, CEMENT CONCRETE Unit = CY Takeoff Quan: 9.000 Engr Quan: 9.000

660.01 BLOCKING, CEMENT CONCRETE Quan: 9.00 CY Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		8.00	CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2CR040	4000LB READY MIX	1.00	9.00	CY	121.150	1,090				1,090
8EX135A	135 Excavator W/Attach	1.00	8.00	HR	68.251			546		546
8EX200	200 Excavator	1.00	8.00	HR	78.000			624		624
8LO950	950 Loader	1.00	8.00	HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00	MH	77.060	805				805
LAP	Labor Underground Water	2.00	16.00	MH	53.880	1,136				1,136
OPE	Operator - Excavator	1.00	8.00	MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00	MH	74.560	780				780
\$6,412.75	4.4444 MH/CY		40.00	MH	[326.52]	3,500	1,090		1,822	6,413

=====> **Item Totals: 661 - BLOCKING, CEMENT CONCRETE**
 \$6,412.75 4.4444 MH/CY 40.00 MH [326.52] 3,500 1,090 1,822 **6,413**
 712.528 9 CY 388.93 121.15 202.44 712.53

BID ITEM = 662 CLIENT# = 661 Land Item SCHEDULE: 1 100
Description = STATION, ELECTROLYSIS TEST Unit = EA Takeoff Quan: 3.000 Engr Quan: 3.000

661.01 STATION, ELECTROLYSIS TEST Quan: 3.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		6.00	CH	Prod:	6.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2STELTEST	STATION ELECTROLYSIS	1.00	3.00	EA	1,483.620	4,451				4,451
3CERTTEST	CERTIFIED TESTER	1.00	3.00	EA	3,897.000		11,691			11,691
8EX135A	135 Excavator W/Attach	1.00	6.00	HR	68.251			409		409
8EX200	200 Excavator	1.00	6.00	HR	78.000			468		468
8LO950	950 Loader	1.00	6.00	HR	81.500			489		489
FOCI	Civil Forman	1.00	6.00	MH	77.060	604				604
LAP	Labor Underground Water	2.00	12.00	MH	53.880	852				852
OPE	Operator - Excavator	1.00	6.00	MH	74.560	585				585
OPL	Operator - Loader	1.00	6.00	MH	74.560	585				585
\$20,133.65	10.0000 MH/EA		30.00	MH	[734.673]	2,625	4,451	11,691	1,366	20,134

=====> **Item Totals: 662 - STATION, ELECTROLYSIS TEST**
 \$20,133.65 10.0000 MH/EA 30.00 MH [734.673] 2,625 4,451 11,691 1,366 **20,134**
 6,711.217 3 EA 875.10 1,483.62 3,897.00 455.50 6,711.22

BID ITEM = 663 CLIENT# = 662 Land Item SCHEDULE: 1 100
Description = SACRIFICIAL ANODE BONDED TO PIPE Unit = EA Takeoff Quan: 64.000 Engr Quan: 64.000

662.01 SACRIFICIAL ANODE BONDED TO PIPE Quan: 64.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNM</u>	Underground Utilities 6 Man		8.00	CH	Prod:	8.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2ANOD	ANODES	1.00	64.00	EA	271.680	17,388				17,388
8EX135A	135 Excavator W/Attach	1.00	8.00	HR	68.251			546		546
8EX200	200 Excavator	1.00	8.00	HR	78.000			624		624
8LO950	950 Loader	1.00	8.00	HR	81.500			652		652
FOCI	Civil Forman	1.00	8.00	MH	77.060	805				805
LAP	Labor Underground Water	2.00	16.00	MH	53.880	1,136				1,136
OPE	Operator - Excavator	1.00	8.00	MH	74.560	780				780
OPL	Operator - Loader	1.00	8.00	MH	74.560	780				780

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 663	CLIENT# = 662		Land Item	SCHEDULE: 1	100					
Description =	SACRIFICIAL ANODE BONDED TO PIPE		Unit =	EA	Takeoff Quan:		64.000	Engr Quan:		64.000
\$22,709.92	0.6250 MH/EA	40.00 MH		[45.917]	3,500	17,388		1,822		22,710
=====> Item Totals: 663 - SACRIFICIAL ANODE BONDED TO PIPE										
\$22,709.92	0.6250 MH/EA	40.00 MH		[45.917]	3,500	17,388		1,822		22,710
354.843	64 EA				54.69	271.68		28.47		354.84

BID ITEM = 664	CLIENT# = 663		Land Item	SCHEDULE: 1	100					
Description =	SUPPORT SPU WITH CUT, CAP, AND CONNECT		Unit =	EA	Takeoff Quan:		9.000	Engr Quan:		9.000
663.01	SUPPORT SPU WITH CUT, CAP, AND CONNECT	Quan:	9.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
<u>UNS</u>	Underground Utilities 4 Man	72.00 CH	Prod:	72.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00		
2AGS07	SEATTLE TYPE 7	1.00 40.00 TON		29.750		1,190		1,190		
2AGS17	SEATTLE TYPE 17	1.00 90.00 TON		25.750		2,318		2,318		
2BI663PIPE	BID ITEM 663 P@110.25	1.00 1.00 LS		15,802.000		17,422		17,422		
3DEDU02D	Dirt Trucking and Dump	1.00 90.00 TCY		24.500		2,205		2,205		
8BA310A	418 Backhoe W/Attachme	1.00 72.00 HR		51.051			3,676	3,676		
8EX100	100 Excavator	1.00 72.00 HR		52.300			3,766	3,766		
FOCI	Civil Forman	1.00 72.00 MH		77.060	7,247			7,247		
LAP	Labor Underground Water	1.00 72.00 MH		53.880	5,112			5,112		
OPB	Operator - Backhoe	1.00 72.00 MH		74.560	7,016			7,016		
OPE	Operator - Excavator	1.00 72.00 MH		74.560	7,016			7,016		
\$56,966.95	32.0000 MH/EA	288.00 MH		[2464.528]	26,391	20,929	2,205	7,441		56,967
=====> Item Totals: 664 - SUPPORT SPU WITH CUT, CAP, AND CONNECT										
\$56,966.95	32.0000 MH/EA	288.00 MH		[2464.528]	26,391	20,929	2,205	7,441		56,967
6,329.661	9 EA				2,932.39	2,325.47	245.00	826.81		6,329.66

BID ITEM = 665	CLIENT# = 664		Land Item	SCHEDULE: 1	100					
Description =	PIPE, WM, D.I. CL 53 MIN, 12 IN, RJ, POL		Unit =	LF	Takeoff Quan:		1,133.000	Engr Quan:		1,133.000
664.01	PIPE, WM, D.I. CL 53 MIN, 12 IN, RJ, POL	Quan:	1,133.00 LF	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
<u>UNM</u>	Underground Utilities 6 Man	120.00 CH	Prod:	120.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00		
2BI664PIPE	BID ITEM 664 PIPE	1.00 1.00 LS		89,317.460		89,317		89,317		
8EX135A	135 Excavator W/Attach	1.00 120.00 HR		68.251			8,190	8,190		
8EX200	200 Excavator	1.00 120.00 HR		78.000			9,360	9,360		
8LO950	950 Loader	1.00 120.00 HR		81.500			9,780	9,780		
FOCI	Civil Forman	1.00 120.00 MH		77.060	12,078			12,078		
LAP	Labor Underground Water	2.00 240.00 MH		53.880	17,040			17,040		
OPE	Operator - Excavator	1.00 120.00 MH		74.560	11,694			11,694		
OPL	Operator - Loader	1.00 120.00 MH		74.560	11,694			11,694		
\$169,153.49	0.5295 MH/LF	600.00 MH		[38.906]	52,506	89,317		27,330		169,153
664.02	FLUSHING AND TESTING ADDITIVE	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG			
<u>UNM</u>	Underground Utilities 6 Man	32.00 CH	Prod:	32.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00		
8EX135A	135 Excavator W/Attach	1.00 32.00 HR		68.251			2,184	2,184		
8EX200	200 Excavator	1.00 32.00 HR		78.000			2,496	2,496		
8LO950	950 Loader	1.00 32.00 HR		81.500			2,608	2,608		
FOCI	Civil Forman	1.00 32.00 MH		77.060	3,221			3,221		
LAP	Labor Underground Water	2.00 64.00 MH		53.880	4,544			4,544		
OPE	Operator - Excavator	1.00 32.00 MH		74.560	3,118			3,118		
OPL	Operator - Loader	1.00 32.00 MH		74.560	3,118			3,118		

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 665	CLIENT# = 664		Land Item	SCHEDULE: 1	100				
Description =	PIPE, WM, D.I. CL 53 MIN, 12 IN, RJ, POL		Unit =	LF	Takeoff Quan:	1,133.000	Engr Quan:		1,133.000
\$21,289.60	80.0000 MH/EA	160.00 MH	[5877.34]	14,002			7,288		21,290
====> Item Totals: 665 - PIPE, WM, D.I. CL 53 MIN, 12 IN, RJ, POL									
\$190,443.09	0.6707 MH/LF	760.00 MH	[49.28]	66,507	89,317		34,618		190,443
168.087	1133 LF			58.70	78.83		30.55		168.09

BID ITEM = 666	CLIENT# = 665		Land Item	SCHEDULE: 1	100				
Description =	DAILY BLOCK, CEMENT CONCRETE, PRECAST		Unit =	EA	Takeoff Quan:	2.000	Engr Quan:		2.000
665.01	DAILY BLOCK, CEMENT CONCRETE, PRECAST	Quan:	2.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>UNM</u>	Underground Utilities 6 Man	4.50 CH	Prod:	4.5000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2AGS02	SEATTLE TYPE 2	1.00 20.00 TON	29.750	595				595	
2CPSDAILY	DAILY BLOCK	1.00 2.00 EA	750.000	1,500				1,500	
8EX135A	135 Excavator W/Attach	1.00 4.50 HR	68.251			307		307	
8EX200	200 Excavator	1.00 4.50 HR	78.000			351		351	
8LO950	950 Loader	1.00 4.50 HR	81.500			367		367	
FOCI	Civil Forman	1.00 4.50 MH	77.060	453				453	
LAP	Labor Underground Water	2.00 9.00 MH	53.880	639				639	
OPE	Operator - Excavator	1.00 4.50 MH	74.560	439				439	
OPL	Operator - Loader	1.00 4.50 MH	74.560	439				439	
\$5,088.84	11.2500 MH/EA	22.50 MH	[826.5]	1,969	2,095		1,025		5,089
====> Item Totals: 666 - DAILY BLOCK, CEMENT CONCRETE, PRECAST									
\$5,088.84	11.2500 MH/EA	22.50 MH	[826.5]	1,969	2,095		1,025		5,089
2,544.420	2 EA			984.50	1,047.50		512.43		2,544.42

BID ITEM = 667	CLIENT# = 666		Land Item	SCHEDULE: 1	100				
Description =	VALVE, GATE, 6 IN		Unit =	EA	Takeoff Quan:	1.000	Engr Quan:		1.000
666.01	VALVE, GATE, 6 IN	Quan:	1.00 EA	Hrs/Shft:	10.00	Cal: 510	WC: WAAVG		
<u>UNM</u>	Underground Utilities 6 Man	1.00 CH	Prod:	1.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00	
2BI666PIPE	BID ITEM 666 PIPE	1.00 1.00 LS	2,944.660	2,945				2,945	
8EX135A	135 Excavator W/Attach	1.00 1.00 HR	68.251			68		68	
8EX200	200 Excavator	1.00 1.00 HR	78.000			78		78	
8LO950	950 Loader	1.00 1.00 HR	81.500			81		81	
FOCI	Civil Forman	1.00 1.00 MH	77.060	101				101	
LAP	Labor Underground Water	2.00 2.00 MH	53.880	142				142	
OPE	Operator - Excavator	1.00 1.00 MH	74.560	97				97	
OPL	Operator - Loader	1.00 1.00 MH	74.560	97				97	
\$3,609.95	5.0000 MH/EA	5.00 MH	[367.35]	438	2,945		228		3,610
====> Item Totals: 667 - VALVE, GATE, 6 IN									
\$3,609.95	5.0000 MH/EA	5.00 MH	[367.35]	438	2,945		228		3,610
3,609.950	1 EA			437.56	2,944.66		227.73		3,609.95

BID ITEM = 668	CLIENT# = 667		Land Item	SCHEDULE: 1	100				
Description =	VALVE, GATE, 12 IN		Unit =	EA	Takeoff Quan:	4.000	Engr Quan:		4.000

Direct Cost Report

Activity Resource	Desc	Pcs	Quantity Unit	Unit Cost	Perm Labor	Constr Material	Equip Matl/Exp	Sub- Contract	Total
BID ITEM = 668	CLIENT# = 667								
Description =	VALVE, GATE, 12 IN			Land Item Unit =	SCHEDULE: 1 EA	100 Takeoff Quan:	4.000	Engr Quan:	4.000
667.01	VALVE, GATE, 12 IN			Quan:	4.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG	
<u>UNM</u>	Underground Utilities 6 Man		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI667PIPE	BID ITEM 667 PIPE	1.00	1.00 LS	14,955.000		14,955			14,955
8EX135A	135 Excavator W/Attach	1.00	4.00 HR	68.251			273		273
8EX200	200 Excavator	1.00	4.00 HR	78.000			312		312
8LO950	950 Loader	1.00	4.00 HR	81.500			326		326
FOCI	Civil Forman	1.00	4.00 MH	77.060	403				403
LAP	Labor Underground Water	2.00	8.00 MH	53.880	568				568
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390				390
OPL	Operator - Loader	1.00	4.00 MH	74.560	390				390
\$17,616.19	5.0000 MH/EA		20.00 MH	[367.33]	1,750	14,955	911		17,616
====> Item Totals: 668 - VALVE, GATE, 12 IN									
\$17,616.19	5.0000 MH/EA		20.00 MH	[367.33]	1,750	14,955	911		17,616
4,404.048	4 EA				437.55	3,738.75	227.75		4,404.05

BID ITEM = 669	CLIENT# = 668								
Description =	VALVE BOX, CAST IRON			Land Item Unit =	SCHEDULE: 1 EA	100 Takeoff Quan:	5.000	Engr Quan:	5.000
668.01	VALVE BOX, CAST IRON			Quan:	5.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG	
<u>UNM</u>	Underground Utilities 6 Man		2.00 CH	Prod:	2.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI668PIPE	BID ITEM 668 PIPE	1.00	1.00 LS	1,486.650		1,487			1,487
8EX135A	135 Excavator W/Attach	1.00	2.00 HR	68.251			136		136
8EX200	200 Excavator	1.00	2.00 HR	78.000			156		156
8LO950	950 Loader	1.00	2.00 HR	81.500			163		163
FOCI	Civil Forman	1.00	2.00 MH	77.060	201				201
LAP	Labor Underground Water	2.00	4.00 MH	53.880	284				284
OPE	Operator - Excavator	1.00	2.00 MH	74.560	195				195
OPL	Operator - Loader	1.00	2.00 MH	74.560	195				195
\$2,817.23	2.0000 MH/EA		10.00 MH	[146.932]	875	1,487	455		2,817
====> Item Totals: 669 - VALVE BOX, CAST IRON									
\$2,817.23	2.0000 MH/EA		10.00 MH	[146.932]	875	1,487	455		2,817
563.446	5 EA				175.02	297.33	91.10		563.45

BID ITEM = 670	CLIENT# = 669								
Description =	HYDRANT, 6 IN CONN, TYPE 311			Land Item Unit =	SCHEDULE: 1 EA	100 Takeoff Quan:	1.000	Engr Quan:	1.000
669.01	HYDRANT, 6 IN CONN, TYPE 311			Quan:	1.00 EA	Hrs/Shft: 10.00	Cal: 510	WC: WAAVG	
<u>UNM</u>	Underground Utilities 6 Man		4.00 CH	Prod:	4.0000 CH	Lab Pcs:	5.00	Eqp Pcs:	3.00
2BI669PIPE	BID ITEM 669 PIPE	1.00	1.00 LS	7,567.640		7,568			7,568
8EX135A	135 Excavator W/Attach	1.00	4.00 HR	68.251			273		273
8EX200	200 Excavator	1.00	4.00 HR	78.000			312		312
8LO950	950 Loader	1.00	4.00 HR	81.500			326		326
FOCI	Civil Forman	1.00	4.00 MH	77.060	403				403
LAP	Labor Underground Water	2.00	8.00 MH	53.880	568				568
OPE	Operator - Excavator	1.00	4.00 MH	74.560	390				390
OPL	Operator - Loader	1.00	4.00 MH	74.560	390				390
\$10,228.83	20.0000 MH/EA		20.00 MH	[1469.32]	1,750	7,568	911		10,229

Direct Cost Report

Activity Resource	Desc	Quantity Pcs	Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub- Contract	Total
BID ITEM = 670	CLIENT# = 669		Land Item	SCHEDULE: 1	100					
Description =	HYDRANT, 6 IN CONN, TYPE 311		Unit =	EA	Takeoff Quan:		1.000	Engr Quan:		1.000
====> Item Totals: 670 - HYDRANT, 6 IN CONN, TYPE 311										
\$10,228.83	20.0000 MH/EA	20.00	MH	[1469.32]	1,750	7,568		911		10,229
10,228.830	1 EA				1,750.19	7,567.64		911.00		10,228.83

BID ITEM = 671	CLIENT# = 670		Land Item	SCHEDULE: 1	100					
Description =	SUPPORT SPU WITH SERVICE TRANSFER OR REN		Unit =	EA	Takeoff Quan:		21.000	Engr Quan:		21.000

670.01 SUPPORT SPU WITH SERVICE TRANSFER OR R Quan: 21.00 EA Hrs/Shft: 10.00 Cal: 510 WC: WAAVG

<u>UNS</u>	Underground Utilities 4 Man		55.00	CH	Prod: 55.0000 CH	Lab Pcs:	4.00	Eqp Pcs:	2.00
8BA310A	418 Backhoe W/Attachme	1.00	55.00	HR	51.051		2,808		2,808
8EX100	100 Excavator	1.00	55.00	HR	52.300		2,876		2,876
FOCI	Civil Forman	1.00	55.00	MH	77.060	5,536			5,536
LAP	Labor Underground Water	1.00	55.00	MH	53.880	3,905			3,905
OPB	Operator - Backhoe	1.00	55.00	MH	74.560	5,360			5,360
OPE	Operator - Excavator	1.00	55.00	MH	74.560	5,360			5,360
\$25,844.45	10.4761 MH/EA	220.00	MH	[806.84]	20,160		5,684		25,844

====> Item Totals: 671 - SUPPORT SPU WITH SERVICE TRANSFER OR REN										
\$25,844.45	10.4761 MH/EA	220.00	MH	[806.84]	20,160		5,684			25,844
1,230.688	21 EA				960.01		270.68			1,230.69

\$62,286,298.89 * Report Totals *** 180,159.77 MH 15,857,899 11,779,587 9,592,374 2,511,818 22,544,620 62,286,299**

>>> indicates Non Additive Activity

-----Report Notes:-----

The estimate was prepared with TAKEOFF Quantities.

This report shows TAKEOFF Quantities with the resources.

Bid Date: Owner: Engineering Firm:

Estimator-In-Charge:

JOB NOTES

Estimate created on: 05/21/2021 by User#: 0 -

Source estimate used: C:\HEAVYBID\EST\ESTMAST

* on units of MH indicate average labor unit cost was used rather than base rate.

[] in the Unit Cost Column = Labor Unit Cost Without Labor Burdens

In equipment resources, rent % and EOE % not = 100% are represented as XXX%YYY where XXX=Rent% and YYY=EOE%

-----Calendar Codes-----

410	40 Hour Week - (4@10)
508	40 Hour Week - (5@8)
509	45 Hour Week - (5@9)
510	50 Hour Week - (5@10) (Default Calendar)
512	60 Hour Week(5@12)
518	58 Hour Week(5@10+Sat@8)
609	54 Hour Week(6@9)
610	60 Hour Week - (6@10)
612	72 Hour Week - (6@12)
709	63 Hour Week - (7@9)
710	70 Hour Week - (7@10)
712	84 Hour Week - (7@12)

Direct Cost Report

Activity	Desc	Quantity		Unit	Unit Cost	Labor	Perm Material	Constr Matl/Exp	Equip Ment	Sub-Contract	Total
BID ITEM	=	671	CLIENT# =	670	Land Item	SCHEDULE:	1	100			
Description =	SUPPORT SPU WITH SERVICE TRANSFER OR REN				Unit =	EA	Takeoff Quan:	21.000	Engr Quan:		21.000
S08	Saturday Only - 8 Hour shift										
S10	Saturday Only - 10 Hr Shift										
S12	Saturday Only - 12 Hr Shift										
X08	Sunday Only - 8 Hr Shift										
X10	Sunday Only - 10 Hr Shift										
X12	Sunday Only - 12 Hr Shift										
Z08	Sat & Sun Only - 8 Hr shifts										
Z10	Sat & Sun Only - 10Hr Shifts										
Z12	Sat &Sun Only - 12 Hr Shifts										